

TECHNICAL REPORT

Name of Work – FDR To Road From.....

Head – FDR

Estimated cost – 25.23386 Lacs

The work done estimate has been framed for the restoration (motarable) of traffic for the above road which was damage during the year 2020-2021 flash flood.

(A) Source of materials

Brick Bats – Local Kiln

Fine sand – Local

Cement Bag – Local Market


Aggregate for G.S.B – Matigara (Silliguri) by road up to site.

Bamboo – Local

Earth – Private land from 1000m lead.

- (B) Rate** - Carriage has been analyzed on minimum lead. Finished rate has been calculated without contractor's profit on MORD norms. Carriage of materials has been added to finished rate. Basic Rates are evaluated from rates approved by State schedule rate committee. 12% GST& 1% Labour cess has been added in the estimate in abstract part.


Sanction of estimate is much needed for payment of the work which was already done.


J.E.

R.W.D
Kishanganj-1


A.E.

R.W.D
Kishanganj-1


E.E.

R.W.D
Kishanganj-1

Inspection Report for flood damage work

Date:

1. Name of PIUs- Executive Eng- RWD works division, Kishanganj-1.

2. Name of Block/Road- sharma tola to Fulbariya mukherjee tola,
1st cutting.

A. For Road

1. Damage Location/Chainage : 2.650 Km.

2. Damage Length : 50m.

3. Nature of Damage : washed out flank damage.

4. Details of Restoration :

i Material being used in Restoration

: Birch bats, sand bags,
bamboo.

ii Equipment/Tools being used in Restoration works:

: Tractor,

iii Procedure taken up in Restoration works

: manual.

iv Restored Length

: 50m.

B. For Bridge

1. Damage Location/Chainage :

2. Damage Length :

3. Nature of Damage :

4. Details of Restoration :

i Material being used in Restoration

:

ii Equipment/Tools being used in Restoration works:

:

iii Procedure taken up in Restoration works

:

iv Restored Length

:

Signature of JE/AE/EE

11/12/20

11/12/20 C 11/12

Signature

(Name of Inspector)

Scanned by CamScanner

Inspection Report for flood damage work

Date:

1. Name of PIUs- Executive Eng. RWD workd division, kishangan-1.

2. Name of Block/Road- shorne tola fulbariya on 4 khetar tola, 2nd cutting.

A. For Road

1. Damage Location/Chainage : 3.0 km.

2. Damage Length : 140m.

3. Nature of Damage : washed out flank damage.

4. Details of Restoration :

i Material being used in Restoration : brick bats, sand bags.

ii Equipment/Tools being used in Restoration works: Tractor.

iii Procedure taken up in Restoration works : manual.

iv Restored Length : 140m.

B. For Bridge

1. Damage Location/Chainage :

2. Damage Length : N/A.

3. Nature of Damage : N/A.

4. Details of Restoration :


i Material being used in Restoration :

ii Equipment/Tools being used in Restoration works:

iii Procedure taken up in Restoration works :

iv Restored Length :

Signature of JE/AE/EE


11/12/20


11/12

Signature

(Name of Inspector)

PMGSV
Inspection Report for flood damage work

Date:

1. Name of PIUs- Executive Eng. RWD works division, Kishanganj-1.

2. Name of Block/Road- Terhegachh / Sharma tola fulbariya mukhter
Tola, 3rd cutting.

A. For Road

1. Damage Location/Chainage : 3.20 Km.

2. Damage Length : 120m.

3. Nature of Damage : washed out

4. Details of Restoration :

i Material being used in Restoration

: Brick bats, sand bags,
H.P Pipe.

ii Equipment/Tools being used in Restoration works:

: Tractor.

iii Procedure taken up in Restoration works

: manual.

iv Restored Length

: 120m.

B. For Bridge

1. Damage Location/Chainage :

2. Damage Length :

3. Nature of Damage :

4. Details of Restoration :

i Material being used in Restoration :

ii Equipment/Tools being used in Restoration works:

iii Procedure taken up in Restoration works :

iv Restored Length :

Signature of JE/AE/EE
11/12/20

11/12/20

11/12

Signature
11/12/20

(Name of Inspector)

Abstract of Cost

Name of Work:- **SHARMA TOLA TO FULBARIYA MUKHTAR TOLA**
Block :- **Terhagachh**
District:- **Kishanganj**

S.L No.	Name of cutting of roads	Chainage in Km	Length in metre	Amount (In Rs.)
1	SHARMA TOLA TO FULBARIYA MUKHTAR TOLA 1st Cutting	2.65	50.00	Rs 457303.00
2	SHARMA TOLA TO FULBARIYA MUKHTAR TOLA 2nd Cutting	3.00	140.00	Rs 1019295.00
3	SHARMA TOLA TO FULBARIYA MUKHTAR TOLA 3rd Cutting	3.20	120.00	Rs 1046788.00
Total Cost=				Rs 2523386.00

Sony
25/12/20 -
J.E
RWD
Terhagachh

[Signature]
25/12/20
A.E
R.W.D
Terhagachh

[Signature]
25/12
E.E
R.W.D
Kishanganj - I

Technically approved for ₹:- 25,23,386 = 00

(Rs. ^{Twenty} ~~Fifty~~ five Lacs ~~twenty~~ ^{thirty} thousand and ~~three~~ ^{three} hundred

eighty size) only .

[Signature]
25/12/21