

TECHNICAL REPORT

Name of Work - FDR To Road From..... To 2 to PMGSY road to giri tola mahua.
Head - FDR
Estimated cost - ... 1,70,840 = 0.17 cracs

The work done estimate has been framed for the restoration (motorable) of traffic for the above road which was damage during the year 2020-2021 flash flood.

(A) Source of materials

Brick Bats - Local Kiln
Fine sand - Local
Cement Bag - Local Market
Aggregate for G.S.B - Matigara (Silliguri) by road up to site.
Bamboo - Local
Earth - Private land from 1000m lead.

(B) Rate - Carriage has been analyzed on minimum lead. Finished rate has been calculated without contractor's profit on MORD norms. Carriage of materials has been added to finished rate. Basic Rates are evaluated from rates approved by State schedule rate committee. 12% GST & 1% Labour cess has been added in the estimate in abstract part.

Sanction of estimate is much needed for payment of the work which was already done.

Sanj
25/12/20-
J.E
R.W.D
Kishanganj-1

Sanj
25/12/20
A.E
R.W.D
Kishanganj-1

C
25/12
E.E
R.W.D
Kishanganj-1

Inspection Report for Flood damage work

Date:

1. Name of PIUs- Executive Eng. RWD works division, Kishanganj-1.

2. Name of Block/Road- Terhagachh | To 2 PMGSY road to giri tola mahua.

A. For Road

1. Damage Location/Chainage : 0.900 km.

2. Damage Length : 30 m.

3. Nature of Damage : washed out flank damage.

4. Details of Restoration :

i Material being used in Restoration

: local sand, wheel barrow.

ii Equipment/Tools being used in Restoration works:

: Tractor.

iii Procedure taken up in Restoration works

: manual.

iv Restored Length

: 30 m.

B. For Bridge

1. Damage Location/Chainage :

2. Damage Length :

3. Nature of Damage :

4. Details of Restoration :

i Material being used in Restoration :

ii Equipment/Tools being used in Restoration works:

iii Procedure taken up in Restoration works :

iv Restored Length :

N.A.

Signature of JE/APEE

28/11/20

C 11/12

Signature

(Name of Inspector)

Detailed Estimate


T02 PMGSY Raod to Giri Tola Mahua


work :-

Item		No	Length (avg.)	Width (avg.)	Height (avg.)	Qnty	Unit	Rate	Amount
1	Providing and cutting of 62 mm to 75 mm dia bamboo piles to size and making shoes, all complete job ----E/I	100	2.60		-	260.00			
		Total				260.00	sqm	50.20	13052.00
2	Providing, fitting and fixing 62 mm to 75 mm dia bamboo runners in position at every vertical pile with 150 mm long nails or 38 swg G.I. wire including cost of G.I. wire or nails complete job as per specification and direction of E/I.	4	30.00	-	-	120.00			
		Total				120.00	sqm	28.53	3424.00
3	Providing and filling empty cement bags with local sand, stitching the bags and placing including supply of sutli etc. all complete job ----E/I	1	30.00	2.00	2.00	120.00			
		0	0.00	0.00	0.00	0.00			
		Total				120.00	cum		
		=	4237.80 cft		Say	3532.00	Nos	38.14	134710.00
TOTAL									151186.00

Add 12 % GST	Rs 18142.00
Add 1 % L. Ces	Rs 1512.00
Total Cost	Rs 170840.00

Sony
25/12/20
J.E
RWD
Kishanganj-1


25/12/20
A.E
R.W.D
Kishanganj-1


25/12
E.E
R.W.D
Kishanganj - I

Technically approved for ₹:- 1,70,840 = 50

(Rs. one Lacs seventy thousand and eight hundred

Forty) only.


25/11/21