

RURAL WORKS DEPARTMENT



GOVERNMENT OF BIHAR

CIRCLE – R.W.D. works Circle, Kishanganj

DIVISION – R.W.D. works Division, Kishanganj-1

Name of Work - Restoration of road from Bhebra To L-054

Block - Kochadhaman

Estimated cost - Rs 342503.00

Year : 2020-21

TECHNICAL REPORT

Name of Work – FDR To Road From... Bhebhara to Losa.

Head – FDR

Estimated cost – 3.425 Lacs

The work done estimate has been framed for the restoration (motarable) of traffic for the above road which was damage during the year 2020-2021 flash flood.

(A) Source of materials

Brick Bats – Local Kiln

Fine sand – Local

Cement Bag – Local Market


Aggregate for G.S.B – Matigara (Silliguri) by road up to site.

Bamboo – Local


Earth – Private land from 1000m lead.

- (B) Rate** - Carriage has been analyzed on minimum lead. Finished rate has been calculated without contractor's profit on MORD norms. Carriage of materials has been added to finished rate. Basic Rates are evaluated from rates approved by State schedule rate committee. 12% GST & 1% Labour cess has been added in the estimate in abstract part.

Sanction of estimate is much needed for payment of the work which was already done.


05.12.20

J.E
R.W.D
Kishanganj-1


8/12/20

A.E
R.W.D
Kishanganj-1


13/12

E.E
R.W.D
Kishanganj-1

Inspection Report for Flood damage work

Date:

1. Name of PIUs- RWD Kishorensent-1.

2. Name of Block/Road- Bhebra to L-054 under Kochadkernam block.

A. For Road

1. Damage Location/Chainage :

2. Damage Length : 40.00 m.

3. Nature of Damage : Flank damage and side cutting

4. Details of Restoration :

i Material being used in Restoration

: Bamboo, sand bag, Brick bats.

ii Equipment/Tools being used in Restoration works: Tractor.

iii Procedure taken up in Restoration works : manual.

iv Restored Length : 40.00 m.

B. For Bridge

1. Damage Location/Chainage :

2. Damage Length :

3. Nature of Damage :

4. Details of Restoration :

i Material being used in Restoration :

ii Equipment/Tools being used in Restoration works:

iii Procedure taken up in Restoration works :

iv Restored Length :

Signature of JE/AF/EE

Signature

(Name of Inspector)

कार्यपालक अभियन्ता
ग्रामीण कार्य विभाग
कार्य प्रमण्डल, अररिया

13.12.20
JE

Detailed Estimate

Name of work :-

Restoration of road from Bhebra To L-054

| Sl No | Item | No | Length | Width | Height | Qty | Unit | Rate | Amount |
|---|--|-------|-------------|-------|--------|---------|--------|--------------|-----------|
| 1 | Providing and cutting of 62 mm to 75 mm dia bamboo piles to size and making shoes, all complete job -----E/I | 42 | 1.50 | - | - | 63.00 | | | |
| | | 25 | 2.50 | - | - | 62.50 | | | |
| | | Total | | | | | 125.50 | RM | 50.20 |
| 2 | Providing, fitting and fixing 62 mm to 75 mm dia bamboo runners in position at every vertical pile with 150 mm long nails or 38 swg G.I. wire including cost of G.I. wire or nails complete job 'as per specification and direction of E/I | 6 | 25.00 | - | - | 150.00 | | | |
| | | 6 | 15.00 | - | - | 90.00 | | | |
| | | Total | | | | | 240.00 | RM | 28.53 |
| 3 | Providing and filling empty cement bags with local sand, stitching the bags and placing including supply of sutli etc. all complete job ----E/I | 2 | 25.00 | 1.10 | 1.50 | 82.50 | | | |
| | | 2 | 15.00 | 1.20 | 1.50 | 54.00 | | | |
| | | Total | | | | | 136.50 | cum | |
| 4 | Providing laying and spreading brick bats in Road ditches all complete as per approved design, specifications and direction of E/I | = | 4820.50 cft | | Say | 4017.00 | Nos | 38.14 | 153208.00 |
| | | 2 | 25.00 | 1.10 | 0.75 | 41.25 | | | |
| | | 2 | 15.00 | 1.00 | 0.75 | 22.50 | | | |
| | | Total | | | | | 63.75 | cum | 2145.02 |
| Total:- | | | | | | | | Rs 303100.00 | |
| Add GST @ 12 % :- | | | | | | | | Rs 36372.00 | |
| Add LC @ 01 % :- | | | | | | | | Rs 3031.00 | |
| Total cost of Restoration with GST & LC:- | | | | | | | | Rs 342503.00 | |

Say, Rs. 342500/-

05.12.20
J.E
RWD
Kochadhaman

8/12/20
A.E
R.W.D
Kochadhaman

C/13/12
E.E
R.W.D
Kishanganj - I

Technically approved for ₹. 342500/-

(Rs. Three Lacs forty two thousand and five

hundred) only

25/12/21
अधीक्षक अभियन्ता
ग्रामीण कार्य विभाग
कार्य अंचल, किशनगंज