

RURAL WORKS DEPARTMENT



GOVERNMENT OF BIHAR

CIRCLE – R.W.D. works Circle, Kishanganj

DIVISION – R.W.D. works Division , Kishanganj-1

Name of Work - Restoration of road from Shapur Kachan Tola to L-048

Block - Kochadhaman

Estimated cost - Rs 931428.00

Year : 2020-21

TECHNICAL REPORT

Name of Work – FDR To Road From Shehpur Kecham Jola to L-048

Head – FDR

Estimated cost – 9.314 Lacs

The work done estimate has been framed for the restoration (motarable) of traffic for the above road which was damage during the year 2020-2021 flash flood.

(A) Source of materials

Brick Bats – Local Kiln

Fine sand – Local

Cement Bag – Local Market


Aggregate for G.S.B – Matigara (Silliguri) by road up to site.

Bamboo – Local

Earth – Private land from 1000m lead.

- (B) Rate** - Carriage has been analyzed on minimum lead. Finished rate has been calculated without contractor's profit on MORD norms. Carriage of materials has been added to finished rate. Basic Rates are evaluated from rates approved by State schedule rate committee. 12% GST & 1% Labour cess has been added in the estimate in abstract part.


Sanction of estimate is much needed for payment of the work which was already done.


05.12.20

J.E
R.W.D
Kishanganj-1


8/12/20

A.E
R.W.D
Kishanganj-1


13/12

E.E
R.W.D
Kishanganj-1

Inspection Report for flood damage work

Date:

1. Name of PUs- RWD Kishanpur-1.

2. Name of Block/Road- Shahpur Kachan talu to 2048 under
Kochadhaman block.

A. For Road

1. Damage Location/Chainage :

2. Damage Length : 430 m.

3. Nature of Damage :

4. Details of Restoration : Flood damage and deep side cutting.

i Material being used in Restoration

: Bamboo, Brick batts.

ii Equipment/Tools being used in Restoration works:

: Tractor.

iii Procedure taken up in Restoration works

: Manual.

iv Restored Length

: 430 m.

B. For Bridge

1. Damage Location/Chainage :

2. Damage Length :

3. Nature of Damage :

4. Details of Restoration :

i Material being used in Restoration

:

ii Equipment/Tools being used in Restoration works:

:

iii Procedure taken up in Restoration works

:

iv Restored Length

:

Signature of JE/AE/EE

13.12.20
JE

कार्यपालक अभियन्ता
ग्रामीण कार्य विभाग
कार्य प्रमण्डल, किशनगंज-1

Signature

कार्यपालक अभियन्ता
(Name of Inspector)
ग्रामीण कार्य विभाग
कार्य प्रमण्डल, अररिया

Detailed Estimate


Name of work :-


Restoration of road from Shapur Kachan Tola to L-048

Sl No	Item	No	Length	Width	Height	Qty	Unit	Rate	Amount
1	Providing and cutting of 62 mm to 75 mm dia bamboo piles to size and making shoes, all complete job -----E/I	350	2.10	-	-	735.00			
		Total					735.00	RM	50.20
2	Providing, fitting and fixing 62 mm to 75 mm dia bamboo runners in position at every vertical pile with 150 mm long nails or 38 swg G.I. wire including cost of G.I. wire or nails complete job as per specification and direction of E/I	8	300.00	-	-	2400.00			
		Total					2400.00	RM	28.53
3	Providing laying and spreading brick bats in Road ditches all complete as per approved design, specifications and direction of E/I	1	200.00	1.00	0.75	150.00			
		1	230.00	1.15	0.70	185.15			
		Total					335.15	cum	2145.02
Total:-									Rs 824272.00
Add GST @ 12 % :-									Rs 98913.00
Add LC @ 01 % :-									Rs 8243.00
Total cost of Restoration with GST & LC:-									Rs 931428.00

504, Rs 931400/-


 05.12.2020
 J.E.
 RWD
 Kochadhaman



 8/12/20
 A.E.
 R.W.D
 Kochadhaman


 13/12
 E.E.
 R.W.D
 Kishanganj - I

Technically approved for Rs. 931400/-

(Rs. Nine Lacs ^{one} thousand and four

hundred) only


 25/1/21

अधीक्षण अभियन्ता
 ग्रामीण कार्य विभाग
 कार्य अंचल, किशनगंज.