

RURAL WORKS DEPARTMENT



GOVERNMENT OF BIHAR

CIRCLE – R.W.D. works Circle, Kishanganj

DIVISION – R.W.D. works Division , Kishanganj-1

Name of Work - Khujurbari Belwa Pothia RCC Bridge Near Chimni
BR-18R-310

Block - POTHIA

Estimated cost - Rs 1919738.00

Year : 2020-21

TECHNICAL REPORT

Name of Work - FDR To Road From... *Kheyzunbai Bahua... Police, RCC Bridge*
Head - FDR *near churi BP 18 R 310*
Estimated cost - *1936.20.00* Lacs

The work done estimate has been framed for the restoration (motarable) of traffic for the above road which was damage during the year 2020-2021 flash flood.

(A) Source of materials

Brick Bats - Local Kiln
Fine sand - Local
Cement Bag - Local Market
Aggregate for G.S.B - Matigara (Silliguri) by road up to site.
Bamboo - Local
Earth - Private land from 1000m lead.

- (B) **Rate** - Carriage has been analyzed on minimum lead. Finished rate has been calculated without contractor's profit on MORD norms. Carriage of materials has been added to finished rate. Basic Rates are evaluated from rates approved by State schedule rate committee. 12% GST & 1% Labour cess has been added in the estimate in abstract part.

Sanction of estimate is much needed for payment of the work which was already done.

[Signature]
12.12.2020
J.E
R.W.D
Kishanganj-2

[Signature]
A.E
R.W.D
Kishanganj-2

[Signature]
J.E
R.W.D
Kishanganj-2

Inspection Report for flood damage work

Date:

1.Name of PIUs- E-E- R.W.D (W) DIV- Kishanganj-2

2.Name of Block/Road- Poltara / Khajurbari Belua Poltara Rce Bridge
near chinnu BR18R-310

A.For Road

1.Damage Location/Chainage : Chm-19.20km

2. Damage Lengh : 35-m

3.Nature of Damage : Wased out fluk damage

4.Details of Restoration :

- i Material being used in Restoration : Local soil Banks Baly
- ii Equipment/Tools being used in Restoration works: Tractor, Mank Bamboo.
- iii Procedure taken up in Restoration works : Manual.
- iv Restored Length : 35-m

B. For Bridge

1.Damage Location/Chainage :

2. Damage Lengh :

3.Nature of Damage :

4.Details of Restoration :

- i Material being used in Restoration :
- ii Equipment/Tools being used in Restoration works:
- iii Procedure taken up in Restoration works :
- iv Restored Length :

Signature of JE/AE/EE


T.M. XX
AB


Signature

(Name of Inspector)

me of work :-

Detailed Estimate
Khujurbari Belwa Pothia RCC Bridge Near Chimni BR-18R-310

18R-510									
Sl No	Item	No	Length	Width	Height	Qty	Unit	Rate	Amount
1	Providing and cutting of 62 mm to 75 mm dia bamboo piles to size and making shoes, all complete job ----E/I	250	3.25	-	-	812.50			
		110	2.50	-	-	275.00			
		Total					1087.50	RM	50.20
2	Providing, fitting and fixing 62 mm to 75 mm dia bamboo runners in position at every vertical pile with 150 mm long nails or 38 swg G.I. wire including cost of G.I. wire or nails complete job as per specification and direction of E/I.	6	110.00	-	-	660.00			
		4	38.00	-	-	152.00			
		Total					812.00	RM	28.53
3	Filling and spreading local sand over brick bats as per drawing and technical specification Clause 305.3.9	1	55.00	5.10	1.70	476.85			
						476.85	cum	626.89	298932.00
4	Providing laying and spreading brick bats in Road ditches all complete as per approved design, specifications and direction of E/I	1	55.00	4.70	1.80	465.30			
						465.30	cum	2145.02	998078.00
5	Providing and filling empty cement bags with local sand, stitching the bags and placing including supply of sutli etc. all complete job ----E/I	2	55.00	1.25	2.10	288.75			
		Total					288.75	cum	
		=	10197.21 cft			Say	8498.00	Nos	38.14
TOTAL									1698883.00
							Add 12 % GST		Rs 203866.00

Add Surcharge for (+)

M 16500200
M 19,36238200
Subs-M 19,36200200

Kur
12/12/2020
J.E
RWD
POTHIA

Yog
12/12/20
A.E
R.W.D
POTHIA

Kishanganj
R.W.D
Kishanganj

Technically approved for ₹ 19,36,200/-

(Rs. Nine... Laes... Six... thousand and... Two... hundred...)only

20/12/20
अधीक्षण अभियन्ता
ग्रामीण कार्य विभाग
कार्य अंचल, किशनगंज