



ग्रामीण कार्य विभाग

Rural Works Department, Govt of Bihar

GOVT. OF BIHAR

FDR

YEAR 2020-21

Detailed Project Report

Division : Rosera

District :	Samastipur	Block :	Sivaji Nagar <i>Singhwa</i>
------------	------------	---------	-----------------------------

Name of
Road :

Akona Dodhina Path

SUBMITTED BY
THE EXECUTIVE ENGINEER
WORKS DIVISION, ROSERA

FDR

Detailed Estimate for

Akona Dodhina Path

Block : *Sivaji Nagar Siglwa*
District : *Samastipur*

ABSTRACT OF COST FOR ROAD

Sl No	Item of Work	Amount (In Rs)	
		As per Estimate	
1	Total Cost for Pavement Works		424769.54
	Total Cost of Project :	Rs -	424769.54
	Total Cost Including (GST + L.Cess) 13% :	Rs -	55220.04
	Total :	Rs -	479989.58
	Say (Lakh) :	Rs -	4.80

Komman
30/12/20

Junior Engineer

RWD (W) Section, Sivaji Nagar

R.R.
30/12/20

Asstt. Engineer

RWD (W) S. Div. Shivajinagar

Anil
30/12/20

Executive Engineer

RWD (W) Div, Rosera

*Technician Approved for Rs 4.80 lac say four -
Lakh Eighty thousand only.*

@Man
19.1.21
बसोदय बसिबहा
बसोदय कारे विभाग
कारे बसब, एबसोदय
19.1.21

FDR

Akona Dohina Path

District : Samastipur

Block : Sivaji Nagar

Total Length (Km):

0.09


SI No	Reference To Mord Spec.	Brief Description of Item	No	Measurements			Unit	Quantity	Rate (Rs)	Amount (Rs)
				L (m)	B (m)	D (m)				
1	401	Supply filling brick bat compacted manually	7	18.00	1.37	0.30	cum	51.79		
			2	20.00	1.50	0.40	cum	24.00		
			4	16.00	2.50	0.20	cum	32.00		
			3	20.00	1.50	0.40	cum	36.00		
			5	25.00	3.75	0.16	cum	75.00		
			1	18.00	1.50	0.40	cum	10.80		
			3	20.00	1.55	0.25	cum	23.25		
Total Quantity :							cum	252.84	1680.02	424769.54
Total Cost of Pavement in Rs :										4.25


30/12/20

Junior Engineer
RWD (W) Section, Shivajinagar


30/12/20

Asstt. Engineer
RWD (W) S. Div. Sivaji Nagar


30/12/20

Executive Engineer
RWD (W) Div, Rosera

प्रतिवेदन

योजना का नाम :

Akona Dodhina Path

प्रस्तावित प्राककलन ग्रामीण कार्य विभाग, बिहार सरकार के पत्रांक-2789 दिनांक-21/08/2020 एवं समस्तीपुर जिलाधिकारी, समस्तीपुर के आदेश के अनुपालन के अलोक में में कार्यपालक अभियंता, ग्रामीण कार्य विभाग, कार्य प्रमंडल-रोसड़ा के निदेशन में तैयार किया गया है। यह पथ विगत बाढ में डूबने एवं पानी के Overlapping होने के कारण काफी क्षतिग्रस्त हो चुका है। इस पथ में क्षतिग्रस्त मर्दों का आवश्यकतानुसार दिनांक-01/07/20 से प्रभावी वर्तमान अनुसूचित दर पर प्रावधान किया गया है, जो जनहित में आवश्यक है। प्राककलन आवश्यक कार्रवाई हेतु समर्पित।



कनीय अभियंता

ग्रामीण कार्य विभाग

कार्य प्रशाखा, Sivaji Nagar



सहायक अभियंता

ग्रामीण कार्य विभाग

कार्य अवर प्रमंडल- Sivaji Nagar



कार्यपालक अभियंता

ग्रामीण कार्य विभाग,

कार्य प्रमंडल-रोसड़ा

ANALYSIS OF RATES.

BRICK BAT FILLING.

1. Gravel sub base providing brick bats including spreading, laying and packing with oil hammer in layers not exceeding 75MM thick including cost of eight barriers, dangle signal, chokidas, taxes, Royalty, etc, all complete job, as per specifications and directions of E/S including cost of bricks. - - - all complete job.

Unit - cum.

assuming - 2.892 M³

Cost of Brick bats - 2.892 M³ @ 1096=00 - Rs 3169=87
 Mazdoor unskilled Local Rs 0.692 M³ @ 141=95/M³ Rs 89=65

Labour (unskilled)

1. Carrying, spreading, compacting
 packing unskilled labour 1.5 M³ @ 297=00 - Rs 490=50
 Compaction of brick bats with
 C.I. hammers, 0.670 M³ @ 287=00 - Rs 192=29
 over head charge @ 6% on (a+b+c) - Rs 228=99
 Total - 4045=29
 Rate / M³ - Rs 1428=42/M³.

Carriage cost

Carriage for Bricks (1 M³ @) Rs 300 M³ @ 669=50/M³ - Rs 199=06
 Local sand 0.320 M³ @ 97=00/M³ - Rs 21=94
 Total Rs 1648=81.
 31=24
 Total - 1680=02

2. Gravel sub base with well graded material, Table 400-1 by mix and place method for grading material all complete job.

Labour - Mate - 0.48 M³ @ 905=00 - Rs 146=40
 Mazdoor unskilled - 2.0 M³ @ 364=00 - Rs 728=00
 Mazdoor unskilled - 10.0 M³ @ 287=00 - Rs 2870=00

Machinery
 Tractor Motor Grader 6.0 H.P. @ 573=20 - Rs 3439=20
 Three wheel 80-100 KN 30.0 H.P. @ 809=00/Hr - Rs 24090=00
 10 M³/Hr
 Tractor with vibrator 12.0 H.P. @ 573=20 - Rs 6878=40
 25 M³/Hr
 Water Tanker 6kg Capacity 5.0 H.P. @ 184=00 - Rs 920=00
 Total 39072=00

Material
 Course Graded Gravel sub base
 53MM to 9.5MM, 95% - 134.40 M³ @ 604=91/M³ - Rs 80695=00
 9.5MM to 2.36MM 15% - 96.00 M³ @ 514=58/M³ - Rs 49410=00
 2.36MM below local sand 15% - 141=95/M³ - Rs 21788=00
 Total - 1,92,153=00
 Add over head charge 6% - Rs 11,529=00
 Total - 2,03,682=00

K. M. M. M.
 20/12/20
 J.E

कार्यपालक अभियंता का कार्यालय

ग्रामीण कार्य विभाग, कार्य प्रमण्डल, समस्तीपुर।

पत्रांक..... 2312/01 रोसड़ा

दिनांक..... 24.12.20

प्रेषक,

कार्यपालक अभियंता,
ग्रामीण कार्य विभाग,
कार्य प्रमण्डल, समस्तीपुर।

सेवा में,

कार्यपालक अभियंता,
ग्रामीण कार्य विभाग,
कार्य प्रमण्डल, रोसड़ा।

विषय:-

FDR अन्तर्गत पथों को जाँच करने के संबंध में।

प्रसंग:-


आपका पत्रांक 2312/01 दिनांक 22.12.20

महाशय,

उपर्युक्त प्रासंगिक विषयक के संबंध में कहना है कि आपके द्वारा निम्न पथों की सूची जाँच करने हेतु समर्पित किया गया था। पथों की जाँच की गई एवं जाँचोपरान्त सभी पथ पूर्ण पाया गया। प्रतिवेदन के साथ आवश्यक कार्रवाई हेतु समर्पित।

अनु०:- यथोक्त।

विश्वासभाजन


24.12.20
कार्यपालक अभियंता
ग्रामीण कार्य विभाग,
कार्य प्रमण्डल, समस्तीपुर।

ग्रामीण कार्य विभाग, कार्य प्रमंडल-रोसड़ा अंतर्गत FDR के तहत मरम्मत कराए गए पथों की सूची एवं जांच से संबंधित प्रतिवेदन

क्रम	प्रखंड	पथ का नाम	कराए गए कार्य	मरम्मत कराए गए पथ की लंबाई	प्राक्कलित राशि	अभ्युक्ति
1	Singhia	Sanbahka To Jamua Path	Brick Bat Filling	2.10	12.75	पूर्ण
2	Singhia	Improvement of road From Bharhar to Kanjara (Mhadalit Tola) To Pansalla mian road via Bangthaiya	Brick Bat Filling	2.00	10.21	पूर्ण
3	Singhia	Akona Dodhina Path	Brick Bat Filling	0.09	4.80	पूर्ण
4	Singhia	Wari chowk se wari gaaw	Brick Bat Filling	1.00	5.63	पूर्ण
5	Singhia	Bara Chowk to Sonmani Via Laxmjnia	Brick Bat Filling	3.20	9.87	पूर्ण
6	Singhia	"MRL01-Karpoori Chowk to Hardia(BR-30P2R-08)Block singhia"	Brick Bat Filling	5.60	17.87	पूर्ण
7	Singhia	Improvement of Road from Bachhuliya to Akopur-Harpur-pabra- lind Phase	Brick Bat Filling	0.40	4.43	पूर्ण
8	Singhia	L028 - T01 to Bashu Deva (VR28)	Brick Bat Filling	1.47	9.50	पूर्ण
9	Singhia	T03 (lilhau) to Kichaka Musahari Tola ward no. 01	Brick Bat Filling	2.95	4.78	पूर्ण
10	Singhia	L081-T01 to Dhakjari (VR81)	Brick Bat Filling	1.61	5.59	पूर्ण
11	Singhia	MDR TO - Lagma	Brick Bat Filling	1.65	9.41	पूर्ण
12	Singhia	L056-T02 To Jibudihuli (VR56)	Brick Bat Filling	1.23	1.48	पूर्ण
13	Singhia	Bharhar to Bhairson	Brick Bat Filling	1.07	5.56	पूर्ण
14	Singhia	T02 Bharhar to Fulwariya	Brick Bat Filling	0.79	3.38	पूर्ण
15	Singhia	Bhishanpura - Kabilashi	Brick Bat Filling	1.09	3.97	पूर्ण
16	Singhia	Kundal to Madhepura	Brick Bat Filling	1.13	5.86	पूर्ण
17	Singhia	Aatapur se kundal high School	Brick Bat Filling	0.75	4.49	पूर्ण
18	Singhia	Salepur - Tenua Road	Brick Bat Filling	6.30	8.70	पूर्ण
19	Singhia	L063-T02 to Mahara (VR63)	Brick Bat Filling	1.63	4.50	पूर्ण
20	Singhia	T01 - Aurahi Bhirar	Brick Bat Filling	4.37	6.72	पूर्ण
21	Singhia	Bela Pawda Path	Brick Bat Filling	1.00	6.93	पूर्ण
22	Singhia	L030-L025 to Rampura (VR30)	Brick Bat Filling	1.76	13.49	पूर्ण
23	Singhiya	Salepur se Singhia kalali Chowk	Brick Bat Filling	0.45	3.98	पूर्ण
24	Singhiya	SH56 To Gadhua	Brick Bat Filling	3.50	2.07	पूर्ण

[Handwritten Signature]
20/12/20

कार्यपालक अभियंता

ग्रामीण कार्य विभाग, कार्य प्रमंडल-समस्तीपुर