

TECHNICAL REPORT

Name of Work - FDR To Road From Chakla Gahangir Chowk Se AND get tak
Hend - FDR
Estimated cost - 6,54,817 Lacs

The work done estimate has been framed for the restoration (motorable) of traffic for the above road which was damage during the year 2020-2021 flash flood.

(A) Source of materials


Brick Bats - Local Kiln
Fine sand - Local
Cement Bag - Local Market
Aggregate for G.S.B - Matigara (Silliguri) by road up to site.
Bamboo - Local
Earth - Private land from 1000m lead.

(B) Rate - Carriage has been analyzed on minimum lead. Finished rate has been calculated without contractor's profit on MORD norms. Carriage of materials has been added to finished rate. Basic Rates are evaluated from rates approved by State schedule rate committee. 12% GST & 1% Labour cess has been added in the estimate in abstract part.

Sanction of estimate is much needed for payment of the work which was already done.


J.E.
R.W.D
Kishanganj-1


A.E.
R.W.D
Kishanganj-1


E.E.
R.W.D
Kishanganj-1

Inspection Report for flood damage work

Date:

1. Name of PIUs- Executive Engineers Kishanganj- I

2. Name of Block/Road- Kishanganj / Chukla Jahagis Chowk

A. For Road To AMU get Juk path nisman

1. Damage Location/Chainage : 150m .

2. Damage Length : 150m .

3. Nature of Damage : flood

4. Details of Restoration :

i Material being used in Restoration

ii Equipment/Tools being used in Restoration works:

iii Procedure taken up in Restoration works

iv Restored Length

: Sandbags, B. bags, Bamboo
Tractor etc.
Manually
150m .

B. For Bridge

1. Damage Location/Chainage :

2. Damage Length :

3. Nature of Damage :

4. Details of Restoration :

i Material being used in Restoration

ii Equipment/Tools being used in Restoration works:

iii Procedure taken up in Restoration works

iv Restored Length


14/12/20

Signature of JE/AF/EE


14/12/20


14/12


Signature

(Name of Inspector)

Detailed Estimate

Chakla Jahangir chowk se AMU get tak path nirman

ame of work

Sl No	Item	No	Length	Width	Height	Qty	Unit	Rate	Amount
1	Providing and cutting of 62 mm to 75 mm dia bamboo piles to size and making shoes, all complete job —E/I	85	1.35	-	-	114.75			
		15	2.00	-	-	30.00			
		Total				144.75	sqm	50.20	7266.00
2	Providing, fitting and fixing 62 mm to 75 mm dia bamboo runners in position at every vertical pile with 150 mm long nails or 38 swg G.I. wire	3	80.00	-	-	240.00			
		2	10.00	-	-	20.00			
		Total				260.00	sqm	28.53	7418.00
3	Providing and filling empty cement bags with local sand, stitching the bags and placing including supply of sutli etc. all complete job — E/I	1	85.00	0.65	1.95	107.74			
		1	10.00	0.45	0.60	2.70			
		Total				110.44	cum		
		=	3900.19 cft		Say	3250.00	Nos	38.14	123955.00
4	Providing laying and spreading brick bats in Road ditches all complete as per approved design, specifications and direction of E/I	1	20.00	4.00	0.50	40.00			
		1	25.00	3.75	0.60	56.25			
		1	22.00	3.12	0.65	44.62			
		2	5.00	3.50	0.50	17.50			
		1	14.00	3.50	0.35	17.15			
		1	15.00	4.00	0.50	30.00			
		Total				205.52	cum	2145.02	440845.00
TOTAL								579484.00	

(Signature)
J.E 14/12/20
RWD
Kishanganj-1

(Signature)
14/12/20
A.E
R.W.D
Kishanganj-1

Say. RS. 654900/-
(Signature)
14/12
E.E
R.W.D
Kishanganj - I

Technically approved for ₹ 654900/-

(Rs. six Lacs fifty four thousand and nine

Hundred) only

(Signature)
25/1/21