

TECHNICAL REPORT

Name of Work - FDR To Road From... *R.T. 7. 67... PWD... Road to Chhagalra.*

Head - FDR

Estimated cost - *5,95,763*..... Lacs

The work done estimate has been framed for the restoration (motorable) of traffic for the above road which was damage during the year 2020-2021 flash flood.

(A) Source of materials

Brick Bats - Local Kiln

Fine sand - Local

Cement Bag - Local Market

Aggregate for G.S.B - Matigara (Silliguri) by road up to site.

Bamboo - Local

Earth - Private land from 1000m lead.

- (B) Rate** - Carriage has been analyzed on minimum lead. Finished rate has been calculated without contractor's profit on MORD norms. Carriage of materials has been added to finished rate. Basic Rates are evaluated from rates approved by State schedule rate committee. 12% GST & 1% Labour cess has been added in the estimate in abstract part.

Sanction of estimate is much needed for payment of the work which was already done.

(Signature)
J.E 14/12/20
R.W.D
Kishanganj-1

(Signature)
14/12/20
A.E
R.W.D
Kishanganj-1

(Signature)
14/12
E.E
R.W.D
Kishanganj-1

Inspection Report for Flood damage work

Date:

1. Name of PIUs- Executive Engineers Kishanganj-1
2. Name of Block/Road- Kishanganj / K.T.T.G. PWD road
to Chhagalia.

A. For Road

1. Damage Location/Chainage :
2. Damage Length : 16m
3. Nature of Damage : Flood
4. Details of Restoration :
i Material being used in Restoration : B. baly
ii Equipment/Tools being used in Restoration works: Tractor
iii Procedure taken up in Restoration works : Manually
iv Restored Length : 16m.

B. For Bridge

1. Damage Location/Chainage :
2. Damage Length :
3. Nature of Damage :
4. Details of Restoration :
i Material being used in Restoration :
ii Equipment/Tools being used in Restoration works:
iii Procedure taken up in Restoration works :
iv Restored Length :


Signature of JE/AE/EE


14/12/20


14/12


11/12/20

Signature

(Name of Inspector)


Detailed Estimate


Name of work :-


K.T.T.G. PWD road to Chhagalia

SI No	Item	No	Length	Width	Height	Qty	Unit	Rate	Amount
1	Providing laying and spreading brick bats in Road ditches all complete as per approved design, specifications and direction of E/I	1	10.00	5.00	3.60	180.00			
		1	6.00	5.10	2.15	65.79			
		Total						245.79	cum
TOTAL									527224.00
							Add 12 % GST		Rs 63267.00
							Add 1 % L. Ces		Rs 5272.00
							Total Cost		Rs 595763.00

SAY, Rs. 595800/-


J.E. 14/11/20
RWD
Kishanganj-1


A.E. 14/11/20
R.W.D
Kishanganj-1


E.E. 14/11/20
R.W.D
Kishanganj - I

Technically approved for ₹ 595800/-

(Rs. Five Lacs ^{five} ~~hundred~~ thousand and ~~eight~~ ^{hundred} only)


25/11/20