

RURAL WORKS DEPARTMENT



GOVERNMENT OF BIHAR

CIRCLE – R.W.D. works Circle, Kishanganj

DIVISION – R.W.D. works Division , Kishanganj-1

Name of Work - Restoration of road from Sontha High School To
Modho Road Via Mohra

Block - Kochadhaman

Estimated cost - Rs 1103579.00

Year : 2020-21

Inspection Report for flood damage work

Date:

1. Name of PIUs- RWD Kishanzen-1.

2. Name of Block/Road- Sonthe High School to Mhodho road via Mohra under Kochathaman block.

A. For Road

1. Damage Location/Chainage :

2. Damage Length : 190 m.

3. Nature of Damage : Bank & subgrade damage. (Deep side cutting)

4. Details of Restoration :

i Material being used in Restoration

: Bamboo, sand bags, sacks
bags.

ii Equipment/Tools being used in Restoration works: tractor.

iii Procedure taken up in Restoration works : manual.

iv Restored Length : 190.00 m.

B. For Bridge

1. Damage Location/Chainage :

2. Damage Length :

3. Nature of Damage :


4. Details of Restoration :

i Material being used in Restoration :

ii Equipment/Tools being used in Restoration works:


iii Procedure taken up in Restoration works :

iv Restored Length :


13/12/20
AE

Signature of JE/AF/EE


C
13/12


13/12/20

Signature

(Name of Inspector)

कार्यपालक अभियन्ता
ग्रामीण कार्य विभाग
कार्य प्रमण्डल, अररिया


13.12.2020
JE

TECHNICAL REPORT

Name of Work – FDR To Road From Somtha Hesh school to Modho mohra
via mohra.
Head – FDR
Estimated cost – 11.035 Lacs

The work done estimate has been framed for the restoration (motarable) of traffic for the above road which was damage during the year 2020-2021 flash flood.

(A) Source of materials

Brick Bats – Local Kiln
Fine sand – Local
Cement Bag – Local Market
Aggregate for G.S.B – Matigara (Silliguri) by road up to site.
Bamboo – Local
Earth – Private land from 1000m lead.

(B) Rate - Carriage has been analyzed on minimum lead. Finished rate has been calculated without contractor's profit on MORD norms. Carriage of materials has been added to finished rate. Basic Rates are evaluated from rates approved by State schedule rate committee. 12% GST & 1% Labour cess has been added in the estimate in abstract part.


Sanction of estimate is much needed for payment of the work which was already done.


05.12.20

J.E
R.W.D
Kishanganj-1


8/12/20

A.E
R.W.D
Kishanganj-1


13/12

E.E
R.W.D
Kishanganj-1


Detailed Estimate


Name of work :-

Restoration of road from Sontha High School To Modho Road
Via Mohra

Sl No	Item	No	Length	Width	Height	Qty	Unit	Rate	Amount
1	Providing and cutting of 62 mm to 75 mm dia bamboo piles to size and making shoes, all complete job -----E/I	83	2.50	-	-	207.50			
		100	2.00	-	-	200.00			
		Total				407.50	RM	50.20	20457.00
2	Providing, fitting and fixing 62 mm to 75 mm dia bamboo runners in position at every vertical pile with 150 mm long nails or 38 swg G.I. wire including cost of G.I. wire or nails complete job as per specification and direction of E/I.	6	60.00	-	-	360.00			
		4	60.00	-	-	240.00			
		Total				600.00	RM	28.53	17118.00
3	Providing and filling empty cement bags with local sand, stitching the bags and placing including supply of sutli etc. all complete job ----E/I	2	30.00	1.50	1.50	135.00			
		2	30.00	2.00	2.50	300.00			
		Total				435.00	cum		
		=	15362.03 cft		Say	12802.00	Nos	38.14	488268.00
4	Providing laying and spreading brick bats in Road ditches all complete as per approved design, specifications and direction of E/I	2	25.00	1.20	1.20	72.00			
		2	30.00	1.50	0.90	81.00			
		1	20.00	1.20	0.20	4.80			
		1	35.00	1.20	0.30	12.60			
		1	20.00	1.20	0.25	6.00			
		1	30.00	1.20	0.30	10.80			
		1	21.00	1.50	0.30	9.45			
		1	30.00	1.50	0.30	13.50			
		Total				210.15	cum	2145.02	450776.00
Total:-								Rs 976619.00	
Add GST @ 12 % :-								Rs 117194.00	
Add LC @ 01 % :-								Rs 9766.00	
Total cost of Restoration with GST & LC:-								Rs 1103579.00	


 05.12.20
 J.E.
 RWD
 Kochadhaman


 8/12/20
 A.E.
 R.W.D
 Kochadhaman



 3/12
 E.E.
 R.W.D
 Kishanganj - I

Say Rs- 1103600/-

Technically approved for Rs 1103600/-

(Rs. eleven Lacs Three thousand and six

hundred.) only


 25/1/21
 अधीक्षण अभियन्ता
 ग्रामीण कार्य विभाग
 कार्य अंचल, किशनगंज