

TECHNICAL REPORT

Name of Work - FDR To Road From.. *Mahingaom Merna toli chark to khagron*
Head - FDR *Deori vai Dulbasti.*
Estimated cost - *737948*..... Lacs


The work done estimate has been framed for the restoration (motarable) of traffic for the above road which was damage during the year 2020-2021 flash flood.

(A) Source of materials

Brick Bats - Local Kiln
Fine sand - Local
Cement Bag - Local Market
Aggregate for G.S.B - Matigara (Silliguri) by road up to site.
Bamboo - Local
Earth - Private land from 1000m lead.

(B) Rate - Carriage has been analyzed on minimum lead. Finished rate has been calculated without contractor's profit on MORD norms. Carriage of materials has been added to finished rate. Basic Rates are evaluated from rates approved by State schedule rate committee. 12% GST & 1% Labour cess has been added in the estimate in abstract part.

Sanction of estimate is much needed for payment of the work which was already done.


J.E.
R.W.D
Kishanganj-1


A.E.
R.W.D
Kishanganj-1

E.E
R.W.D
Kishanganj-1

Inspection Report for Flood damage work

Date:

1. Name of PIUs- Executive Engineer Kishanganj - I

2. Name of Block/Road- Kishanganj / Mohingaon Mazraa Jali
Chauk do Khagra Darsi via fulbari

A. For Road

1. Damage Location/Chainage :

2. Damage Length : 160m.

3. Nature of Damage : flood

4. Details of Restoration :

i Material being used in Restoration

: B. Bah

ii Equipment/Tools being used in Restoration works:

: Tractor

iii Procedure taken up in Restoration works

: Manually

iv Restored Length

: 160m.

B. For Bridge

1. Damage Location/Chainage :

2. Damage Length :

3. Nature of Damage :

4. Details of Restoration :

i Material being used in Restoration

:

ii Equipment/Tools being used in Restoration works:

:

iii Procedure taken up in Restoration works


:

iv Restored Length

:


Signature of JE/AF/EE


Signature of JE/AF/EE


Signature of JE/AF/EE


Signature

(Name of Inspector)


Detailed Estimate

Name of work :-


Mahingaon Marwa toli chowk to Khagra Deori via Fulbasti

SI No	Item	No	Length	Width	Height	Qty	Unit	Rate	Amount
1	Providing laying and spreading brick bats in Road ditches all complete as per approved design, specifications and direction of E/I	1	10.00	3.20	0.30	9.60			
		1	100.00	3.25	0.60	195.00			
		1	5.00	3.00	0.65	9.75			
		1	15.00	3.60	0.65	35.10			
		1	10.00	3.00	0.80	24.00			
		1	20.00	3.10	0.50	31.00			
		Total					304.45	cum	2145.02
TOTAL								653051.00	
							Add 12 % GST	Rs 78366.00	
							Add 1 % L. Ces	Rs 6531.00	
							Total Cost	Rs 737948.00	

Say. RS. 738000/-


J.E. 14/11/22
RWD
Kishanganj-1


A.E.
R.W.D
Kishanganj-1


E.E.
R.W.D
Kishanganj - I

Technically approved for ₹ 738000/-

(Rs. Seven Lacs ^{Eight} Thirty thousand and -)

.....) only


25/11/22