

TECHNICAL REPORT

Name of Work – FDR To Road From... *Grachhpara Gaonyo* *Adh* *Rauri Boudi* *Amdhwal*

Head – FDR

Estimated cost – *533882* Lacs

The work done estimate has been framed for the restoration (motorable) of traffic for the above road which was damage during the year 2020-2021 flash flood.

(A) Source of materials

Brick Bats – Local Kiln

Fine sand – Local

Cement Bag – Local Market

Aggregate for G.S.B – Matigara (Silliguri) by road up to site.

Bamboo – Local

Earth – Private land from 1000m lead.

- (B) Rate** - Carriage has been analyzed on minimum lead. Finished rate has been calculated without contractor's profit on MORD norms. Carriage of materials has been added to finished rate. Basic Rates are evaluated from rates approved by State schedule rate committee. 12% GST & 1% Labour cess has been added in the estimate in abstract part.

Sanction of estimate is much needed for payment of the work which was already done.

[Signature]
J.E

R.W.D

Kishanganj-1

[Signature]
A.E

R.W.D

Kishanganj-1

[Signature]
E.E

R.W.D

Kishanganj-1

Inspection Report for flood damage work

Date:

1. Name of PIUs- Executive Engineer Kishanganj-1
2. Name of Block/Road- Kishanganj / Gachpara Gachon do
A. For Road Anandnagar Khuri Basti Taluk.

1. Damage Location/Chainage : 114 m
2. Damage Length :
3. Nature of Damage : Flood
4. Details of Restoration :
i Material being used in Restoration : Brick bats,
ii Equipment/Tools being used in Restoration works: Tractor
iii Procedure taken up in Restoration works : Manually
iv Restored Length : 114 m.


B. For Bridge

1. Damage Location/Chainage :
2. Damage Length :
3. Nature of Damage :
4. Details of Restoration :
i Material being used in Restoration :
ii Equipment/Tools being used in Restoration works:
iii Procedure taken up in Restoration works :
iv Restored Length :


14/12/20

Signature of JE/AF/EE


14/12/20


14/12


14/12/20

Signature

(Name of Inspector)


Detailed Estimate

Name of work :-


Gachpara Gaon yo Andhwakol kHuri Basti Tak

SI No	Item	No	Length	Width	Height	Qty	Unit	Rate	Amount
1	Providing laying and spreading brick bats in Road ditches all complete as per approved design, specifications and direction of E/I	1	50.00	3.50	0.35	61.25			
		1	5.00	3.70	0.65	12.03			
		1	8.00	3.20	1.14	29.18			
		1	30.00	3.15	0.65	61.43			
		2	4.50	3.50	1.50	47.25			
		1	12.20	1.15	0.65	9.12			
		Total						220.26	cum
TOTAL								472462.00	
							Add 12 % GST	Rs 56695.00	
							Add 1 % L. Ces	Rs 4725.00	
							Total Cost	Rs 533882.00	

Say Rs. 533900/-



JE
RWD
Kishanganj-1


AE
RWD
Kishanganj-1


EE
RWD
Kishanganj - I

Technically approved for ₹ 533900/-

(Rs. five Lacs thirty thousand and nine hundred) only


25/1/21