

TECHNICAL REPORT

Name of Work = Pingsy Kachhari tola to Sitagach Tak Tak Via Kachhari Tola Madarsa
Head = FDR
Estimated cost = 8.88356 Lacs


The work done estimate has been framed for the restoration (motable) of traffic for the above road which was damage during the year 2020-21 flash flood.


(A) Source of materials


Brick Bats = Local Kiln
Fine sand = Local
Cement Bag = Local Market
Aggregate for G.S.B = Matigara (Silliguri) by road up to site.
Bamboo = Local
Earth = Private land from 1000m lead.

(B) Rate - Carriage has been analyzed on minimum lead. Finished rate has been calculated without contractor's profit on MORD norms. Carriage of materials has been added to finished rate. Basic Rates are evaluated from rates approved by State schedule rate committee. 12% GST & 1% Labour cess has been added in the estimate in abstract part.

Sanction of estimate is much needed for payment of the work which was already done.


J.E
R.W.D
Kishanganj-1


A.E
R.W.D
Kishanganj-1


E.E
R.W.D
Kishanganj-1

Inspection Report for Flood damage work

Date:- 13.12.20

1. Name of PIUs: R.W.D, Kishanganj-3

2. Name of Block/Road: Bahadurganj / P.M.S.Y Kachhri 7019 to Sitajacharan via
Kachhri 7019 Madani

A. For Road

1. Damage Location/Chainage : 2.20 KM

2. Damage Length : 40.00 M

3. Nature of Damage : washed out

4. Details of Restoration :

i Material being used in Restoration

: H.P, sand bags and brick bats

ii Equipment/Tools being used in Restoration works: JCB, Tractor

iii Procedure taken up in Restoration works : manual

iv Restored Length : 40.00 M

B. For Bridge

1. Damage Location/Chainage :

2. Damage Length :

3. Nature of Damage :

4. Details of Restoration :

i Material being used in Restoration

: N/A

ii Equipment/Tools being used in Restoration works:

:

iii Procedure taken up in Restoration works

:

iv Restored Length

:

13.12.20
Signature of JE/AE/EE

13.12.2020
AE

13/12/20

13/12/20
Signature

(Name of Inspector)

Detailed Estimate

Name of work :-

Pmgsy Kachhari Tola to Sitagach Tak Tak Via Kachhari Tola Madarsa

SI No	Item	No	Length	Width (av)	Ht. (av)	Qty	Unit	Rato	Amount
1	Providing and laying reinforced cement concrete pipe NP3 for culverts of 1000 dia, all complete job -----E/I.	2	2.50	-	-	5.00			
		1	0.00	-	-	0.00			
		Total				5.00	RM	4781.89	23909.00
2	Providing and filling empty cement bags with local sand, stitching the bags and placing including supply of sutli etc. all complete job ---- E/I	1	5.00	0.55	1.50	4.13			
		1	5.00	0.60	1.40	4.20			
		Total				8.33	cum		
		=	294.17 cft		Say	245.00	Nos	38.14	9344.00
3	Providing laying and spreading brick bats in Road ditches all complete as per approved	1	40.00	4.50	1.95	351.00			
		Total				351.00	cum	2145.02	752902.00
								TOTAL	786155.00
								Add GST@12%	94339.00
								Add L.C@1%	7862.00
								TOTAL -	888356.00

[Signature]
10/12/20
J.E
RWD
Bahadurganj-1

[Signature]
11/12/2020
A.E
R.W.D
Bahadurganj

Say RS- 888400/-
[Signature]
13/12/20
E.E
R.W.D
Kishanganj - I

Technically approved for ₹ 888400 /-

(Rs. Eight ^{eight} Lacs Eighty ^{eight} thousand and ^{four} _{hundred} only)

[Signature]
25/12