

RURAL WORKS DEPARTMENT



GOVERNMENT OF BIHAR

CIRCLE – R.W.D. works Circle, Kishanganj

DIVISION – R.W.D. works Division , Kishanganj-2

Name of Work - T05 to Ganjabari

Block - POTHIA

Estimated cost - Rs 1017928.00

Year : 2020-21

TECHNICAL REPORT

Name of Work – FDR To Road From.....*Tos to Wanjabari*.....

Head – FDR

Estimated cost –*10,26,900*..... Lacs

The work done estimate has been framed for the restoration (motorable) of traffic for the above road which was damage during the year 2020-2021 flash flood.

(A) Source of materials

Brick Bats – Local Kiln

Fine sand – Local

Cement Bag – Local Market

Aggregate for G.S.B – Matigara (Silliguri) by road up to site.

Bamboo – Local

Earth – Private land from 1000m lead.

- (B) Rate** - Carriage has been analyzed on minimum lead. Finished rate has been calculated without contractor's profit on MORD norms. Carriage of materials has been added to finished rate. Basic Rates are evaluated from rates approved by State schedule rate committee. 12% GST & 1% Labour cess has been added in the estimate in abstract part.

Sanction of estimate is much needed for payment of the work which was already done.

Kur
12/12/2020
J.E
R.W.D
Kishanganj-2

Yeo
A.E
R.W.D
Kishanganj-2

9
E.E
R.W.D
Kishanganj-2
12/12/20

Inspection Report for flood damage work

Date:

1. Name of PIUs-

E. G. R. W. D (W) DIV - Kithangar-2

2. Name of Block/Road-

Polthia / Tos to Mangabari

A. For Road

1. Damage Location/Chainage : Chn - 2-10 km

2. Damage Length : 35-com

3. Nature of Damage : Washed out Mark Damage

4. Details of Restoration :

i Material being used in Restoration

: Local sand Bricks Bates

ii Equipment/Tools being used in Restoration works:

Bamboo.

iii Procedure taken up in Restoration works

: Tractor. Maintenance.

iv Restored Length

35-com

B. For Bridge

1. Damage Location/Chainage :

2. Damage Length :

3. Nature of Damage :

4. Details of Restoration :


i Material being used in Restoration :


ii Equipment/Tools being used in Restoration works:

iii Procedure taken up in Restoration works :

iv Restored Length :

Signature of JE/AE/EE


T.M. XXX
AB


Signature

(Name of Inspector)

Detailed Estimate

T05 to Ganjabari

SI No	Item	No	Length	Width	Height	Qty	Unit	Rate	Amount
1	Providing and cutting of 62 mm to 75 mm dia bamboo piles to size and making shoes, all complete job ----E/I	100	1.50	-	-	150.00			
		10	1.00	-	-	10.00			
		Total					160.00	RM	50.20
2	Providing, fitting and fixing 62 mm to 75 mm dia bamboo runners in position at every vertical pile with 150 mm long nails or 38 swg G.I. wire including cost of G.I. wire or nails complete job as per specification and direction of E/I.	6	30.00	-	-	180.00			
		2	10.00	-	-	20.00			
		Total					200.00	RM	28.53
3	Fillling and spreading local sand over brick bats as per drawing and technical specification Clause 305.3.9	1	35.00	5.25	1.50	275.63			
						275.63	cum	626.96	172806.00
4	Providing laying and spreading brick bats in Road ditches all complete as per approved design, specifications and direction of E/I	1	35.00	5.00	1.30	227.50			
						227.50	cum	2145.02	487992.00
5	Providing and filling empty cement bags with local sand, stitching the bags and placing including supply of sutli etc. all complete job ----E/I	2	35.00	1.60	1.80	201.60			
		Total					201.60	cum	
		=	7119.50 cft		Say	5933.00	Nos	38.14	226285.00
TOTAL								900821.00	
							Add 12 % GST on	Rs 108099.00	
							Add 1 % L. Cess	Rs 9008.00	
							Total Cost	Rs 1017928.00	

Add Sengunze fee Rs 9000.00
 M 10,26,928.20
 Sys M 10,26,900.20

[Signature]
 J.E
 RWD
 POTHIA

[Signature]
 A.E
 R.W.D
 POTHIA

[Signature]
 R.W.D
 Kishanganj

Technically approved for ₹ 10,26,900/-

(Rs. Ten...Lacs Twenty Six thousand and Nine

hundred -) only

[Signature]
 24/12/20
 अधीक्षण अभियन्ता
 ग्रामीण कार्य विभाग
 कार्य अंचल, किशनगंज