

TECHNICAL REPORT

Name of Work – FDR To Road From... *To 8 to Durgapur Bangama*
Head – FDR
Estimated cost – ... *9.00876* ... Lacs

The work done estimate has been framed for the restoration (motarable) of traffic for the above road which was damage during the year 2020-2021 flash flood.

(A) Source of materials

Brick Bats – Local Kiln
Fine sand – Local
Cement Bag – Local Market
Aggregate for G.S.B – Matigara (Silliguri) by road up to site.
Bamboo – Local
Earth – Private land from 1000m lead.

(B) Rate - Carriage has been analyzed on minimum lead. Finished rate has been calculated without contractor's profit on MORD norms. Carriage of materials has been added to finished rate. Basic Rates are evaluated from rates approved by State schedule rate committee. 12% GST & 1% Labour cess has been added in the estimate in abstract part.

Sanction of estimate is much needed for payment of the work which was already done.

J.E
10.12.20
J.E
R.W.D
Kishanganj-1

A.E
11/12/2020
A.E
R.W.D
Kishanganj-1

E.E
12/12/20
E.E
R.W.D
Kishanganj-1

Inspection Report for Flood damage work

Date: - 12.12.20

1. Name of PIUs- R.W.D, Kishanganj-I

2. Name of Block/Road- Bahadurganj / To 8 to Durgapur Bangarma

A. For Road

1. Damage Location/Chainage : 3rd & 4th Km

2. Damage Length : - 85.00M

3. Nature of Damage : crust damage, flank damage

4. Details of Restoration :

i Material being used in Restoration

: - Bamboo, sand bags, brick bats

ii Equipment/Tools being used in Restoration works: JCV, Tractors etc

: Manual

iii Procedure taken up in Restoration works

: 85.00M

iv Restored Length

B. For Bridge

1. Damage Location/Chainage :

2. Damage Length :

3. Nature of Damage :

4. Details of Restoration :

i Material being used in Restoration

ii Equipment/Tools being used in Restoration works:

iii Procedure taken up in Restoration works

iv Restored Length

N.A

12.12.20
Signature of JE/AFEE

12/12/2020
BB

13/12/20

12/12/2020
Signature

(Name of Inspector)

Detailed Estimate

Line of work :-

T08 to Durgapur Bangama

No	Item	No	Length	Width	Height	Qty	Unit	Rate	Amount
1	Providing and cutting of 62 mm to 75 mm dia bamboo piles ---do---E/I	141	3.60	-	-	507.60			
		32	3.25	-	-	104.00			
		Total				611.60	RM	50.20	30702.00
2	Providing, fitting and fixing 62 mm to 75 mm dia bamboo runners ---do--- E/I.	8	45.00	-	-	360.00			
		7	40.00	-	-	280.00			
		Total				640.00	RM	28.53	18259.00
3	Providing and filling empty cement bags with local sand, stitching the bags and placing including supply of sutli etc. all complete job ----E/I	1	85.00	1.65	1.80	252.45			
		Total				252.45	cum		
		=	8915.27 cft		Say	7429.00	Nos	38.14	283342.00
4	Providing laying and spreading brick bats in Road ditches all complete as per approved design, specifications and direction of E/I	1	85.00	1.50	1.70	216.75			
		Total				216.75	cum	2145.02	464933.00
TOTAL									797236.00

Add GST@12% 95668.00

Add L.C@1% 7972.00

TOTAL - 900876.00

SAY RS-

900900/-
13/12/20

[Signature]
10.12.20
J.E
RWD
Bahadurganj-1

[Signature]
11/12/2020
A.E
R.W.D
Bahadurganj

E.E
R.W.D
Kishanganj - I

Technically approved for ₹ 900900/-

(Rs. Nine Lacs. -- thousand and nine hundred.) only

[Signature]
25/11/20