

## TECHNICAL REPORT

Name of Work – FDR To Road From... *PM. G.S.Y. To Kharin Baoti* .....

Head – FDR

Estimated cost – *514.891* ..... Lacs

The work done estimate has been framed for the restoration (motarable) of traffic for the above road which was damage during the year 2020-2021 flash flood.

**(A) Source of materials**

Brick Bats – Local Kiln

Fine sand – Local

Cement Bag – Local Market

Aggregate for G.S.B – Matigara (Silliguri) by road up to site.

Bamboo – Local

Earth – Private land from 1000m lead.

- (B) Rate** - Carriage has been analyzed on minimum lead. Finished rate has been calculated without contractor's profit on MORD norms. Carriage of materials has been added to finished rate. Basic Rates are evaluated from rates approved by State schedule rate committee. 12% GST & 1% Labour cess has been added in the estimate in abstract part.

Sanction of estimate is much needed for payment of the work which was already done.

*(Signature)*  
J.E

R.W.D  
Kishanganj-1

*(Signature)*  
A.E

R.W.D  
Kishanganj-1

*(Signature)*  
E.E

R.W.D  
Kishanganj-1

Inspection Report for flood damage work

Date:

1. Name of PIUs- Executive Engineer Kishanganj-1  
2. Name of Block/Road- Kishanganj / Pingsy do Khari Barsti

**A. For Road**

1. Damage Location/Chainage : 205 m.  
2. Damage Length :  
3. Nature of Damage : flood  
4. Details of Restoration :


- i Material being used in Restoration
- ii Equipment/Tools being used in Restoration works:
- iii Procedure taken up in Restoration works
- iv Restored Length

: B. brk<sup>5</sup> sand bags etc  
: Tractor  
: Munnahy  
: 205 m.

**B. For Bridge**


1. Damage Location/Chainage :  
2. Damage Length :  
3. Nature of Damage :  
4. Details of Restoration :


- i Material being used in Restoration :
- ii Equipment/Tools being used in Restoration works:
- iii Procedure taken up in Restoration works :
- iv Restored Length :



Signature of JE/AF/EE







Signature

(Name of Inspector)

### Detailed Estimate

Name of work :-

### Pmgsy to Khari Basti

SI No	Item	No	Length	Width	Height	Qty	Unit	Rate	Amount
1	Providing and filling empty cement bags with local sand, stitching the bags and placing including supply of sutli etc. all complete job — E/I	1	110.00	0.45	0.80	39.60			
		1	55.00	0.45	0.85	21.04			
		1	25.00	0.60	0.82	12.30			
		1	15.00	0.45	0.80	5.40			
		Total				78.34	cum		
		=	2766.58 cft		Say	2305.00	Nos	38.14	87913.00
2	Providing laying and spreading brick bats in Road ditches all complete as per approved design, specifications and direction of E/I	1	110.00	1.15	0.60	75.90			
		1	55.00	1.10	1.25	75.63			
		1	25.00	1.25	0.45	14.06			
		1	15.00	1.30	0.30	5.85			
		Total				171.44	cum	2145.02	367742.00
		TOTAL							

Add 12 % GST Rs 54679.00

Add 1 % L. Ces Rs 4557.00

Total Cost Rs 514891.00

Say. RS. 514900/-

  
JE 14/12/20  
RWD  
Kishanganj-1

  
JE 14/12/20  
RWD  
Kishanganj-1

  
JE 14/12  
RWD  
Kishanganj - I

Technically approved for ₹ 514900/-

(Rs. Five Lacs four thousand and nine

Hundred) only

  
25/1/24