

## TECHNICAL REPORT

Name of Work – FDR To Road From... *P.M. GSY Road to Patkwa*

Head – FDR

Estimated cost – ... *1,21,890* ..... Lacs

The work done estimate has been framed for the restoration (motarable) of traffic for the above road which was damage during the year 2020-2021 flash flood.

**(A) Source of materials**

Brick Bats – Local Kiln

Fine sand – Local

Cement Bag – Local Market

Aggregate for G.S.B – Matigara (Silliguri) by road up to site.

Bamboo – Local

Earth – Private land from 1000m lead.

- (B) **Rate** - Carriage has been analyzed on minimum lead. Finished rate has been calculated without contractor's profit on MORD norms. Carriage of materials has been added to finished rate. Basic Rates are evaluated from rates approved by State schedule rate committee. 12% GST & 1% Labour cess has been added in the estimate in abstract part.


Sanction of estimate is much needed for payment of the work which was already done.

  
J.E.

R.W.D  
Kishanganj-1

  
A.E.

R.W.D  
Kishanganj-1

  
E.E.

R.W.D  
Kishanganj-1

# Inspection Report for Road Damage work

Date:

1. Name of P.W.D. *Coastal Engineering*
2. Name of Block/Road *Kishangang / Highway Road to Station*

## A. For Road

1. Damage Location/Chainage : *15m*
2. Damage Length : *15m*
3. Nature of Damage : *felced*
4. Details of Restoration :
  - i. Material being used in Restoration
  - ii. Equipment/Tools being used in Restoration works
  - iii. Procedure taken up in Restoration works
  - iv. Restored Length

*Sand bags, 8 bags*  
*Trails*  
*Manually*  
*15m*

## B. For Bridge

1. Damage Location/Chainage :
2. Damage Length :
3. Nature of Damage :
4. Details of Restoration :
  - i. Material being used in Restoration
  - ii. Equipment/Tools being used in Restoration works
  - iii. Procedure taken up in Restoration works
  - iv. Restored Length

*[Signature]*

Signature of JDA/ITE

*[Signature]*  
*12/12/20*

*[Signature]*  
*12/12*

*[Signature]*  
 Signature

(Name of Inspector)

Name of work :-

**Detailed Estimate**

PMGSY Raod to Patalwa

Sl No	Item	No	Length	Width	Height	Qty	Unit	Rate	Amount
1	Providing and filling empty cement bags with local sand, stitching the bags and placing including supply of sutt etc. all complete job --- E/I	1	10.00	1.60	1.00	16.00			
		1	5.00	0.85	1.00	4.25			
		Total				20.25	cum		
		715.13 cft				Say 596.00	Nos	38.14	22731.00
2	Providing laying and spreading brick bats in Road ditches all complete as per approved design, specifications and direction of E/I	1	10.00	2.50	1.25	31.25			
		1	5.00	1.35	1.25	8.44			
		Total				39.69	cum	2145.02	85136.00
						TOTAL			107867.00

Add 12 % GST Rs 12944.00

Add 1 % L. Ces Rs 1079.00

Total Cost Rs 121890.00

say. RS. 121900/-

*(Signature)*  
J.E. 14/12/20  
RWD  
Kishanganj-1

*(Signature)*  
14/12/20  
A.E.  
R.W.D  
Kishanganj-1

*(Signature)*  
14/12  
E.E.  
R.W.D  
Kishanganj - I

Technically approved for ₹ 121900/-

(Rs. One Lacs twenty thousand and nine

Hundred only

*(Signature)*  
25/11/21