

## TECHNICAL REPORT

Name of Work - FDR To Road From pmgsy Road to Boma banti road no 7

Head - FDR

Estimated cost - 331-350 Lacs

The work done estimate has been framed for the restoration (motarable) of traffic for the above road which was damage during the year 2020-2021 flash flood.

**(A) Source of materials**

Brick Bats - Local Kiln

Fine sand - Local

Cement Bag - Local Market


Aggregate for G.S.B - Matigara (Silliguri) by road up to site.

Bamboo - Local

Earth - Private land from 1000m lead.

- (B) Rate** - Carriage has been analyzed on minimum lead. Finished rate has been calculated without contractor's profit on MORD norms. Carriage of materials has been added to finished rate. Basic Rates are evaluated from rates approved by State schedule rate committee. 12% GST & 1% Labour cess has been added in the estimate in abstract part.


Sanction of estimate is much needed for payment of the work which was already done.

  
14/12/20

J.E  
R.W.D  
Kishanganj-I

  
14/12/20

A.E  
R.W.D  
Kishanganj-I

  
14/12

E.E  
R.W.D  
Kishanganj-I

Inspection Report for Flood damage work

Date:

1. Name of PIUs- Executive Engineer Kishangemj-1  
2. Name of Block/Road- Kishangemj / PIRUBSY Road to Boma  
Basti ward no. 7

**A. For Road**


1. Damage Location/Chainage :  
2. Damage Length : 45m .  
3. Nature of Damage : Flood  
4. Details of Restoration :  
i Material being used in Restoration : Bamboo, Sandbags, B. bag  
ii Equipment/Tools being used in Restoration works: Tractor  
iii Procedure taken up in Restoration works : Manually  
iv Restored Length : 45m

**B. For Bridge**

1. Damage Location/Chainage :  
2. Damage Length :  
3. Nature of Damage :  
4. Details of Restoration :  
i Material being used in Restoration :  
ii Equipment/Tools being used in Restoration works:  
iii Procedure taken up in Restoration works :  
iv Restored Length :

  
Signature of JE/AF/EE

  
14/12/20

  
14/12

  
Signature

(Name of Inspector)

# **Detailed Estimate**

**PMGSY Road to Boma basti ward no. 7**

Sl No	Item	No	Length	Width	Height	Qty	Unit	Rate	Amount		
1	Providing and cutting of 62 mm to 75 mm dia bamboo piles to size and making shoes, all complete job — E/I	50	1.50	-	-	75.00					
		30	1.65	-	-	49.50					
		Total						124.50	sqm	50.20	6250.00
2	Providing and filling empty cement bags with local sand, stitching the bags and placing including supply of sutli etc. all complete job — E/I	1	15.00	0.80	1.20	14.40					
		1	30.00	1.25	0.80	30.00					
		Total						44.40	cum		
=						1567.99 cft	Say	1307.00	Nos	38.14	49949.00
3	Providing laying and spreading brick bats in Road ditches all complete as per approved design, specifications and direction of E/I	1	15.00	2.10	0.90	28.35					
		1	30.00	2.15	1.30	83.85					
		Total						112.20	cum	2145.02	240671.00
TOTAL									296770.00		
								Add 12 % GST	Rs 35612.00		
								Add 1 % L. Ces	Rs 2968.00		
								Total Cost	Rs 335350.00		

5025 Rs 335400/-

*(Signature)*  
JE 14/12/20  
RWD  
Kishanganj-1

*(Signature)*  
14/12/20  
AE  
RWD  
Kishanganj-1

*(Signature)*  
14/12  
EE  
RWD  
Kishanganj - I

Technically approved for ₹ 335400/-

(Rs. Three Lacs <sup>FAE</sup> ~~Thirteen~~ Thousand and ~~four~~

hundred) only

*(Signature)*  
29/1/21