SRAL WORKS DEPARTMENT



GOVERNMENT OF BIHAR

CIRCLE - R.W.D. works Circle, Kishanganj DIVISION - R.W.D. works Division, Kishanganj-1

Name of Work - Restoration of road from T04 to Najarpur

Kochadhaman Block

Estimated cost - Rs 343225.00

Year: 2020-21

TECHNICAL REPORT

Name of Work	- FDR To Road From Tog to Nezes pus.
Head	- FDR
Estimated cost	_ 3-432_ Lacs

The work done estimate has been framed for the restoration (motarable) of traffic for the above road which was damage during the year 2020-2021 flash flood.

(A) Source of materials

Brick Bats - Local Kiln

Fine sand – Local

Cement Bag - Local Market

Aggregate for G.S.B - Matigara (Silliguri) by road up to site.

Bamboo - Local

Earth - Private land from 1000m lead.

(B) Rate - Carriage has been analyzed on minimum lead. Finished rate has been calculated without contractor's profit on MORD norms. Carriage of materials has been added to finished rate. Basic Rates are evaluated from rates approved by State schedule rate committee. 12% GST& 1% Labour cess has been added in the estimate in abstract part.

Sanction of estimate is much needed for payment of the work which was already done.

J.E

R.W.D

Kishanganj-1

R.W.D

Kishanganj-1

R.W.D

Kishanganj-1

Inspection Report for flood damage work

1. Name of PIUS- RWD Kishansans-1.

2. Name of Block/Road- To4 to Hazerbur under Kochatheman block.

A.For Road

Date:

1. Damage Location/Chainage:

2. Damage Lengh

:95.00 m. 3. Nature of Damage : Flank damese and cutting.

4. Details of Restoration

i Material being used in Restoration

ii Equipment/Tools being used in Restoration works: Towards : Bamboo, Boick bath, seand

iii Procedure taken up in Restoration works

iv Restored Length : manual. : 95.00 M.

B. For Bridge

1.Damage Location/Chainage:

2. Damage Lengh

3. Nature of Damage

4. Details of Restoration

i Material being used in Restoration

ii Equipment/Tools being used in Restoration works:

iii Procedure taken up in Restoration works

iv Restored Length

Signature of JE/AE/EE

Signature

(Name of Inspector)

कार्यपालक अभियन्ता ग्रामीण कार्य विभाग कार्य प्रमण्डल, अररिया

Detailed Estimate

Name of work:- Restoration of road from T04 to Najarpur

Name of work :- SI No Item		No	Length	Width	Height	Qnty	Unit	Rate	Amount
	Providing and laying reinforced		2.50	<i>j.</i> -	-	7.50			
	cement concrete pipe NP3 for culverts of 1000 dia, all	0	0.00	-	•	0.00			
	complete jobE/I.				Total	7.50	RM	4781.89	35864.00
	Providing and cutting of 62 mm to 75 mm dia bamboo piles to size and making shoes, all complete jobE/I		2.00		-	112.00			
			2.50	-	-	125.00			
					Total	237.00	RM	50.20	11897.00
3	Providing and filling empty cement bags with local sand,	1	50.00	0.85	1.50	63.75			
			45.00	0.80	1.25	45.00			
	stitching the bags and placing including supply of sutli etc. all complete jobE/I		-l		Total	108.75	cum		
			3840.	51 cft	Say	3200.00	Nos	38.14	122048.00
4	Providing laying and spreading brick bats in Road ditches all		50.00	1.15	0.45	25.88			
	complete as per approved	1	45.00	1.25	0.65	36.56			
	design, specifications and direction of E/I				Total	62.44	cum	2145.02	133930.00
	an oction of 2,1							Total:-	
-								@ 12 % :-	Rs 36449.00 Rs 3037.00
	Add LC @ 01 % :- Total cost of Restoration with GST & LC:-								

Saz, Ps. 343200/-

J.E RWD

Kochadhaman

A.E 8 12/20

R.W.D Kochadhaman E.E RWD

R.W.D Kishanganj - I

Technically approved for ₹.3432-0/-

(RS Three Lacs proses thousand and two

hundred Only

अधीक्षण अधियन्ता प्रामीण कार्य विभाग कार्य अंचल, किशनगंज