

TECHNICAL REPORT

Name of Work – FDR To Road From... *Rupani Kamati Tola to Khari Tola Nakh Tola*
Head – FDR
Estimated cost – *2.51719* Lacs

The work done estimate has been framed for the restoration (motarable) of traffic for the above road which was damage during the year 2020-2021 flash flood.

(A) Source of materials

Brick Bats – Local Kiln
Fine sand – Local
Cement Bag – Local Market
Aggregate for G.S.B – Matigara (Silliguri) by road up to site.
Bamboo – Local
Earth – Private land from 1000m lead.

(B) Rate - Carriage has been analyzed on minimum lead. Finished rate has been calculated without contractor's profit on MORD norms. Carriage of materials has been added to finished rate. Basic Rates are evaluated from rates approved by State schedule rate committee. 12% GST & 1% Labour cess has been added in the estimate in abstract part.

Sanction of estimate is much needed for payment of the work which was already done.

[Signature]
10.12.20
J.E
R.W.D
Kishanganj-1

[Signature]
11/12/2020
A.E
R.W.D
Kishanganj-1

[Signature]
13/12/20
E.E
R.W.D
Kishanganj-1

Inspection Report for flood damage work

Date: - 12.12.20

1. Name of PIUs- R.W.D, Kishanganj-I

2. Name of Block/Road- Bahadurganj / Rupani Kamat Talu to Kharitoli Nabton

A. For Road

1. Damage Location/Chainage : 0.800 K.M

2. Damage Length : 30.00M

3. Nature of Damage : Washed out

4. Details of Restoration :

i Material being used in Restoration

: Soil, Sand bags, brick bats

ii Equipment/Tools being used in Restoration works: Tractor

iii Procedure taken up in Restoration works

: Manual

iv Restored Length

: 30.00M

B. For Bridge

1. Damage Location/Chainage :

2. Damage Length :

3. Nature of Damage :

4. Details of Restoration :

i Material being used in Restoration

:

ii Equipment/Tools being used in Restoration works:

:


iii Procedure taken up in Restoration works

:

iv Restored Length

:

N.A


12.12.20
Signature of JE/AE/EE


12/12/2020
RS


12/12/20


12/12/20
Signature


(Name of Inspector)


Detailed Estimate


Name of work :-

Rupani Kamal Tola to Khari Tola Nab Tola

SI No	Item	No	Length	Width	Height	Qty	Unit	Rate	Amount
1	Construction of embankment with approved materials deposited at site from borrow pits with	1	30.00	6.50	1.50	292.50			
						Total	292.50	cum	189.45
									55414.00
2	Providing and filling empty cement bags with local sand, stitching the bags and placing including supply of sutli etc. all complete job ---- E/I	1	30.00	0.90	1.45	39.15			
		1	29.50	0.90	1.55	41.15			
						Total	80.30	cum	
			2835.79 cft		Say	2363.00	Nos	38.14	90125.00
3	Providing laying and spreading brick bats in Road ditches all complete as per approved design, specifications and direction of E/I	1	30.00	4.00	0.30	36.00			
						Total	36.00	cum	2145.02
									77221.00
TOTAL									222760.00
Add GST@12%									26731.00
Add L.C@1%									2228.00
TOTAL -									251719.00



 10/12/20
 J.E.
 R.W.D.
 Bahadurganj-1


 11/12/20
 A.E.
 R.W.D.
 Bahadurganj

Say Rs- 251700/-

 13/12/20
 E.E.
 R.W.D.
 Kishanganj - I

Technically approved for ₹ 251700/-

(Rs. Two Lacs fifty one thousand and seven hundred) only


 25/11/20