

## TECHNICAL REPORT

Name of Work - FDR To Road From *Hybrid Road kashra to Kadam Pased to Sherishana*  
*Tola Eytami Buti.*  
Head - FDR  
Estimated cost - *1.2.62.566*.... Lacs


The work done estimate has been framed for the restoration (motarable) of traffic for the above road which was damage during the year 2020-2021 flash flood.

(A) Source of materials


Brick Bats - Local Kiln  
Fine sand - Local  
Cement Bag - Local Market  
Aggregate for G.S.B - Matigara (Silliguri) by road up to site.  
Bamboo - Local  
Earth - Private land from 1000m lead.

(B) Rate - Carriage has been analyzed on minimum lead. Finished rate has been calculated without contractor's profit on MORD norms. Carriage of materials has been added to finished rate. Basic Rates are evaluated from rates approved by State schedule rate committee. 12% GST & 1% Labour cess has been added in the estimate in abstract part.

Sanction of estimate is much needed for payment of the work which was already done.

  
J.E.  
R.W.D  
Kishanganj-1

  
A.E.  
R.W.D  
Kishanganj-1

  
E.E.  
R.W.D  
Kishanganj-1

Inspection Report for Flood damage work


Date:

1. Name of PIUs- Executive Engineer Kishanganj-1  
2. Name of Block/Road- Kishanganj / Hybrid Road Lehsa do  
A. For Road Kadam Rasool do Sheshawardi Talu  
Futani Barsti


1. Damage Location/Chainage :  
2. Damage Length : 130m.  
3. Nature of Damage : Flood  
4. Details of Restoration :  
i Material being used in Restoration : Bamboo Savelay, Bibub  
ii Equipment/Tools being used in Restoration works: Tractor  
iii Procedure taken up in Restoration works : Manually  
iv Restored Length : 130m.

**B. For Bridge**

1. Damage Location/Chainage :  
2. Damage Length :  
3. Nature of Damage :  
4. Details of Restoration :  
i Material being used in Restoration :  
ii Equipment/Tools being used in Restoration works:  
iii Procedure taken up in Restoration works :  
iv Restored Length :

  
14/12/20  
Signature of JE/AE/EE

  
14/12/20

  
14/12

  
Signature

(Name of Inspector)

# Detailed Estimate

Name of work :-


Hybrid Road Lahra to Kadam Rasool to Shershavadi Tola Futani Basti

SI No	Item	No	Length	Width	Height	Qty	Unit	Rate	Amount
1	Providing and cutting of 62 mm to 75 mm dia bamboo piles to size and making shoes, all complete job —E/I	350	2.50	-	-	875.00			
		65	2.00	-	-	130.00			
		Total				1005.00	sqm	50.20	50451.00
2	Providing, fitting and fixing 62 mm to 75 mm dia bamboo runners in position at every vertical pile with 150 mm long nails or 38 swg G.I. wire	6	100.00	-	-	600.00			
		4	50.00	-	-	200.00			
		Total				800.00	sqm	28.63	22824.00
3	Providing and filling empty cement bags with local sand, stitching the bags and placing including supply of sutl etc. all complete job — E/I	2	100.00	0.85	1.50	255.00			
		2	30.00	0.80	1.25	60.00			
		Total				315.00	cum		
		=	11124.23 cft		Say	9270.00	Nos	38.14	353558.00
4	Providing laying and spreading brick bats in Road ditches all complete as per approved design, specifications and direction of E/I	1	100.00	4.00	0.60	240.00			
		1	30.00	4.20	0.65	81.90			
		Total				321.90	cum	2145.02	890482.00
							TOTAL		1117315.00
							Add 12 % GST		Rs 134078.00
							Add 1 % L. Cess		Rs 11173.00
							Total Cost		Rs 1262566.00

Say, Rs. 1262600/-

  
J.E.  
RWD  
Kishanganj-1


  
A.E.  
R.W.D  
Kishanganj-1

  
E.E.  
R.W.D  
Kishanganj - I

Technically approved for ₹ 1262600/-

(Rs. twelve Lacs sixty two thousand and...

hundred) only

  
25/1/17