

RURAL WORKS DEPARTMENT



GOVERNMENT OF BIHAR

CIRCLE – R.W.D. works Circle, Kishanganj

DIVISION – R.W.D. works Division, Kishanganj-1

Name of Work - MNP sadak chunamari to kaji tola

Block - Kochadhaman

Estimated cost - Rs 4574144.00

Year : 2020-21

Inspection Report for flood damage work

Date:

1. Name of PIUs- ~~PIU~~ Kishanganj-1

2. Name of Block/Road- MNP Sadak chunamari to Kaji tolq

A. For Road

1. Damage Location/Chainage :

2. Damage Length : 1700 m.

3. Nature of Damage :

4. Details of Restoration :

i Material being used in Restoration

ii Equipment/Tools being used in Restoration works:

iii Procedure taken up in Restoration works

iv Restored Length

Damage and deep side cutting

sand, cement bags,
bamboo, brick ball

Tractor

manual

1700 m.

B. For Bridge

1. Damage Location/Chainage :

2. Damage Length :

3. Nature of Damage :

4. Details of Restoration :

i Material being used in Restoration

ii Equipment/Tools being used in Restoration works:

iii Procedure taken up in Restoration works

iv Restored Length


13-12-20
Signature of JE/AF/EE


13/12/20


13/12/20
Signature
कार्यपालक अभियन्ता
(Name of Inspector)
कार्य प्रमण्डल, अररिया

Detailed Estimate

Name of work :-

MNP sadak chunamari to kaji tola

Sl No	Item	No	Length	Width	Height	Qty	Unit	Rate	Amount	
1	Providing and cutting of 62 mm to 75 mm dia bamboo piles to size and making shoes, all complete job -----E/I	15	1.20	-	-	18.00				
		9	1.20	-	-	10.80				
		Total					28.80	RM	50.20	1446.00
2	Providing, fitting and fixing 62 mm to 75 mm dia bamboo runners in position at every vertical pile with 150 mm long nails or 38 swg G.I. wire including cost of G.I. wire or nails complete job as per specification and direction of E/I.	4	10.00	-	-	40.00				
		4	6.00	-	-	24.00				
		Total					64.00	RM	28.53	1826.00
3	Providing and filling empty cement bags with local sand, stitching the bags and placing including supply of sutli etc. all complete as per approved design, specifications and direction of E/I	1	10.00	1.65	2.10	34.65				
		1	6.00	1.50	1.80	16.20				
		Total					50.85			
		=	1795.77 cft		Say	1496.00	Nos	38.14	57057.00	
4	Fillling and spreading local sand over brick bats as per drawing and technical specification Clause 305.3.9	1	1250.00	3.00	0.30	1125.00				
		1	400.00	3.00	0.30	360.00				
		Total					1485.00	cum	626.89	930932.00
5	Providing laying and spreading brick bats in Road ditches all complete as per approved design, specifications and direction of E/I	1	1250.00	3.00	0.30	1125.00				
		1	400.00	3.00	0.25	300.00				
		Total					1425.00	cum	2145.02	3056654.00
Total:-									Rs 4047915.00	
Add GST @ 12 % :-									Rs 485750.00	
Add LC @ 01 % :-									Rs 40479.00	
Total cost of Restoration with GST & LC:-									Rs 4574144.00	

P. J. E
10-12-20

J.E
RWD
Kochadhaman

A. E
10/12/20

A.E
R.W.D
Kochadhaman

E. E
12/12/20

E.E
R.W.D
Kishanganj - I

Technically approved for Rs. 4574144/- (Forty five lakh, seventy four thousand one hundred forty four) only.

[Signature]
25/1/21


अधीक्षण अभियन्ता
ग्रामीण कार्य विभाग
कार्य अंचल, किशनगंज

LEAD CHART

S.L No.	Name of material	Source	Mode of transport	From	To	Lead in K.M		Loading	Unloading	Total Loading + Unloading
						Surface Road	Katcha Road			
1	2		3	4	5	6	7	8	9	10
1	Bricks	Local Kiln	By road	Local Kiln	Site	7	1	203.05	203.05	406.10
2	Fine sand	Local source	By road	Local	Site	2	1	59.43	37.10	96.53
3	Coarse Sand	Chopra	By road	Chopra	Site	80	0	59.43	37.10	96.53
4	Boulder	Siliguri	By road	Siliguri	Site	120	0	118.86	59.43	178.29
6	Stone metal for GSB	Siliguri	By road	Siliguri	Site	120	0	118.86	59.43	178.29
7	Seel	Local	By road	Local	Site	5	0	118.86	59.43	178.29
8	Hume pipe (1000 mm	Purnia	By road	Purnia	Site	90	0	41.62	28.00	69.62
9	Hume pipe (600 mm	Purnia	By road	Purnia	Site	90	0	17.84	12.00	29.84
10	Bamboo 62 to 75 mm	Local	By road	Local	Site	5	5	1,112.00	1,112.00	2,224.00


 J.E
 RWD
 Kishanganj-1


 A.E
 R.W.D
 Kishanganj-1


 E.E
 R.W.D
 Kishanganj - I

FDR 2020
RATE ANALYSIS

Sl. No.	SDB Sl. No.	MORD Ref. No.	DESCRIPTION	Unit	Quantity	Rate	Amount in Rs.
1	302	(i)	Excavation in cutting in soil by manual means with lead up to 50 m Excavation for roadway in soil using manual means for carrying of cut earth to embankment site with a lift upto 1/2 m and lead upto 50 m as per technical specification clause 302.3 Unit = cum Taking output = 120 cum				
		a)	Labour	day	1.80	305.00	549.00
			Mate	day	45.00	267.00	12015.00
			Mazdoor (Unskilled)				
		b)	Overheads @ 6 % on (a)				
		c)	Contractor's profit @ 0% on (a+b)				0.00
		d)	Cost for 120 cum = a+b+c				13,444.00
			Rate per cum = (a+b+c)/120				112.20
			Total Cost	CUM			112.20
2	3.3	301.5	Construction of embankment with material obtained from road way cutting Construction of embankment with approved materials deposited at site and obtained from roadway cutting and excavation from drain and foundation of other structures graded and compacted to meet requirement of Tables 300.1 and 300.2 as per Technical Specification Clause 301.5 Unit = cum Taking output = 100 cum				
		a)	Labour	day	0.02	305.00	6.10
			Mate	day	0.50	287.00	143.50
			Mazdoor (Unskilled)				
		b)	Machinery	hour	0.50	3,337.90	1,668.95
			Dozer D-50 for spreading @ 100 cum per hour	hour	1.00	573.20	573.20
			Tractor mounted grader arrangement for grading @ 100 cum per hour	hour	2.00	184.00	368.00
			Water tanker 6 kl capacity	hour	1.25	803.00	1,003.75
			Three wheel 80-100 kN Static Roller				
		c)	Material	kl	12.00	40.00	480.00
			Water	cum	100.00	34.81	3,481.00
			Compensation for earth				
		d)	Overheads @ 6 % on (a+b+c)				0.00
		e)	Contractor's profit @ 10% on (a+b+c+d)				7,724.50
			Rate for 100 cum = a+b+c+d+e				77.25
			Rate per cum = (a+b+c+d+e)/100=				77.25
			Total Cost	CUM			77.25
			Grand total = 112.2 + 77.25 =	CUM			189.45
3	9.3	1100	Providing and Laying Reinforced Cement Concrete Pipe NP3 as per design in Single Row Providing and laying reinforced cement concrete pipe NP3 for culverts on first class bedding of granular material in single row including fixing collar with cement mortar 1:2 but excluding excavation, protection works, backfilling, concrete and masonry works in head walls and parapets Clause 1106.				
		A.	600 MM DIA Unit = m Taking output = 7.5 m (5 pipes of 2.5 m length each)				
		a)	Material	cum		175.80	0.00
		i) Sand at site	ton			4850.80	0.00
		ii) Cement at site	m	7.50		2075.92	15569.40
		iii) RCC pipe NP 3 pipe including collar at site					
		b)	Labour	day	0.04	305.00	12.20
			Mate	day	0.12	388.00	46.56
			Mason (1st class)	day	0.96	287.00	275.52
			Mazdoor (Unskilled)				
		c)Overheads @6 % on (a+b)					
		d)Contractor's profit @ 0% on (a+b+c)					0.00
		e)	Carriage	cum	0	2107.51	0.00
		i) Sand at site	ton	0		5547.44	0.00
		ii) Cement at site	m	7.50		921.38	6910.35
		iii) RCC pipe NP 3 pipe including collar at site					22814.03
			Cost for 7.5m = (a+b+c)				3041.87
			Rate per m =(a+b+c)/ 7.5				3041.87
			Total	M			3041.87
4	9.3	1100	Providing and Laying Reinforced Cement Concrete Pipe NP3 as per design in Single Row Providing and laying reinforced cement concrete pipe NP3 for culverts on first class bedding of granular material in single row including fixing collar with cement mortar 1:2 but excluding excavation, protection works, backfilling, concrete and masonry works in head walls and parapets Clause 1106.				
		B.	1000 MM DIA				

			Unit =m Taking output =7.5 m (3 pipes of 2.5 m length each) a) Material i) Sand at site ii) Cement at site iii) RCC pipe NP 3 pipe including collar at site Jute b) Labour Fitter Mason (1st class) Mazdoor (Unskilled) c)Overheads @6 % on (a+b) d)Contractor's profit @ 0% on (a+b+c) e) Carriage i) Sand at site ii) Cement at site iii) RCC pipe NP 3 pipe including collar at site Cost for 7.5m = (a+b+c+d) Rate per m =(a+b+c+d)/ 7.5 Total	cum ton m kg day day day day day cum ton m	0 7.50 7.50 1.00 2.00 21.00 0 0 7.50	175.80 4850.80 2758.22 33.66 395.00 388.00 287.00 2107.51 5547.44 1030.28	0.00 0.00 20686.65 252.45 395.00 776.00 6027.00 0.00 0.00 7727.10 35864.20 4781.89 4781.89
5	9.5 (C)	1100	Providing and Laying Reinforced Cement Concrete Pipe NP3 as per Design In Double Row Providing and laying reinforced cement concrete pipe NP3 for culverts on first class bedding of granular material in double row including fixing collar with cement mortar 1:2 but excluding excavation, protection works, backfilling, concrete and masonry works in head walls and parapets as per Clause 1106. C. 2 X 1000 MM DIA Unit =m Taking output =7.5 m (6 pipes of 2.5 m length each in two rows) a) Material i) Sand at site ii) Cement at site iii) RCC pipe NP 3 pipe including collar at site Jute b) Labour Fitter Mason (1st class) Mazdoor (Unskilled) c)Overheads @6 % on (a+b) d)Contractor's profit @ 0% on (a+b+c) e) Carriage i) Sand at site ii) Cement at site iii) RCC pipe NP 3 pipe including collar at site Cost for 7.5m = (a+b+c) Rate per m =(a+b+c)/7.5 Total	cum ton m kg day day day day cum ton m	0 15.00 15.00 2.00 4.00 42.00 0 0 15.00	175.80 4850.80 2758.22 33.66 395.00 388.00 287.00 2107.51 5547.44 1030.28	0.00 0.00 41373.30 504.90 790.00 1552.00 12054.00 0.00 0.00 15454.20 71728.40 9563.79 9563.79
6	WRD 5,740.1		Providing and Placing Sand bags including all material and Labour for filling empty cement bags with local sand, stitching the bags and placing including supply of sutli etc. all complete as per approved design, specifications and direction of E/I Unit :- Taking Out put:- M-159 Cost of E.C. Bags Cost of Sand(100x1.2/35.3)(120Cft) Overheads @ 0% on (a+b+c) Overheads @5 % Carriage of sand For filling & stitching & stacking (Sub analysis below) For Placing (Sub Analysis below) Rate Per % Bags Final Rate Per % Bags Sub Analysis A For filling & stitching & stacking (a) Unskilled mazdoor for filling sand into bags and sewing	Per % nos 100 nos % cum Per % nos cum nos	100 3.40 3.40 2.00	8.46 141.05 306.27 287.00	846.00 482.22 1328.29 1041.32 583.88 861.00 Rs.3814.49 Rs.3814.50 574.00

			b) Suttali						
			c) Overheads @ 0% on (a+b+c)	Kg	0.50	19.75	9.88		
			d) Overheads @ 5 %						
			Cost for 100 nos = a+b+c+d						
			Rate per % Nos =						583.88
			Final Rate For filling & stitching & stacking						583.88
					Per % nos	(a)			Rs.583.88
5.7.40.1.	1	WRD	Labour rate for filling of E.C.Bags with stitching and stacking						
			Sub Analysis						
			B For Placing						
			(a) Unskilled mazdoor for carring filled bags and placing to work site	nos	3	287.00	861.00		
			b) Overheads @0% on (a+b+c)						
			c) Overheads @5 %						
			Cost for 100 nos = a+b+c				861.00		
			Rate per % Nos =				861.00		
			Final Rate						
			Only Labour Charge			Per%Nos	(b)		Rs.861.00
7	5.7.7	WRD	Providing bamboo piles including Labour for cutting 62 mm to 75 mm dia sal bamboo piles to size and making shoes and driving etc. complete job as per specification and direction of E / I.						Rs.1444.00
				Unit :-	Per M				
			Taking Out put:-	30.50	Mtr				
			(Assuming 20 nos pile sunk 1.525 mtr deep)						
			Total depth sunk 30.50 meter						
		(a)	Labour						
			Carpenter Gr II	nos	0.25	345.00	86.25		
			Unskilled mazdoor for pilling	nos	2.5	287.00	717.50		
		(b)	Materials						
			Bamboo 75 mm to 62 mm dia	m	30.5	23.85	727.43		
			Sub total				1531.19		
		(c)	Overheads @5 %	%	15				
			Total for 30.5 Mtr Length				1531.19		
			Rate Per M				50.20		
						Say Rs	Per M		50.20
8	5.7.9	WRD	Supplying fitting and fixing 62mm to 75 mm dia bamboo runners in position at every vertical pile with 150 mm long nails or 38 swg G.I. wire including cost of G.I. wire or nails, all material and Labour complete job as per specification and direction of E / I.						
				Unit :-	Per M				
			Taking Out put:-	30.50	Mtr				
		(a)	Materials						
			Cost of 150 mm long nails	Kg	0.5	55.84	27.92		
			Bamboo 75 mm to 62 mm dia	m	30.5	23.85	727.43		
		(b)	Labour						
			Carpenter Gr II	nos	0.125	345.00	43.13		
			Unskilled mazdoor	nos	0.25	287.00	71.75		
			Sub total				870.22		
		(c)	Overheads @5 %		15 %				
			Total for 30.5 Mtr Length				870.22		
			Rate Per M				28.53		
						Say Rs	28.53 Per M		
9	5.7.8	WRD	Providing fitting and fixing split bamboo woven chachar in position with 20 swg G.I. wire or 75 mm to 100 mm long nails alternatively including cost of G.I. wire or nails, bamboo Labour for complete job as per specification and direction of E / I.						
				Unit :-	Per M ²				
			Taking Out put:-	9.30	Sqm				
			(Assuming strip of 3.05x3.05 = 9.30 sqm)						

		Materials					
		Nails up to 100 mm long nails					
		Bamboo 25 mm to 62 mm dia		Kg	0.25	55.84	14.96
		Bamboo 25 mm x 3050/75 x 40.67 say 41 nos X 3.05 = 125.05m					
		MAJOR LOWER ORDER OF MATERIALS 20 x 30 x 30					
		Runner (@ 150mm C/C) 7 x 3.05 = 21.35m					
		(Total=143.35m, Hence, 176.9/6 = 30 Nos)					
(B)		Labour		m	143.35	23.85	3418.90
		Carpenter Gr II					
		Unskilled mazdoor		nos	1	345.00	345.00
		Sub total		nos	1	287.00	287.00
(c)		Overheads @ 5 %					4064.86
		Total for 9.30 SqM		15	%		4064.86
		Rate Per SqM					437.08
							437.08
10	9.2 (1)	1100 & 800	Sand filling or Type B (First Class) Bedding Laying (First Class) bedding on well compacted sand, moorum or approved granular material as per Clause 1105 (ii) Filling in foundation trenches as per drawing and technical specification Clause 305.3.9 Sand filling Unit = cum	Say Rs	Per M ²		437.08
		a) Labour					
		Mate		day	0.01	305.00	3.05
		Mazdoor (Unskilled)		day	0.30	287.00	86.10
		b) Material					
		Sand (assuming 20 per cent voids)		cum	1.20	141.85	170.22
		c) Overheads @ 6 % on (a+b)					0.00
		d) Overheads @ 5 %					
		<u>CARRIAGE COST</u>					
		sand		Cum	1.2	306.27	367.52
		Rate per cum = a+b+c					625.82
		Total Cost		CUM			625.89
11	WRD	5.7.40	Construction of granular sub base using Jhama metal/ Brick Bat vide WRD Providing and laying dry graded jhama khoa? Brickbat or stone filter under brick pitching or boulder pitching in slope or apron including light ramming etc.all complete job as per specification and direction of E / I. Unit = cum Taking output = 2.832 cum				
		(a) Labour					
		Mazdoor (Unskilled)		day	0.00	305.00	0.00
		Mazdoor (Unskilled)		day	3.00	287.00	861.00
		Sub total of Labour for 2.832 Cum					861.00
		Labour charge for 1.00 cum					304.03
		(b) Material					
		Brick bat		cum	1.200	1,062.00	1,275.60
		(e) Carriage					
		Brick bat		cum	1.200	471.16	565.39
		Cost for 1.00 cum = a+b+c+d+e					2,145.02
		Rate per cum = (a+b+c+d+e)					Rs.2145.02
		Final Rate					Rs.2145.02

C
12/12/20