

## TECHNICAL REPORT

Name of Work - FDR To Road From... *Balwa... Buati... to... Tarabani... via High Bridge.*

Head - FDR

Estimated cost - *7.56.70.9*..... Lacs

The work done estimate has been framed for the restoration (motarable) of traffic for the above road which was damage during the year 2020-2021 flash flood.

**(A) Source of materials**

Brick Bats - Local Kiln

Fine sand - Local

Cement Bag - Local Market

Aggregate for G.S.B - Matigara (Silliguri) by road up to site.

Bamboo - Local

Earth - Private land from 1000m lead.

- (B) Rate** - Carriage has been analyzed on minimum lead. Finished rate has been calculated without contractor's profit on MORD norms. Carriage of materials has been added to finished rate. Basic Rates are evaluated from rates approved by State schedule rate committee. 12% GST & 1% Labour cess has been added in the estimate in abstract part.

Sanction of estimate is much needed for payment of the work which was already done.

*(Signature)*  
J.E  
14/12/20

R.W.D  
Kishanganj-1

*(Signature)*  
A.E  
14/12/20

R.W.D  
Kishanganj-1

*(Signature)*  
E.E  
14/12

R.W.D  
Kishanganj-1

Inspection Report for Flood damage work

Date:

1. Name of PIUs- Executive Engineer Kishangang-1  
2. Name of Block/Road- Kishangang / Below Basti do Tasebasi  
via High Bridge.

**A. For Road**

1. Damage Location/Chainage :  
2. Damage Length : 150m  
3. Nature of Damage : flood  
4. Details of Restoration :  
i Material being used in Restoration : B. buls  
ii Equipment/Tools being used in Restoration works: Tractor  
iii Procedure taken up in Restoration works : Manually  
iv Restored Length : 150m.


**B. For Bridge**

1. Damage Location/Chainage :  
2. Damage Length :  
3. Nature of Damage :  
4. Details of Restoration :  
i Material being used in Restoration :  
ii Equipment/Tools being used in Restoration works:  
iii Procedure taken up in Restoration works :  
iv Restored Length :

  
14/11/20

Signature of JE/AF/EE

  
14/11/20

  
14/11/20

  
14/11/20

Signature


(Name of Inspector)


### Detailed Estimate

Name of work :-

Belwa Basti to Tarabari via High Bridge

SI No	Item	No	Length	Width	Height	Qty	Unit	Rate	Amount
1	Providing laying and spreading brick bats in Road ditches all complete as per approved design, specifications and direction of E/I	1	55.00	4.25	0.65	151.94			
		1	20.00	3.25	0.85	55.25			
		1	75.00	2.80	0.50	105.00			
		Total					312.19	cum	2145.02
TOTAL								669654.00	
							Add 12 % GST	Rs 80358.00	
							Add 1 % L. Ces	Rs 6697.00	
							Total Cost	Rs 756709.00	

  
J.E. 14/11/20  
RWD  
Kishanganj-1

  
A.E. 14/11/20  
R.W.D  
Kishanganj-1


SAY RS. 756700/-

  
E.E. 14/11/20  
R.W.D  
Kishanganj - I

Technically approved for ₹.....756700/-

(Rs. Seven Lacs Fifty six thousand and seven)

Amount only

  
25/11/20