

Name of work :

Situation of Work-

Agency by which work is executed-

Date of measurement.

No. and date of agreement

(These four lines should be repeated at the commencement of the measurements relating to each work.)

Particulars	Details of actual measurement				Contents of area
	No.	L.	B.	D.	
FIRST		R/AC	BILL		
Name of the work:					
Construction of Road Telpur					
To Telpur Deoraj Under					
MMGSY (SC).					
Agreement No: 52 SBD/ 20-21					

Name of Agency:					
New Blue Star Construction,					
At - Kandhualiya, P.S. - Lauriya					
West Champaran.					
Agreement Value: Rs. 8435688.00					
Date of work order: 14-01-2021					
Time of Completion: 13-10-2021					
MEASUREMENT					
Item No-1/1					
Construction of Reference &					
Working bench mark - T/S					
Continuation					
0.95 Km					

Item	No - 4/3			
Cleaning and grubbing road land				T/S
$2 \times 31 \times 30.00 \times \left( \frac{1.55 + 1.45}{2} \right) = 2790.00$				
$2 \times 1 \times 20.00 \times \left( \frac{1.52 + 1.48}{2} \right) = 60.00$				
				2850.00 m <sup>2</sup>
				= 0.29 H
Item	No - 5/9			
Construction of granular sub sub grade				F/S
$1 \times 12 \times 30.00 \times \left( \frac{8.20 + 8.00}{2} \right) \times 0.30$				
Continuation				
				= 874.80 m <sup>3</sup>
$1 \times 1 \times 9.00 \times 7.98 \times 0.30 = 21.55 \text{ m}^3$				



## Sch. XLV-Form No. 134

Particulars	Details of actual measurement				Contents of area
	No.	L.	B.	D.	
ABSTRACT OF COST					
Item No- 1/1					
Construction of reference and working bench mark					T/S
From T. M. B. page no - 1					
				Qty = 0.95 Km	
				@ Rs. 8659.59/Km	
				= Rs. 8227.00	
Item No- 2/2					
Construction of reference pillar					T/S

From T. M. B. page no - 2					
				Qty = 0.95 Km	
				@ Rs. 4778.51/Km	
				= Rs. 4540.00	

Item No- 3/3					
Clearing and grubbing road land					T/S

From T. M. B. page no - 2					
				Qty = 0.29 H	
				@ Rs. 51133.76/H	
				= Rs. 14829.00	

## Sch. XLV-Form No. 134

Particulars	Details of actual measurement				Contents of area
	No.	L.	B.	D.	
Item No- 4/5.					
Construction of sub grade					
From T. M. B. page no- 3					
					Qty = 1745.23m <sup>3</sup>
					@ Rs. 204.16/m <sup>3</sup>
					= Rs. 356306.00
Item No- 5/9					
Construction of G.S. B.					
From T. M. B. page no- 3					
					Qty = 676.59m <sup>3</sup>

@ Rs. 3172.76/m<sup>3</sup>

= Rs. 2151394.80

Item No- 6/23  
Providing and fixing of  
typical MMGSY informatory  
sign board ———— T/S

From T. M. B. page no- 2  
Qty = 2 Each  
@ Rs. 12574.80/No  
= Rs. 25149.60

Rs. 2560445.00

Add G.S.T. @ 12% = Rs. 307253.00

Add L.C @ 1% = Rs. 25604.00

Rs. 2893302.00

Continuation

less for below @ 0.03% = Rs. 868.00

Rs. 2892434.00

Sanjay K.  
10-03-2021  
J.E.



Name of Agency: - New Blue Star Construction, AT- Kandhwaliya, P.S Lauriya,  
West Chaparan

Name of Work: - Construction of Road Telpur To Telpur Deorai  
Under MMGSY (SC)

Agreement no.: - 523BD/20-21

Rate approved by C.E. 03 RWD Bihar Patna.

Letter No. 7308 (encl) Date 12.09.2020.

Agreement value :- ₹ 8435688=00 Eighty-four Lakh Thirty-five  
Thousand Six Hundred Eighty-eight Only

Date of work order :- 14.01.2021

Time of Completion :- 13.10.2021

Performance Security :- } ₹ 1,90,000=00 One Lakh Ninety Thousand only  
Additional Performance Guarantee :- }

Security Deduct from bill :- 8%.

No of Items :- 44 as per (B.O.D) for Const.

Rate :- 0.03% (Zero point zero Three Percent) Below

NEW BLUE STAR CONSTRUCTION  
92115547  
Managing Partner

Mot N

Executive Engineer  
R.W.D. (W) Division  
Bagaha-1  
14.1.21



एक हजार रुपये

रु.1000

ONE THOUSAND RUPEES

Rs.1000



2010-11-3-20-1000/- वाराणसी जिला - न्यायिक लार्जर फॉर्म - एन.डी. 62  
बिहार BIHAR कान्धवाली - न्यायिक - AH 689091

Standard Form: Agreement

### Agreement

This agreement made the 14<sup>th</sup> Day of January 2021  
Between Executive Engineer RWD (W) Division Bagaha-1 [name and address of Employer]  
(Hereinafter called "the Employer" of the one part, and New Blue Star Construction  
At - Kandhwaliya P.S. - Lauriya, west Champaran.

[Name and address of Contractor (hereinafter called "the Contractor" of the other part).  
Whereas the Employer is desirous that the Contractor execute Const. & Maint. of road under  
M.M.S.U. (SC) from Telpur to Telpur Deo nij. [Name and  
identification number of Contract] (Hereinafter called "the Works") and Employer has accepted the Bid  
by the Contractor for the execution and completion of such Works and the remedying of nay defects  
therein at a cost of Rupees 8435688 = 84,35,688 Eighty four lakh Thirty five Thousand Six Hundred and Eighty -  
Eight only.

NOW THIS AGREEMENT WITNESSETH as follows:

1. In this Agreement, words and expression shall have the same meanings as are respectively assigned to them in the Conditions of Contract hereinafter referred to, and they shall be deemed to form and be read and construed as part of this Agreement.
2. In consideration of the payments to be made by the employer to the Contractor as hereinafter Mentioned the Contractor hereby covenants with the Employer to execute and complete the Works and remedy and defects therein in conformity in all aspects with the provisions of the Contract.
3. The Employer hereby covenants to pay the Contractor in consideration of the execution and completion of the Works and the remedying the defects wherein the Contract Price of such other sum as may become payable under the provisions of the Contract at the time and in the manner prescribed by the Contract.

NEW BLUE STAR CONSTRUCTION

प्रधान कार्यकारी  
Managing Partner

Executive Engineer  
R.W.D. (W) Division  
Bagaha-1

14/1/2021