



# ग्रामीण कार्य विभाग

Rural Works Department, Govt of Bihar

## DETAILED PROJECT REPORT FOR REPAIRING OF ROAD

F.D.R. PART - A (2020)

L049 T04 TO RASIYA (VR49) BRIDGE PAR T04 TO RASIYA  
ROAD KE 7TH KM (DIVERSION)

### DETAILED ESTIMATE OF F.D.R. REPAIRING ROAD

ROAD LENGTH	0 TO 59.42		
DISTRICT	KISHANGANJ		
BLOCK	THAKURGANJ		
DIVISION	KISHANGANJ - 2		
TOTAL LENGTH OF ROAD	0.059	KM	
TOTAL COST OF F.D.R. PART - A	Rs. 11.832	Lacs	
ADD G.S.T @ 12%	Rs. 1.420	Lacs	
Add Seigniorage Fee @ 10 %	Rs. 0.386	Lacs	
TOTAL COST OF RESTORATION WORK In Rs.	Rs. 13.639	Lacs	

SUBMITTED BY  
The Executive Engineer,  
Works Division, Kishanganj - 2

Inspection Report for flood damage work

Date: 12.12.2020

1. Name of PIUs- E.E, RWD (W) Div. Kishanganj-2

2. Name of Block/Road- Thakmargaj/ 1049-704 TO Rasiya (VR 49) Bridge  
Par 704 TO Rasiya Road ke 7th  
km (Diversion)

**A. For Road**

1. Damage Location/Chainage :

2. Damage Length :

3. Nature of Damage :

4. Details of Restoration :

i Material being used in Restoration :

ii Equipment/Tools being used in Restoration works:

iii Procedure taken up in Restoration works :

iv Restored Length :

N.A.

**B. For Bridge**

1. Damage Location/Chainage : 0.0 km

2. Damage Length : 109.60 M

3. Nature of Damage : Bridge diversion


4. Details of Restoration :


i Material being used in Restoration : Local sand & bales/bags.


ii Equipment/Tools being used in Restoration works: Tractor & JCB

iii Procedure taken up in Restoration works :

iv Restored Length : 109.60 M

  
Signature of JE/AE/EE

  
12/12/2020  
AE

  
12/12/20

  
Signature  
(Name of Inspector)

## TECHNICAL REPORT

Name of Work - FDR To Road From Lolig Fdy to Rasiga (VR49) Bridge Par Toy  
Head - FDR to Rasiga Road KE 7+R KM.  
Estimated cost - ..... 13.639 Lacs

The work done estimate has been framed for the restoration (motarable) of traffic for the above road which was damage during the year 2020-2021 flash flood.

### (A) Source of materials

Brick Bats - Local Kiln

Fine sand - Local

Cement Bag - Local Market


Aggregate for G.S.B - Matigara (Silliguri) by road up to site.

Bamboo - Local


Earth - Private land from 1000m lead.

(B) Rate - Carriage has been analyzed on minimum lead. Finished rate has been calculated without contractor's profit on MORD norms. Carriage of materials has been added to finished rate. Basic Rates are evaluated from rates approved by State schedule rate committee. 12% GST & 1% Labour cess has been added in the estimate in abstract part.

Sanction of estimate is much needed for payment of the work which was already done.

  
J.E.  
R.W.D  
Kishanganj-2

  
A.E.  
R.W.D  
Kishanganj-2

  
R.W.D  
Kishanganj-2

**GENERAL ABSTRACT OF COST FOR MAINTENANCE OF ROAD**

NAME OF ROAD : L049 T04 TO RASIYA (VR49) BRIDGE PAR T04 TO RASIYA ROAD KE 7TH  
KM (DIVERSION)  
DISTRICT KISHANGANJ  
DIVISION KISHANGANJ - 2  
BLOCK THAKURGANJ  
LENGTH OF ROAD (IN KM) 0.059

Sl. No.	ITEM OF WORK	AMOUNT (LAKHS)
1	EARTH WORK	6.165
2	BRICK BAT	5.667
3	G.S.B.	0.000
4	SAND BAG	0.000
5	BAMBOO WORK	0.000
4	HUME PIPE	0.000
TOTAL COST OF PROJECT =		11.832
Add G.S.T. @ 12%		1.42
Add Seigniorage Fee @ 10 %		0.386
Total Cost of Restoration Work =		13.639

*SKM*  
12/12/20  
JE  
RWD

*huf*  
12/12/20  
AE  
RWD

*SP*  
12/12/20  
EE  
RWD

Technically Approved For Rs. 13.639 Lacs. (Thirteen  
Lac Sixty three thousand Nine hundred) only.

*SP*  
30/12/20  
अधीक्षण अभियन्ता  
ग्रामीण कार्य विभाग  
कार्य अंचल, किशनगंज