



ग्रामीण कार्य विभाग

Rural Works Department, Govt of Bihar

DETAILED PROJECT REPORT FOR REPAIRING OF ROAD

F.D.R. PART - A (2020)

PAWAKHALI T04 2 KM VADRANI RCC BRIDGE

PAWAKHALI TO 2 KM TO VADRANI PATH

DETAILED ESTIMATE OF F.D.R. REPAIRING ROAD

ROAD LENGTH	0 TO 117	
DISTRICT	KISHANGANJ	
BLOCK	THAKURGANJ	
DIVISION	KISHANGANJ - 2	
TOTAL LENGTH OF ROAD	0.117	KM
TOTAL COST OF F.D.R. PART - A	Rs. 7.012	Lacs
ADD G.S.T @ 12%	Rs. 0.841	Lacs
Add Seigniorage Fee @ 10 %	Rs. 0.199	Lacs
TOTAL COST OF RESTORATION WORK In Rs.	Rs. 8.052	Lacs

SUBMITTED BY
The Executive Engineer,
Works Division, Kishanganj - 2

Inspection Report for flood damage work

Date: 12-12-2020

1. Name of PIUs- E.E, RWD (W) Div. Kishungay-2

2. Name of Block/Road- Thakungay / Pawakhali to 2 km Vadraani Rce.
Bridge Pawakhali to 2 km to Vadraani
Path.

A. For Road

1. Damage Location/Chainage :

2. Damage Length :

3. Nature of Damage :

4. Details of Restoration :

i Material being used in Restoration :

ii Equipment/Tools being used in Restoration works:

iii Procedure taken up in Restoration works :

iv Restored Length :

N.A.

B. For Bridge

1. Damage Location/Chainage : 90M

2. Damage Length : 30M

3. Nature of Damage : Diversions.

4. Details of Restoration :

i Material being used in Restoration

ii Equipment/Tools being used in Restoration works:

iii Procedure taken up in Restoration works

iv Restored Length

: Humapipe, sand filling, Boj/c bats.

: Tractor

: 93.70M

Signature of JE/AE/EE
12/12/20

12/12/20
AE

12/12/20

Signature

(Name of Inspector)

TECHNICAL REPORT

Name of Work - FDR To Road From... *Pawakhali To 2KM Vadhani RCE Bridge*
Pawakhali to 2KM to Vadhani Path.
Head - FDR
Estimated cost - *08.052* Lacs

The work done estimate has been framed for the restoration (motorable) of traffic for the above road which was damage during the year 2020-2021 flash flood.

(A) Source of materials

Brick Bats - Local Kiln

Fine sand - Local

Cement Bag - Local Market

Aggregate for G.S.B - Matigara (Silliguri) by road up to site.

Bamboo - Local

Earth - Private land from 1000m lead.

(B) Rate - Carriage has been analyzed on minimum lead. Finished rate has been calculated without contractor's profit on MORD norms. Carriage of materials has been added to finished rate. Basic Rates are evaluated from rates approved by State schedule rate committee. 12% GST & 1% Labour cess has been added in the estimate in abstract part.

Sanction of estimate is much needed for payment of the work which was already done.

[Signature]
J.E
R.W.D
Kishanganj-2

[Signature]
11/12/20
A.E
R.W.D
Kishanganj-2

[Signature]
E.E
R.W.D
Kishanganj-2

GENERAL ABSTRACT OF COST FOR MAINTENANCE OF ROAD

NAME OF ROAD : PAWAKHALI T04 2 KM VADRANI RCC BRIDGE PAWAKHALI TO 2 KM TO VADRANI PATH
DISTRICT KISHANGANJ
DIVISION KISHANGANJ - 2
BLOCK THAKURGANJ
LENGTH OF ROAD (IN KM) 0.117

Sl. No.	ITEM OF WORK	AMOUNT (LAKHS)
1	EARTH WORK	3.912
2	BRICK BAT	2.918
3	G.S.B.	0.000
4	SAND BAG	0.000
5	BAMBOO WORK	0.000
4	HUME PIPE	0.182
TOTAL COST OF PROJECT =		7.012
Add G.S.T. @ 12%		0.841
Add Seigniorage Fee @ 10 %		0.199
Total Cost of Restoration Work =		8.052

[Signature]
12/12/20
JE
RWD

[Signature]
12/12/20
AE
RWD

[Signature]
12/12/20
EE
RWD

Technically Approved For Rs. 8.052 Lacs (Eight Lac five thousand two hundred) only.

[Signature] 30/11/20
अधीक्षण अभियन्ता
ग्रामीण कार्य विभाग
कार्य अंचल, किशनगंज