



ग्रामीण कार्य विभाग

Rural Works Department, Govt of Bihar

DETAILED PROJECT REPORT FOR REPAIRING OF ROAD

F.D.R. PART - A (2020)

T04 KE 7 TH KM SABODANGI RCC BRIDGE TO T04 KE 7 TH KM SABODANGI ROAD (DIVERSION)

DETAILED ESTIMATE OF F.D.R. REPAIRING ROAD

ROAD LENGTH	0 TO 140		
DISTRICT	KISHANGANJ		
BLOCK	THAKURGANJ		
DIVISION	KISHANGANJ - 2		
TOTAL LENGTH OF ROAD		0.140	KM
TOTAL COST OF F.D.R. PART - A		Rs. 19.230	Lacs
ADD G.S.T @ 12%		Rs. 2.308	Lacs
Add Seigniorage Fee @ 10 %		Rs. 1.168	Lacs
TOTAL COST OF RESTORATION WORK In Rs.		Rs. 22.706	Lacs

SUBMITTED BY
The Executive Engineer,
Works Division, Kishanganj - 2

Inspection Report for flood damage work

Date: 11.12.2020

1. Name of PIUs- E.E. RWD (W) Div - Kishnarganj-2

2. Name of Block/Road- Thakurganj / 7th KM Sabodange RCC
Bridge to 7th KM Sabodange
Road (Diversion)

A. For Road

1. Damage Location/Chainage :

2. Damage Length :

3. Nature of Damage :

4. Details of Restoration :

i Material being used in Restoration :

ii Equipment/Tools being used in Restoration works:

iii Procedure taken up in Restoration works :

iv Restored Length :

} N.A.

B. For Bridge

1. Damage Location/Chainage : 0.11M

2. Damage Length : 165M

3. Nature of Damage : Bridge diversion


4. Details of Restoration :

i Material being used in Restoration : Humapipe, Local sand, Bojolebaks.


ii Equipment/Tools being used in Restoration works:

iii Procedure taken up in Restoration works :

iv Restored Length : 165.11M


Signature of JE/AE/EE


11/12/2020
AE


12.12.20


Signature

(Name of Inspector)

TECHNICAL REPORT

Name of Work - FDR To Road From... To 4 KE 7th KM Sabodangi Rec Bridge
to To 4 KE 7th KM Sabodangi Road (diversion)
Head - FDR
Estimated cost - 22.706 ... Lacs

The work done estimate has been framed for the restoration (motorable) of traffic for the above road which was damage during the year 2020-2021 flash flood.

(A) Source of materials

Brick Bats - Local Kiln

Fine sand - Local

Cement Bag - Local Market


Aggregate for G.S.B - Matigara (Silliguri) by road up to site.


Bamboo - Local


Earth - Private land from 1000m lead.

(B) Rate - Carriage has been analyzed on minimum lead. Finished rate has been calculated without contractor's profit on MORD norms. Carriage of materials has been added to finished rate. Basic Rates are evaluated from rates approved by State schedule rate committee. 12% GST & 1% Labour cess has been added in the estimate in abstract part.

Sanction of estimate is much needed for payment of the work which was already done.


J.E.
R.W.D
Kishanganj-2


A.E.
R.W.D
Kishanganj-2


E.E.
R.W.D
Kishanganj-2

GENERAL ABSTRACT OF COST FOR MAINTENANCE OF ROAD

NAME OF ROAD : T04 KE 7 TH KM SABODANGI RCC BRIDGE TO T04 KE 7 TH KM
SABODANGI ROAD (DIVERSION)
DISTRICT KISHANGANJ
DIVISION KISHANGANJ - 2
BLOCK THAKURGANJ
LENGTH OF ROAD (IN KM) 0.140

Sl. No.	ITEM OF WORK	AMOUNT (LAKHS)
1	EARTH WORK	0.000
2	BRICK BAT	17.129
3	G.S.B.	0.000
4	SAND BAG	0.000
5	BAMBOO WORK	0.000
4	HUME PIPE	2.101
TOTAL COST OF PROJECT =		19.230
Add G.S.T. @ 12%		2.308
Add Seigniorage Fee @ 10 %		1.168
Total Cost of Restoration Work =		22.706

[Signature]
10/12/20
JE
RWD

[Signature]
11/12/20
AE
RWD

[Signature]
12/12/20
EE
RWD

Technically Approved for Rs. 22.706 Laes (Twenty two Laes Seventy thousand Six hundred) only.

[Signature]
30/12/20
अधीक्षण अभियन्ता
ग्रामीण कार्य विभाग
कार्य अंचल, किशनगंज