



ग्रामीण कार्य विभाग

Rural Works Department, Govt of Bihar

DETAILED PROJECT REPORT FOR REPAIRING OF ROAD

F.D.R. PART - A (2020)

BALESHWAR FORM TO ADIVASHI TOLA

DETAILED ESTIMATE OF F.D.R. REPAIRING ROAD

ROAD LENGTH	0 TO 1500		
DISTRICT	KISHANGANJ		
BLOCK	THAKURGANJ		
DIVISION	KISHANGANJ - 2		
TOTAL LENGTH OF ROAD		1.500	KM
TOTAL COST OF F.D.R. PART - A		Rs. 4.894	Lacs
ADD G.S.T @ 12%		Rs. 0.587	Lacs
Add Seigniorage Fee @ 10 %		Rs. 0.379	Lacs
TOTAL COST OF RESTORATION WORK In Rs.		Rs. 5.860	Lacs

SUBMITTED BY
The Executive Engineer,
Works Division, Kishanganj - 2

Inspection Report for flood damage work

Date: 11/12/2020

1. Name of PIUs- Executive Engineer RWD, work Div. Kishanganj - 2

2. Name of Block/Road- Thakurganj / Baleshwar from to Aadiyashi Tola.

A. For Road

1. Damage Location/Chainage : 820 m.

2. Damage Length : 13.6 m.

3. Nature of Damage : Culvert damage in Approach, Floor protection

4. Details of Restoration :

i Material being used in Restoration :

Sand Bag, Brick Bat, Bamboo

ii Equipment/Tools being used in Restoration works: Tractor

iii Procedure taken up in Restoration works :

iv Restored Length : 13.6 m

B. For Bridge

1. Damage Location/Chainage :

2. Damage Length :

3. Nature of Damage :

4. Details of Restoration :

i Material being used in Restoration :

ii Equipment/Tools being used in Restoration works:

iii Procedure taken up in Restoration works :

iv Restored Length :

NA

Signature of JE/AE/EE

11/12/2020

11/12/2020
AE

12/1/2021

Signature

(Name of Inspector)

TECHNICAL REPORT

Name of Work - FDR To Road From Balashwar Form to Adivashi Tola
Head - FDR
Estimated cost - 05.860 Lacs

The work done estimate has been framed for the restoration (motarable) of traffic for the above road which was damage during the year 2020-2021 flash flood.

(A) Source of materials

Brick Bats - Local Kiln
Fine sand - Local
Cement Bag - Local Market
Aggregate for G.S.B - Matigara (Silliguri) by road up to site.
Bamboo - Local
Earth - Private land from 1000m lead.

(B) Rate - Carriage has been analyzed on minimum lead. Finished rate has been calculated without contractor's profit on MORD norms. Carriage of materials has been added to finished rate. Basic Rates are evaluated from rates approved by State schedule rate committee. 12% GST & 1% Labour cess has been added in the estimate in abstract part.

Sanction of estimate is much needed for payment of the work which was already done.

Amor
11/12/20

J.E
R.W.D
Kishanganj-2

Amul
11/12/2020

A.E
R.W.D
Kishanganj-2

Q-S
12/1/20

E.E
R.W.D
Kishanganj-2

GENERAL ABSTRACT OF COST FOR MAINTENANCE OF ROAD

NAME OF ROAD : BALESHWAR FORM TO ADIVASHI TOLA
DISTRICT KISHANGANJ
DIVISION KISHANGANJ - 2
BLOCK THAKURGANJ
LENGTH OF ROAD (IN KM) 1.500

Sl. No.	ITEM OF WORK	AMOUNT (LAKHS)
1	EARTH WORK	0.000
2	BRICK BAT	3.260
3	G.S.B.	0.000
4	SAND BAG	1.569
5	BAMBOO WORK	0.065
4	HUME PIPE	0.000
TOTAL COST OF PROJECT =		4.894
Add G.S.T. @ 12%		0.587
Add Selgniorage Fee @ 10 %		0.379
Total Cost of Restoration Work =		5.860

Amrsv.
10/12/20
JE
RWD

Amrsv.
11/12/20
AE
RWD

Amrsv.
12/12/20
EE
RWD

Technically Approved For Rs. 5.860 Laes. (Five Laes eighty six thousand) only .

Amrsv.
30/12/20
अधीक्षण अभियन्ता
ग्रामीण कार्य विभाग
कार्य अंचल, किशनगंज