



ग्रामीण कार्य विभाग

Rural Works Department, Govt of Bihar

DETAILED PROJECT REPORT FOR REPAIRING OF ROAD

F.D.R. PART - A (2020)

TARAWARI MAHESHPUR TO PAURABHITTA VIA
HARJARI KAMAARDANGI TAK

DETAILED ESTIMATE OF F.D.R. REPAIRING ROAD

ROAD LENGTH	0 TO 3000		
DISTRICT	KISHANGANJ		
BLOCK	THAKURGANJ		
DIVISION	KISHANGANJ - 2		
TOTAL LENGTH OF ROAD		3.000	KM
TOTAL COST OF F.D.R. PART - A		Rs. 21.091	Lacs
ADD G.S.T @ 12%		Rs. 2.531	Lacs
Add Seigniorage Fee @ 10 %		Rs. 1.494	Lacs
TOTAL COST OF RESTORATION WORK In Rs.		Rs. 25.116	Lacs

SUBMITTED BY
The Executive Engineer,
Works Division, Kishanganj - 2

Inspection Report for flood damage work

Date: 11.12.2020

1. Name of PIUs- E.E., RWD (W) Div. Kishanganj-2

2. Name of Block/Road- Thakurganj / Tarawan Maheshpur to Paurabahi
Via Harjari Ramardangi, Tak.

A. For Road

1. Damage Location/Chainage : 150M, 200M, 2105M

2. Damage Length : 78.30 M

3. Nature of Damage : culvert damage & flank coast

4. Details of Restoration :

i Material being used in Restoration

: Bamboo, Sandbags, H.Pipe, Bolekbecks.

ii Equipment/Tools being used in Restoration works: Tractor

iii Procedure taken up in Restoration works :

iv Restored Length : 78.30 M

B. For Bridge

1. Damage Location/Chainage :

2. Damage Length :

3. Nature of Damage :

4. Details of Restoration :

i Material being used in Restoration :

ii Equipment/Tools being used in Restoration works:

iii Procedure taken up in Restoration works :

iv Restored Length :

N.A.

Signature of JE/AE/EE

Signature

(Name of Inspector)

TECHNICAL REPORT

Name of Work - FDR To Road From... *Tarawari Maheshpur to Paurabhiha Via*
Harjari Kamardangi Tar.
Head - FDR
Estimated cost - *25.11.6* Lacs

The work done estimate has been framed for the restoration (motorable) of traffic for the above road which was damage during the year 2020-2021 flash flood.

(A) Source of materials

Brick Bats - Local Kiln
Fine sand - Local
Cement Bag - Local Market
Aggregate for G.S.B - Matigara (Silliguri) by road up to site.
Bamboo - Local
Earth - Private land from 1000m lead.

(B) Rate - Carriage has been analyzed on minimum lead. Finished rate has been calculated without contractor's profit on MORD norms. Carriage of materials has been added to finished rate. Basic Rates are evaluated from rates approved by State schedule rate committee. 12% GST & 1% Labour cess has been added in the estimate in abstract part.

Sanction of estimate is much needed for payment of the work which was already done.

[Signature]
J.E
R.W.D
Kishanganj-2

[Signature]
A.E
R.W.D
Kishanganj-2

[Signature]
E.E
R.W.D
Kishanganj-2

GENERAL ABSTRACT OF COST FOR MAINTENANCE OF ROAD

NAME OF ROAD : TARAWARI MAHESHPUR TO PAURABHITTA VIA HARJARI KAMAARDANGI
TAK
DISTRICT KISHANGANJ
DIVISION KISHANGANJ - 2
BLOCK THAKURGANJ
LENGTH OF ROAD (IN KM) 3.000

Sl. No.	ITEM OF WORK	AMOUNT (LAKHS)
1	EARTH WORK	0.000
2	BRICK BAT	15.205
3	G.S.B.	0.000
4	SAND BAG	4.568
5	BAMBOO WORK	0.395
4	HUME PIPE	0.924
TOTAL COST OF PROJECT =		21.091
Add G.S.T. @ 12%		2.531
Add Seigniorage Fee @ 10 %		1.494
Total Cost of Restoration Work =		25.116

[Signature]
JE
RWD

[Signature]
AE
RWD

[Signature]
EE
RWD

Technically Approved For Rs. 25.116 Lacs. (Twenty five Lacs eleven thousands six hundred) only.

[Signature]
अधीक्षक अभियन्ता
ग्रामीण कार्य विभाग
काय अंचल, किशनगंज