



# ग्रामीण कार्य विभाग

Rural Works Department, Govt of Bihar

WORK CIRCLE :- KISHANGANJ

WORK DIVISION :- KISHANGANJ-2


BLOCK :- DIGHALBANK

FLOOD DAMAGE REPAIR (F.D.R)

EMERGENT TEMPORARY RESTORATION WORK 2020-21

NAME OF ROAD :- HARIBHITTA TO DUBBA TOLI

|                                     |   |    |           |   |            |
|-------------------------------------|---|----|-----------|---|------------|
| CONSTRUCTION COST                   | = | Rs | 752616.00 | = | 7.526 LACS |
| GST 12%                             | = | Rs | 90314     | = | 0.903 LACS |
| LABOUR CESS 1%                      | = | Rs | 7526      | = | 0.075 LACS |
| SEIGNORAGE FEE 10% OF MATERIAL COST | = | Rs | 25603     | = | 0.256 LACS |
| ESTIMATED COST                      | = | Rs | 876059    | = | 8.761 LACS |



SUBMITTED BY :-

EXECUTIVE ENGINEER  
RURAL WORKS DEPARTMENT  
WORK DIVISION KISHANGANJ-2

NAME OF ROAD :- HARIBHITTA TO DUBBA TOLI

कार्य प्रमंडल :- ग्रामीण कार्य विभाग कार्य प्रमंडल  
किशनगंज -2

प्रखण्ड :- दिघलबैंक

## प्रतिवेदन

सचिव, ग्रामीण कार्य विभाग बिहार, पटना के पत्रांक 2521 दिनांक 05-08-2020 के निदेशानुसार बाढ़ / अतिवृष्टि से क्षतिग्रस्त पथों की आपातकालीन मरम्मत कर अविलंब यातायात को पुनर्बहाल करने का आदेश प्राप्त हुआ।

उपरोक्त आदेश के आलोक में आलोच्य पथ में बाढ़ / अतिवृष्टि से क्षतिग्रस्त भाग की आपातकालीन मरम्मत कर यातायात को पुनः स्थापित किया गया। आदेश के आलोक में पथ के कटाव का विवरणी MIS MODULE में विहित प्रपत्र में फोटोग्राफ सहित अपलोड की गई। पुनः RESTORATION के पश्चात MIS MODULE में विहित प्रपत्र में फोटोग्राफ सहित अपलोड की गई।

सचिव, ग्रामीण कार्य विभाग बिहार, पटना के पत्रांक 4672 दिनांक 17-12-2020 के निदेशानुसार बाढ़ / अतिवृष्टि से क्षतिग्रस्त पथों की Temporary Restoration कार्य का प्राक्कलन समर्पित करने के आदेश के आलोक में उपरोक्त पथ में हुए Restoration कार्य का प्राक्कलन मो0 876059/- 845997/- रुपया का समर्पित किया जाता है।

प्रस्तुत प्राक्कलन में मूलतः आवश्यकतानुसार brick bat / local sand की भराई कार्य कर यातायात बहाल किया गया। जहाँ तुरंत संभव नहीं था वहाँ बाँस की चचरी बना कर यातायात बहाल किया गया, बाद में जैसे ही कार्य करने की स्थिति बनी चचरी हटा कर Restore कर दिया गया। नदी से प्रभावित वाले पथों में कटाव निरोधक कार्य में sand bag filling , bamboo piling with runner के साथ NC कार्य भी आवश्यकतानुसार कराया गया। जहाँ Hume Pipe की आवश्यकता थी, वहाँ Hume Pipe का उपयोग किया गया।

प्राक्कलन में प्रयुक्त दर पूर्णिया प्रमंडल के लिए स्वीकृत वर्तमान अनुसूचित दर विश्लेषण के आधार पर, एवं जल संसाधन विभाग के वर्तमान प्रभावी अनुसूची दर को समाहित करते हुए उपयोग में लाया गया है। कार्य विभागीय होना है अस्तु ओवरहेड एवं संवेदक का मुनाफा की कटौती कर दी गई है।

नए प्रावधान के तहत निर्माण की राशि, जीएसटी 12% की राशि, लेबर सेस 1% की राशि के साथ ही मालिकाना हक की राशि को अलग अलग दर्शाते हुए सबको जोड़कर प्राक्कलित राशि तैयार की गई है।

कार्य की महत्ता को देखते हुए प्राक्कलन की स्वीकृति अपेक्षित है।

21/12/20.  
कनीय अभियंता  
ग्रामीण कार्य विभाग  
कार्य प्रशाखा - दिघलबैंक

21/12/20  
सहायक अभियंता  
ग्रामीण कार्य विभाग  
कार्य अवर प्रमंडल - दिघलबैंक

21/12/20  
कार्यपालक अभियंता  
ग्रामीण कार्य विभाग  
कार्य प्रमंडल किशनगंज -2

## Inspection Report for flood damage work

Date:

1. Name of PIUs- Rwd works Division Kishanganj-2

2. Name of Block/Road- Dighal Bank/ Haribhita To Duba Toli

### **A. For Road**

1. Damage Location/Chainage : 300 - 600 m

2. Damage Length : 228 m

3. Nature of Damage : cut & erosion & Ditch

4. Details of Restoration : L/sand, Bk/Bats filling, Bombo filling with sand Bag

i Material being used in Restoration :- L/sand, Bk Bat, Bamboo, Sand Bag

ii Equipment/Tools being used in Restoration works: Tractor trolley, JCB etc

iii Procedure taken up in Restoration works : Manual

iv Restored Length : 228 m

### **B. For Bridge**

1. Damage Location/Chainage :

2. Damage Length :

3. Nature of Damage :

4. Details of Restoration :


i Material being used in Restoration :

ii Equipment/Tools being used in Restoration works:

iii Procedure taken up in Restoration works :

iv Restored Length :

  
Signature of JE/AE/EE

  
21/12/20  
MB

  
Signature  
(Name of Inspector)

# GENERAL ABSTRACT OF COST

NAME OF ROAD :- HARIBHITTA TO DUBBA TOLI

1 CONSTRUCTION COST <sup>752616.00</sup>  
748670.00 7.487 LACS

GST 12% = Rs <sup>90314.00</sup>  
89840 = 0.898 LACS


LABOUR CESS 1% = Rs <sup>7526.00</sup>  
7487 = 0.075 LACS

SEIGNORAGE FEE 10% OF M = Rs 25603 = 0.256 LACS

ESTIMATED COST = Rs 845997 = 8.460 LACS

<sup>876059.00</sup> = 8.760 LACS

Say Rs. 8,46,000/- to 8,76,000/-

  
JUNIOR ENGINEER  
RWD (W) SECTION  
DIGHALBANK

  
ASSISTANT ENGINEER  
RWD (W) SUB DVN  
DIGHALBANK

  
EXECUTIVE ENGINEER  
RWD (W) DVN  
KISHANGANJ-2

Technically Approved  
Technically approved for ₹ 8,46,000/- for Rs. 8,76,000/-  
(Rupees Eight Lacs  
(Rs. Eight Lacs, forty six thousand and <sup>200</sup>  
Seventy six thousand  
only.  
hundred) only

  
30/11/20  
अधीक्षण अभियन्ता  
ग्रामीण कार्य विभाग  
कार्य अंचल, किशनगंज