



GOVERNMENT OF BIHAR

NAME OF WORK:- Restoration work of Road PMGSY Sultan
Chowk to Bari Gidarmari

(FDR PART-A)

Restoration Length :- 200 M

Block:- Barari

DETAILED PROJECT REPORT

UNDER FDR (2245)

ESTIMATED COST

Rs. 5,67,863.00

**-: PREPARED BY :-
EXECUTIVE ENGINEER
R.W.D. (W) DIVISION**

ग्रामीण कार्य विभाग, कार्य प्रमंडल, कटिहार।
बाढ़/अतिवृष्टि से क्षतिग्रस्त पथों/पुलों की आपातकालीन मरम्मत हेतु जाँच प्रतिवेदन।
(वित्तीय वर्ष-2020-21)

Block - Barari

Sl No.	Name of District	Name of Division	Name of Road	Road Status	Length (In Km)	Estimated Cost For Restoration (In Lakh)	Remarks
1	2	3	4	5	6	7	8
1	Katihar	Katihar	Mohna Chandpur Bandh To Pratapganj	Ongoing	0.900	417145.00	Restoration Work Complete
2	Katihar	Katihar	L119- L072 To Jotram Rai	Completed	6.000	644425.00	Restoration Work Complete
3	Katihar	Katihar	PMGSY Road Idgah to Kadar Tola	Completed	0.700	804953.00	Restoration Work Complete
4	Katihar	Katihar	L076-T04 TO GORIARI (TRACK76)	Completed	1.400	341799.00	Restoration Work Complete
5	Katihar	Katihar	L058-L057 TO BAGHWA KOLE (TRACK57)	Completed	1.900	2152127.00	Restoration Work Complete
6	Katihar	Katihar	L084-L080 To Ranichak	Completed	2.200	695220.00	Restoration Work Complete
7	Katihar	Katihar	L045-L021 TO GANJ TOLA (TRACK45)	Completed	4.175	474034.00	Restoration Work Complete
8	Katihar	Katihar	PMGSY Sultan Chowk to Bari Gidarmari	Completed	1.500	567863.00	Restoration Work Complete
Total :-						6097566.000	

(ई० मृत्युंजय कुमार)
कनीय अभियंता
ग्रामीण कार्य विभाग
कार्य प्रशाखा, बरारी-3

(ई० फागु मंडल)
कनीय अभियंता
ग्रामीण कार्य विभाग
कार्य प्रशाखा, बरारी-1,2

(ई० राम वरण सिंह)
सहायक अभियंता
ग्रामीण कार्य विभाग
कार्य अवर प्रमंडल, बरारी।

(ई० चन्द्रशेखर कुमार)
कार्यपालक अभियंता
ग्रामीण कार्य विभाग
कार्य प्रमंडल, कटिहार।

(ई० अम्यानेन्द शर्मा)
कार्यपालक अभियंता
ग्रामीण कार्य विभाग
कार्य प्रमंडल, मनिहारी।

तकनीकी प्रतिवेदन

ना का नाम :- अतिवृष्टि एवं बाढ़ के कारण क्षतिग्रस्त "पी0एम0जी0एस0वाई सुल्तान चौक से बड़ी गिदरमारी" पथ आकस्मिक मरम्मत कार्य (पार्ट-A)

ग्रस्त पथ की लम्बाई :- 200 मी0

कलित राशि :- रू0 5,67,863.00

तना शीर्ष :- FDR (2245)

प्रकार :- सचिव, ग्रामीण कार्य विभाग, बिहार, पटना का पत्रांक-2789 दिनांक 21.08.2020

प्रतिवेदन

प्रस्तुत प्राक्कलन अतिवृष्टि/बाढ़ के कारण क्षतिग्रस्त पथ के पथांश का प्राक्कलन 5,67,863.00 मात्र के लिए ग्रामीण कार्य विभाग, कार्य प्रमंडल, कटिहार के द्वारा शीर्ष FDR के अंतर्गत बनाया गया है।


पथ के आकस्मिक मरम्मत हेतु पथांशों में Brick Bats एवं बॉस पाईलिंग भरकर पथ का कार्य करते हुए यातायात पुर्नस्थापित किया गया है।


पथ मरम्मत कार्य का प्राक्कलन वर्तमान अनुसूचित दर एवं सामग्री की दुलाई उत्तम खदान से प्रावधान कर बनाया गया है। दर गणना में संवेदक लाभांश सम्मिलित नहीं हैं।

उक्त कार्य को विभागीय रूप से कराये जाने हेतु आदेश प्राप्त है (प्रति संलग्न) एवं तत्पश्चात् स्वीकृति हेतु तकनीकी अनुमोदन अपेक्षित है।

प्रमाणित किया जाता है कि प्राक्कलन कार्य स्थल के अनुरूप है।


तकनीकी अभियंता,
बरारी।


सहायक अभियंता,
ग्रा0का0वि0, कार्य अवर प्रमंडल,
बरारी।


कार्यपालक अभियंता,
ग्रा0का0वि0, कार्य प्रमंडल,
कटिहार।

NAME OF WORK:- Restoration work of Road PMGSY Sultan Chowk to Bari Gidarmari

Total Length :- 1.500 Km

Restoration Length :- 200 M

ABSTRACT OF COST			
1	Cost of Emergent repair of road	Rs.	4,78,192.00
2	Add 1 % Labour Cess	Rs.	4,782.00
3	Add 12 % GST	Rs.	57,383.00
4	Add for Seigniorage Fee	Rs.	27,506.00
Total :-		Rs.	5,67,863.00
Say		Rs.	5,67,863.00

[Signature]
17/10/20
J.E.

[Signature]
17/10/20
A.E.
RWD, Sub-Division, Barari

[Signature]
E.E. Ahmed
RWD (W) Div. Katihar

Technically approved for ₹ 5,67,863.00 (Rupees Five Lacs Sixty Seven thousand Eight hundred Sixty Three) only

checked by me
20/10/21
A.E.

[Signature]
20-10-21
SUPERINTENDING ENGINEER
R.W.D. WORKS CIRCLE, PURNEA

NAME OF WORK:- Restoration work of Road PMGSY Sultan Chowk to Bari Gidarmari

Total Length :- 1.500 Km

Restoration Length :- 200 M

Sl. No.	ITEM OF WORKS	QTY	UNIT	RATE	AMOUNT
1	Providing and Laying of Brick Bats Placing tractor at loading point loading with front end loader dumpong ,turning for return trip exluding time for haulage and return tirp				
	1 x 30.0 x 1.4 x ($\frac{2.10 + 0.90}{2}$) = 63.00				
	1 x 10.0 x 1.4 x ($\frac{2.20 + 1.10}{2}$) = 23.10				
	1 x 14.0 x 1.1 x ($\frac{1.20 + 1.50}{2}$) = 20.79				
	1 x 32.0 x 1.3 x ($\frac{1.50 + 2.10}{2}$) = 74.88				
	1 x 12.0 x 1.2 x ($\frac{1.30 + 2.10}{2}$) = 24.48				
	Total = 206.25	206.25	cum	1,717.37	3,54,208.00
2	Providing, cutting and fixing of 62 mm to 75 mm dia bamboo piles in size with making shoes and driving etc. complete job as per specification and direction E/I.				
	1 x 490 No. x 5 M = 2450.00				
	Total = 2450.00	2450.00	M	47.58	1,16,571.00
3	providing, fitting and fixing 62 mm to 75 mm dia bamboo runners in position at every verticle pile with 150 mm long nails or 38 swg G. I. wire including cost of G.I. or nails complete job as per specification and direction of E/I				
	25 No. x 12 = 300.00				
	Total = 300.00	300.00	M	24.71	7,413.00
	Total cost			Rs.	4,78,192.00

[Signature]
J.E.

[Signature]
A.E.

[Signature]
Executive Engineer
RWD. (W) Div. Katihar.