



ग्रामीण कार्य विभाग

Rural Works Department, Govt of Bihar

DETAILED PROJECT REPORT FOR REPAIRING OF ROAD

F.D.R. PART - A (2020)

L036- L023 TO KISHANPUR (TRACK 10)

DETAILED ESTIMATE OF F.D.R. REPAIRING ROAD


ROAD LENGTH	0 TO 950	
DISTRICT	KATIHAR	
BLOCK	AMDABAD	
DIVISION	MANIHARI	
TOTAL LENGTH OF ROAD	0.950	KM
TOTAL COST OF F.D.R. PART - A	Rs. 4.518	Lacs
ADD G.S.T @ 12%	Rs. 0.542	Lacs
ADD Labour Cess @ 1%	Rs. 0.045	Lacs
ADD Seigniorage Fee @ 10%	Rs. 0.336	Lacs
TOTAL COST OF RESTORATION WORK In Rs.	Rs. 5.441	Lacs


SUBMITTED BY
The Executive Engineer,
Works Division, Manihari

GENERAL ABSTRACT OF COST FOR MAINTENANCE OF ROAD

NAME OF ROAD : L036- L023 TO KISHANPUR (TRACK 10)
DISTRICT KATIHAR
DIVISION MANIHARI
BLOCK AMDABAD
LENGTH OF ROAD (IN KM) 0.950

Sl. No.	ITEM OF WORK	AMOUNT (LAKHS)
1	BRIKCK BAT	4.518
2	SAND BAGS	0.000
3	BAMBOO WORK	0.000
4	HUME PIPE	0.000
TOTAL COST OF PROJECT =		4.518
Add G.S.T. @ 12%		0.542
Add Labour Cess @ 1%		0.045
Add Selgniorage Fee @ 10%		0.336
Total Cost of Restoration Work =		5.441


JE 8/3/21
RWD


AE 8.3.21
RWD


JE
RWD

Technically approved for Rs 5.441 Lacs
(Rupees Five Lacs forty four Thousame
one Hundred) only


SUPERINTENDING ENGINEER
R.W.D. WORKS CIRCLE, PURNEA

L036- L023 TO KISHANPUR (TRACK 10)

Sl. No.	SDB SL. NO	MORD Ref.No	Description	Unit	NOS	LENGTH	WIDTH	HEIGHT	QUANTITY	RATE	AMOUNT (in Rs.)
1	4.5		Brick Bats								
			Providing Brick Bats including, Spreading, Laying Compacting with C.I. Hammer all complete job as per Specification and Direction E/I.								
			C/O To ANNEXURE "A"						263.060		
				Cum					263.060	1717.370	451771.35
									Total Cost fo Flood Protective work (In Rs.) =		451771.35
									Total Cost fo Flood Protective work (In Lakh) =		4.518

[Signature]
8/3/21
JE.

[Signature]
A.E. 8.3.21

[Signature]
E.E.