



ग्रामीण कार्य विभाग

Rural Works Department, Govt of Bihar

DETAILED PROJECT REPORT FOR REPAIRING OF ROAD

F.D.R. PART-A (2020)

AZAMNAGAR KESHRI CHOWK TO PARIHARPUR

DETAILED ESTIMATE OF F.D.R. RESTORATION WORK

ROAD LENGTH	10.500 KM	
DISTRICT	KATIHAR	
BLOCK	AZAMNAGAR	
DIVISION	MANIHARI	
ESTIMATED COST	41.791	LACS

SUBMITTED BY
The Executive Engineer,
R.W.D., Works Division, Manihari.


GENERAL ABSTRACT OF COST FOR MAINTENANCE OF ROAD

NAME OF ROAD: AZAMNAGAR KESHRI CHOWK TO PARIHARPUR
BLOCK : AZAMNAGAR
DISTRICT : KATIHAR
LENGTH OF ROAD IN KM 10.500 KM

Sl. No.	ITEM OF WORK	AMOUNT (IN LAKHS)
1	BRICK BATS	36.983
2	NP3	0.665
	TOTAL COST OF PROJECT	36.983
	ADD G.S.T. @ 12%	4.438
	ADD Labour Cess @ 1%	0.370
	Total Cost of Restoration work	41.791


J.E.
R.W.D.
AZAMNAGAR.


A.E.
R.W.D.
AZAMNAGAR.


E.E.
R.W.D.
Manihari.

(Technically approved for Rs. 41.791 Lac (Rs. _____
Crore. Forty one Lac. seventy
nine Thousand. One Hundred only)


SUPERINTENDING ENGINEER
R.W.D. WORKS CIRCLE, PURNEA

AZAMNAGAR KESHRI CHOWK TO PARIHARPUR
During Flood/heavy rain fall in year 2020

Sl. No.	SBD Sl. No.	Description	Unit	Nos.	Length	Quantity	Rate	Amount (in Rs.)
1	4.5	Providing and Laying of Brick Bats						
		Placing tractor at loading point loading with front end loader dumping, turning for return trip excluding time for haulage and return trip.						
		C/O To Annexure "A"	Cum	0	0	2198.85		
		Less H.P. Qty. $24 \times 1.0 + 2.60/2 \times 1.1 + 1.0/2 = 45.36$	Cum	0	0	-45.36		
		Total	Cum	0	0	2153.49	1717.370	3698334.327
2	9.3	Providing and Laying Reinforced Cement Concrete Pipe NP3 as per design						
		Providing and Laying Reinforced Cement Concrete Pipe NP3 for Restoration (1000mm dia Single Raw)	RM	6	2.50	15.00	4432.830	66492.450
Total Cost of Project								3764826.777

[Signature]
22/11/21

J.E.
R.W.D., Azamnagar.

[Signature]
A.E.

R.W.D., Azamnagar.

[Signature]
E.E.

R.W.D., Manihari..