



ग्रामीण कार्य विभाग

Rural Works Department, Govt of Bihar

DETAILED PROJECT REPORT FOR REPAIRING OF ROAD

F.D.R. PART-A (2020)

PASTIYA TO PHULBARI

DETAILED ESTIMATE OF F.D.R. RESTORATION WORK

ROAD LENGTH	2.830 KM	
DISTRICT	KATIHAR	
BLOCK	AZAMNAGAR	
DIVISION	MANIHARI	
ESTIMATED COST	29.625	LACS


SUBMITTED BY
The Executive Engineer,
R.W.D., Works Division, Manihari.


GENERAL ABSTRACT OF COST FOR MAINTENANCE OF ROAD

NAME OF ROAD: PASTIYA TO PHULBARI
BLOCK : AZAMNAGAR
DISTRICT : KATIHAR
LENGTH OF ROAD IN KM 2.830 KM

Sl. No.	ITEM OF WORK	AMOUNT (IN LAKHS)
1	BRICK BATS	24.617
2	BAMBOO PILE & CHACHRI	1.600
	TOTAL COST OF PROJECT	26.217
	ADD G.S.T. @ 12%	3.146
	ADD Labour Cess @ 1%	0.262
	Total Cost of Restoration work	29.625


J.E.
R.W.D.
AZAMNAGAR


A.E.
R.W.D.
AZAMNAGAR.


E.E.
R.W.D.
Manihari.


(Technically approved for Rs. 29.625 Lac (Rs. _____
Crore. Twenty nine Lac. Sixty two
_____ Thousand. Five _____ Hundred))



SUPERINTENDING ENGINEER
R.W.D WORKS CIRCLE, PURNEA

**Details Estimate for Irratic Restoration in damage/cut road
PASTIYA TO PHULBARI
During Flood/heavy rain fall in year 2020**

Sl. No.	SBD Sl. No.	Description	Unit	Quantity	Rate	Amount (in Rs.)
1	4.5	Providing and Laying of Brick Bats Placing tractor at loading point loading with front end loader dumping, turning for return trip excluding time for haulage and return trip.				
		C/O To Annexure "A"	Cum	1433.40	1717.370	2461672.577
3	5.7.7 (A)	S/F fixing 62 mm to 75 mm dia bamboo piles in size and making shoes and driving etc. complete job as per specification and direction E/I. Bamboo Pile C/C 0.3 m 524 x 3 = 1572.00	m	1572.00	47.58	74795.760
4	5.7.46 (C)	C/O To Annexure "B" Supplying fitting and fixing Bamboo Runner including cost of bambooe etc. complete job as per specification and direction E/I. 157.20 x 4 = 628.80	m	628.80	24.71	15537.648
5	14.18	C/O To Annexure "B" Supplying fitting and fixing in position split bamboo woven chachary with 20 SWG G.I. etc. complete job as per specification and direction E/I. 157.20 x 2 = 314.40	Sqm	314.40	221.69	69699.336
Total Cost of Project						2621705.321


J.E.
R.W.D., Azamnagar.


A.E.
R.W.D., Azamnagar.


R.W.D. MANIHARI.