



ग्रामीण कार्य विभाग

Rural Works Department, Govt of Bihar

DETAILED PROJECT REPORT FOR REPAIRING OF ROAD

F.D.R. PART-A (2020)

MMGSY ROAD TO IDGAH SEEJ

DETAILED ESTIMATE OF F.D.R. RESTORATION WORK

ROAD LENGTH	0.600 KM	
DISTRICT	KATIHAR	
BLOCK	MANIHARI	
DIVISION	MANIHARI	
ESTIMATED COST	6.925	LACS

SUBMITTED BY
The Executive Engineer,
R.W.D., Works Division, Manihari.

प्रतिवेदन

योजना का नाम : MMGSY ROAD TO IDGAH SEEJ
वित्तीय वर्ष : 2020-21 / FDR- 2020
पथ की लम्बाई : 0.600 KM
प्राक्कलित राशि : 6.92500
प्रखंड : MANIHARI

प्रस्तुत प्राक्कलन वर्ष-2020 में आयी भीषण बाढ़/अतिवृष्टि से क्षतिग्रस्त हुए पथों में तत्काल यातायात बहाल करने हेतु तैयार किया गया है।

प्राक्कलन विभागीय सचिव, ग्रामीण कार्य विभाग, बिहार पटना के पत्रांक-मु०अ०-04(मु०) विविध कार्य (कार्य)-23-40/2016-2789 दिनांक-21.08.2020 के आलोक में अधीक्षण अभियंता, ग्रामीण कार्य विभाग, कार्य अंचल, पूर्णियाँ के निदेशानुसार तैयार किया गया है।

प्राक्कलन में आवश्यकता एवं उपलब्धता के अनुसार ईट के टुकड़े (Bricks Bats), Bamboo Pilling, Runner & Chachari के द्वारा पथ में कटाव/गड्ढे को भरने का प्रावधान किया गया है। प्राक्कलन में अंकित मदों का दर अधीक्षण अभियंता, ग्रामीण कार्य विभाग, कार्य अंचल, पूर्णियाँ के द्वारा अनुमोदित दर पर आधारित है।

प्राक्कलन में Contractor Profit एवं Over Head Charge नहीं जोड़ा गया है, चूंकि विभागीय रूप से कार्य कराया गया है परन्तु GST एवं Labour Cess को जोड़ा गया है। प्रमाणित किया जाता है कि यह प्राक्कलन स्थल के अनुरूप है।

प्राक्कलन तकनीकी अनुमोदन हेतु समर्पित किया जाता है।



कनीय अभियंता,
ग्रामीण कार्य विभाग, कार्य
प्रशाखा, मनिहारी।



सहायक अभियंता,
ग्रामीण कार्य विभाग, कार्य
अवर प्रमंडल, मनिहारी।



कार्यपालक अभियंता,
ग्रामीण कार्य विभाग, कार्य
प्रमंडल, मनिहारी।

GENERAL ABSTRACT OF COST FOR MAINTENANCE OF ROAD

NAME OF ROAD: MMGSY ROAD TO IDGAH SEEJ
BLOCK : MANIHARI
DISTRICT : KATIHAR
LENGTH OF ROAD IN KM 0.600 KM


Sl. No.	ITEM OF WORK	AMOUNT (IN LAKHS)
1	BRICK BATS	5.055
2	BAMBOO PILE & CHACHRI	0.713
3	CEMENT BAG	0.361
	TOTAL COST OF PROJECT	6.128
	ADD G.S.T. @ 12%	0.735
	ADD Labour Cess @ 1%	0.061
	Total Cost of Restoration work	6.925


J.E. 22/01/2021

R.W.D.
MANIHARI.



22/01/2021

A.E.
R.W.D.
MANIHARI.


J.E. 22/01

R.W.D.
Manihari.

(Technically approved for Rs. 6.925 Lac (Rs. _____
Crore. Six Lac. ninety two
_____ Thousand. five Hundred only)


SUPERINTENDING ENGINEER
R.W.D. WORKS CIRCLE, PURNEA

**Details Estimate for Traffic Restoration in daimage/cut road
MMGSY ROAD TO IDGAH SEEJ**

During Flood/heavy rain fall in year 2020

Sl. No.	SBD Sl. No.	Description	Unit	Quantity	Rate	Amount (in Rs.)
1	4.5	Providing and Laying of Brick Bats Placing tractor at loading point loading with front end loader dumping, turning for return trip excluding time for haulage and return trip. C/O To Annexure "A", "B"	Cum	294.35	1717.370	505507.860
2	10.7.40 WRD	Supplying of empty cement bag and Labour for filling Cement Bag, swing and laying Materials. C/O To Annexure "B"	Nos.	1122	32.140	36062.971
3	5.7.7 (A)	S/F/fixing 62 mm to 75 mm dia bamboo piles in size and making shoes and driving etc. complete job as per specification and direction E/I. Bamboo Pile C/C 0.3 m C/O To Annexure "C"	m	700.00	47.58	33306.000
4	5.7.46 (C)	Supplying fitting and fixing Bamboo Runner including cost of bambooe etc. complete job as per specification and direction E/I. C/O To Annexure "C"	m	280.00	24.71	6918.800
5	14.18	Supplying fitting and fixing in position spot bamboo woven chachary with 20 SWG G.I. etc. complete job as per specification and direction E/I. C/O To Annexure "C"	Sqm	140.00	221.69	31036.600
Total Cost of Project						612832.230

[Signature]
J.E.
22/01/2021

R.W.D., MANIHARI

[Signature]
A.E.
22/01/2021

R.W.D., MANIHARI

[Signature]
A.E.
22/01/2021

R.W.D., MANIHARI.