



ग्रामीण कार्य विभाग

Rural Works Department, Govt of Bihar

DETAILED PROJECT REPORT FOR REPAIRING OF ROAD

F.D.R. PART-A (2020)

PMGSY ROAD MALLICPUR TO MALLICKPUR SOUTH
TOLA

DETAILED ESTIMATE OF F.D.R. RESTORATION WORK

ROAD LENGTH	1.050 KM	
DISTRICT	KATIHAR	
BLOCK	AZAMNAGAR	
DIVISION	MANIHARI	
ESTIMATED COST	15.726	LACS

SUBMITTED BY
The Executive Engineer,
R.W.D., Works Division, Manihari.

GENERAL ABSTRACT OF COST FOR MAINTENANCE OF ROAD

NAME OF ROAD: PMGSY ROAD MALLICPUR TO MALLICKPUR
BLOCK : SOUTH TOLA
DISTRICT : AZAMNAGAR
LENGTH OF ROAD IN KM KATIHAR
1.050 KM

Sl. No.	ITEM OF WORK	AMOUNT (IN LAKHS)
1	BRICK BATS	13.031
2	BAMBOO PILE & CHACHARI	0.886
	TOTAL COST OF PROJECT	13.917
	ADD G.S.T. @ 12%	1.670
	ADD Labour Cess @ 1%	0.139
	Total Cost of Restoration work	15.726


J.E.
R.W.D.
AZAMNAGAR.


A.E.
R.W.D.
AZAMNAGAR.



E.E.
R.W.D.
Manihari.

(Technically approved for Rs. 15.726.Lac (Rs. _____
Crore. Fifteen Lac Seventy
two Thousand two Hundred only)



SUPERINTENDING ENGINEER
R.W.D. WORKS CIRCLE, PURNEA

Details Estimate for Traffic Restoration in daimage/cut road
PMGSY ROAD MALLICPUR TO MALLICKPUR SOUTH TOLA
During Flood/heavy rain fall in year 2020

Sl. No.	SBD Sl. No.	Description	Unit	Quantity	Rate	Amount (in Rs.)
1	4.5	Providing and Laying of Brick Bats Placing tractor at loading point loading with front end loader dumping, turning for return trip excluding time for haulage and return trip. C/O To Annexure "A"	Cum	758.80	1717.370	1303145.126
2	5.7.7 (A)	S/F-fixing 62 mm to 75 mm dia bamboo piles in size and making shoes and driving etc. complete job as per specification and direction E/I. Bamboo Pile C/C 0.3 m C/O To Annexure "C"	m	870.00	47.58	41394.600
3	5.7.46 (C)	Supplying fitting and fixing Bamboo Runner including cost of bambooe etc. complete job as per specification and direction E/I. C/O To Annexure "C"	m	348.00	24.71	8599.080
4	14.18	Supplying fitting and fixing in position split bamboo woven chachary with 20 SWG G.I. etc. complete job as per specification and direction E/I. C/O To Annexure "C"	Sqm	174.00	221.69	38574.060
Total Cost of Project						1391712.866


J.E.
R.W.D., Azamnagar.


A.E.
R.W.D., Azamnagar.


R.W.D., MANIHARI.