



बिहार सरकार

FLOOD DAMAGE REPAIR (FDR)

YEAR 2020-21

FOR T/A

DISTRICT :- BEGUSARAI
BLOCK :- BHAGWANPUR

CONSTRUCTION COST :- Rs. 2.519 Lac
TOTAL COST :- Rs. 2.519 Lac

PMGSY YOJNA

NAME OF ROAD :- FLOOD DAMAGE REPAIR OF ROAD
L032-T02 TO MAHESHPUR (VR-32).

TOTAL LENGTH : 4.95 KM
LENGTH DAMAGE DUE TO FLOOD : 0.205 KM.

SUBMITTED BY:
EXECUTIVE ENGINEER
R.W.D. WORKS DIVISION, TEGHRA

Name of Road :- Flood Damage Repair of Road L032-T02 to Maheshpur (VR-32).

Year 2020-21

District :- Begusarai
Block :- Bhagwanpur

GENERAL ABSTRACT OF COST

Sl No.	Item of Work	Amount (in Rs.) As Per Estimate
1	COST OF FDR	2,11,976.00
2	Add L.C. @1%	2,120.00
3	ADD GST @ 12%	25,437.00
	Add S.F. @ 10% on Material Rate	12,294.00
	Total Rs. :-	2,51,827.00
	Say Rs. :-	2,51,900.00

Asst. Insp. Sharma
10/2/21
J.E.
RWD. Teghra

[Signature]
A.E.
RWD. Teghra

[Signature]
10/2/21
E.E.
RWD. Teghra

Technically Approved Rs 2,51,900.00 Two Lakh fifty one thousand nine hundred only.

[Signature]
23/2/21
प्रमुख अभियंता
राज्य
महानगर, प्रमुख

SDB SL NO	MORD Ref No	Description	Unit	NOS	LENGTH	WIDTH	HEIGHT	QUANTITY	RATE	AMOUNT (in Rs.)
1		Providing brick bats including spreading, laying, hand packing with CI hammers in layers has exceeding 75mm thick including cost of light barriers, danger equal, chouldar, taxes, royalty etc all complete job, as per specifications and direction of E/I including cost of bricks, all complete job.								
		Qty From Calculation Sheets	Cum					83.00	1680.02	1,39,442.00
2		Construction of road embankment materials obtained from borrow pits all complete job as per clause 300.1, 300.2 with lead upto 1000m								
		Qty From Calculation Sheets	Nos					225.00	173.05	38,936.00
3		Construction of granular sub-base by providing well graded material, spreading in uniform layers with tractor mounted grader arrangement on prepared surface, mixing by mix in place method with rotavator at OMC, and compacting with smooth wheel roller to achieve the desired density, complete as per Technical Specification Clause 401.								
		Qty From Calculation Sheets	Cum					18.75	1,791.92	33,598.00
								Total =		21,19,76.00

Arvind Sharma
10/2/2021
J.E.
RWD Teghra

h 10/2/21
A.E.
RWD Teghra

pratik
10/2/21
E.E.
RWD Teghra

कार्यपालक अभियंता का कार्यालय
ग्रामीण कार्य विभाग, कार्य प्रमण्डल, मंझौल-बखरी।

पत्रांक-...238/मंझौल-बखरी,

दिनांक-18.02.2021/

प्रेषक,

कार्यपालक अभियंता,
ग्रामीण कार्य विभाग,
कार्य प्रमण्डल, मंझौल-बखरी।

सेवा में,

कार्यपालक अभियंता,
ग्रामीण कार्य विभाग,
कार्य प्रमण्डल, तेघड़ा।

विषय : शीर्ष-FDR अन्तर्गत पथों की जाँच प्रतिवेदन समर्पित करने के संबंध में।


प्रसंग : आपका पत्रांक-238 दिनांक-18.02.2021

महाशय,

उपर्युक्त विषयक प्रसांगिक पत्र के संबंध में कहना है कि ग्रामीण कार्य विभाग, कार्य प्रमण्डल, तेघड़ा के अधीन शीर्ष-FDR अन्तर्गत वर्ष-2020-21 के पथों की जाँच कर जाँच प्रतिवेदन समर्पित की जाती है।

अनु०-प्रतिवेदन संलग्न।

विश्वासभाजन


18.02.2021

कार्यपालक अभियंता
ग्रामीण कार्य विभाग, कार्य प्रमण्डल,
मंझौल-बखरी।

ग्रामीण कार्य विभाग, कार्य प्रमण्डल, तैयडा द्वारा कराए गए पथों की जाँच से संबंधित प्रतिवेदन

क्र० सं०	पथ का नान	क्षतिग्रस्त भाग (मी० में)	कराए गए कार्य	कराए गए निर्माण कार्य की राशि (रु० में)	GST @12%	L. Cess @1%	S. Fee @10%	Total	अभियुक्ति
1	Flood Damage Repair of Road T02 Rajghat To House of Narayan Rai Via Bhumihar Tola.	140	E/W & Bricks Bats	297537.00	35704.00	2975.00	21448.00	357664.00	कार्य पूर्ण।
2	Flood Damage Repair of Road MMSGY Road PWD Road To Rasalpur.	280	Sand Bag	420901.00	50508.00	4209.00	8198.00	483816.00	कार्य पूर्ण।
3	Flood Damage Repair of Road MMSGY Road Basahi To Churaman chak To PMGSY Road L025 To Basahi	58	Sand Bag	388105.00	46573.00	3881.00	7559.00	446118.00	कार्य पूर्ण।
4	Flood Damage Repair of Road L032-T02 to Maheshpur (VR-32).	205	E/W & Bricks Bats & Gsb	211976.00	25437.00	2120.00	12294.00	251827.00	कार्य पूर्ण।


Executive Engineer
RWD (W) Div., Manjhaul-Bakhari

अधीक्षण अभियंता का कार्यालय
ग्रामीण कार्य विभाग, कार्य अंचल, समस्तीपुर।

पत्रांक-.....483...../समस्तीपुर

दिनांक-.....23/2/21.....

प्रेषक,

अधीक्षण अभियंता,
ग्रामीण कार्य विभाग,
कार्य अंचल, समस्तीपुर।

सेवा में,

मुख्य अभियंता-4,
ग्रामीण कार्य विभाग,
बिहार, पटना।

विषय :- शीर्ष FDR अन्तर्गत वित्तीय वर्ष-2020-21 के पथों के प्राक्कलन के तकनीकी अनुमोदनोपरान्त प्रशासनिक स्वीकृति के संबंध में।

प्रसंग :- कार्यपालक अभियंता, ग्रामीण कार्य विभाग, कार्य प्रमण्डल, तेघड़ा के पत्रांक-.....26.8..... अनु०, दिनांक-.....22.2.21.....


महाशय,

उपर्युक्त विषय के संबंध में कहना ग्रामीण कार्य विभाग, कार्य प्रमण्डल, तेघड़ा के अधीन शीर्ष FDR अन्तर्गत वित्तीय वर्ष-2020-21 के पथों का प्राक्कलन तकनीकी अनुमोदनोपरान्त प्रशासनिक स्वीकृति हेतु समर्पित किया जाता है।

Sl. No.	Name of Road	Repair Length (In m)	Total Cost (in Lac)
1	Flood Damage Repair of Road T02 Rajghat To House of Narayan Rai Via Bhumihaar Tola.	140	3.577
2	Flood Damage Repair of Road MMGSY Road PWD Road To Rasalpur.	280	4.839
3	Flood Damage Repair of Road MMGSY Road Basahi To Churaman chak To PMGSY Road L025 To Basahi	58	4.462
4	Flood Damage Repair of Road L032-T02 to Maheshpur (VR-32)	205	2.519

अनु०-प्राक्कलन एक-एक प्रतियों में।

विश्वासभाजन


अधीक्षण अभियंता,
ग्रामीण कार्य विभाग,
कार्य अंचल, समस्तीपुर।

AC
23/2/21