

32

(46)

(5)

Inspection Report For Flood Damage Work

Date :

1 Name of PIUs : Gopalganj-2

2 Name of Block/Road : Baikunthpur / Chintahi Kalo'sham se Chintahi
Panchayat Bhawan.

A For Road

1 Damage Location / Chainage : 0.00 m to

2 Damage Length : 178.00 m.

3 Nature of Damage : H. Rain / Flood.

4 Details of Restoration Works:

i. Material being used in Restoration Works: Brick Bats

ii Equipments / Tools being used in Restoration Works : JCB, Tractor, Probe, Bekker, Shovel etc.

iii Procedure taken up in Restoration Works: Yes

iv Restored Length: 178.00 m.

B For Bridge

N/A.

1 Damage Location / Chainage:

2 Damage Length:

3 Nature of Damage:

4 Details of Restoration Works:

i. Material being used in Restoration Works :

ii Equipments / Tools being used in Restoration Works :


iii Procedure taken up in Restoration Works:

iv Restored Length :


 JE 24/11/2020


 AE 24/11/2020


 EE 24/11/20


 Signature
 Executive Engineer
 R.W.D. W.D.
 Hathua



ग्रामीण कार्य विभाग

Rural Works Department, Govt. of Bihar

FLOOD DAMAGED REPAIR (F.D.R.)

STATE :- BIHAR
DISTRICT :- GOPALGANJ
BLOCK :- BAIKUNTHPUR

Chiutaha Kali Sthan Se Chiutaha Panchayat Bhawan

ESTIMATED COST - RS. 1449900.00

**SUBMITTED BY :-
EXECUTIVE ENGINEER
RWD (W) DIVISION
GOPALGANJ-2**

Report

Name of Work :- Motorable work of Chiutaha Kali Sthan Se
Chiutaha Panchayat Bhawan

Estimated Cost :- 1449900.00


Total length of Road :- km

Description :- The present estimate has been farmed under the supervision of Assistant engineer in accordance with the order of Executive Engineer, RWD, WD Gopalganj-2, letter No. - 1574 dated 18-08-2020. The part of above mentioned road has been damaged due to heavy rain/flood. And due to this damage the transporation has been obstructed. The immediate motorable work is necessary in public interest. Villagers will be benefitted by the completion of this motorable work.

In the estimate there has been a provision of repairing the damaged part of the road & making it motorable by filling brickbats. In the context of post flood scenario there is still the flow of water which prevails through the damaged part of the road.

In this estimate the rate of raw materials and labour wages has been prepared after the analysis of new rate. This estimate is as per the specifications. The estimate is devoted to technical and administrative acceptance.


25/10/2020
J.E.


25-10-2020
A.E.


25/10/20
E.E.

**Detailed Estimate For Motorable Work in Road from Chiutaha Kali Sthan Se
Chiutaha Panchayat Bhawan damaged due to Heavy rain/flood for year 2020-2021**

Items	No.	L (M.)	W (M.)	D (M.)	Qty.	Unit	Rate	Amount
Providing brick bats billed in ditches including all cost of labour & material with all complete job.								
CH - 0 M to 00 M	1	10.00	0.90	0.60	5.40	M3		
	1	7.00	0.60	1.00	4.20	M3		
	1	10.00	1.10	0.30	3.30	M3		
	1	9.00	1.30	2.50	29.25	M3		
	1	11.00	1.10	1.40	16.94	M3		
	1	30.00	1.30	1.60	62.40	M3		
	1	21.00	1.95	1.85	75.76	M3		
	1	29.00	1.75	2.00	101.50	M3		
	2	30.00	1.60	2.60	249.60	M3		
	1	21.00	1.05	1.95	43.00	M3		
Less for H.P.	0	1.23	1.23	0.95	0.00	M3	2412.11	142640.12
					591.35	M3	2427.65	1435578.69
Providing & laying 1000 MM Dia NP3 Hume Pipe in single row -do-do- complete job.	0	2.50			0.00	M	2744.50 4159.56	0.00
								142640.12 1435578.69
Add 1 % Contingency								142640.12 14355.79
							Total	1449934.48
							Say	1449900.00-

Rs 144066520
Sery Rs 14.4076

12/10/2020
J.E.

A.E.

E.E.
25/10/20

Technically Approved For Rs 14.407 lacs (Rupees Fourteen Lacs Forty Thousand & Seven Hundred) only

21/01/21
Superintending Engineer,
Raham RWD
21/01/2021