

Inspection Report For Flood Damage Work

Date :

1 Name of PIUs : Gopalganj - 2

2 Name of Block/Road : Baikunthapur / Dighawan Kachari Tol Sadhu Singh  
Ke Ghar-Hole Dobawali Bazar Pak

A For Road

1 Damage Location / Chainage : 0 m To 1200 m

2 Damage Length : 379.00 m

3 Nature of Damage : ~~379.00 m~~ Heavy Rain / Flood

4 Details of Restoration Works:

i. Material being used in Restoration Works: Brick Bats

ii Equipments / Tools being used in Restoration Works : ICB, Tractor, Trolly, Betels, Shaved  
etc

iii Procedure taken up in Restoration Works: Yes

iv Restored Length: 379.00 m

B For Bridge

1 Damage Location / Chainage: N/A

2 Damage Length:

3 Nature of Damage:

4 Details of Restoration Works:

i. Material being used in Restoration Works :

ii Equipments / Tools being used in Restoration Works :

iii Procedure taken up in Restoration Works:

iv Restored Length :

*[Signature]*  
24/11/2020  
AE

*[Signature]*  
24.11.2020  
AE

*[Signature]*  
24/11/20  
EE  
Signature  
Executive Engineer  
(Name of Inspector)  
R.W.D. W.D.  
Hathua



# ग्रामीण कार्य विभाग

Rural Works Department, Govt. of Bihar

## FLOOD DAMAGED REPAIR (F.D.R.)

STATE :- BIHAR  
DISTRICT :- GOPALGANJ  
BLOCK :- BAIKUNTHPUR

Dighawa Kachari Tola Sadhu Singh ke Ghar Hote Dobawali Bajar Tak

ESTIMATED COST - RS.

1747100.00

SUBMITTED BY :-  
EXECUTIVE ENGINEER  
RWD (W) DIVISION  
GOPALGANJ-2

## Report

Name of Work :- Motorable work of Dighawa Kachari Tola Sadhu Singh ke Ghar

Estimated Cost :- 1747100.00

Total length of Road :- 1.200 km

Description :- The present estimate has been farmed under the supervision of Assistant engineer in accordance with the order of Executive Engineer, RWD, WD Gopalganj-2, letter No. - 1574 dated 18-08-2020. The part of above mentioned road has been damaged due to heavy rain/flood. And due to this damage the transporation has been obstructed. The immediate motorable work is necessary in public interest. Villagers will be benefitted by the completion of this motorable work.

In the estimate there has been a provision of repairing the damaged part of the road & making it motorable by filling brickbats. In the context of post flood scenario there is still the flow of water which prevails through the damaged part of the road.

In this estimate the rate of raw materials and labour wages has been prepared after the analysis of new rate. This estimate is as per the specifications. The estimate is devoted to technical and administrative acceptance.

  
25/10/2020  
J.E.

  
25.10.2020  
A.E.

  
25/10/20  
E.E.



**Detailed Estimate For Motorable Work in Road from Dighawa Kachari Tola Sadhu Singh ke Ghar Hote Dobawali Bajar Tak damaged due to Heavy rain/flood for year 2020-2021**

r.	Items	No.	L (M.)	W (M.)	D (M.)	Qty.	Unit	Rate	Amount
	Providing brick bats blled in ditches including all cost of labour & material with all complete job.								
	CH - 0 M to 1200 M	1	18.00	1.80	1.50	48.60	M3		
		1	29.00	2.40	1.00	69.60	M3		
		1	23.00	2.90	0.90	60.03	M3		
		1	17.00	1.40	1.40	33.32	M3		
		1	22.00	1.35	1.20	35.64	M3		
		1	29.00	1.55	1.35	60.68	M3		
		1	18.00	1.30	1.00	23.40	M3		
		1	30.00	1.65	0.95	47.03	M3		
		1	30.00	1.40	0.95	39.90	M3		
		1	30.00	1.50	0.90	40.50	M3		
		1	29.00	1.70	0.75	36.98	M3		
		1	28.00	4.00	0.60	67.20	M3		
		1	22.00	4.00	0.80	70.40	M3		
		1	30.00	3.75	0.50	56.25	M3		
		1	24.00	1.20	0.80	23.04	M3		
	Less for H.P.	0	1.23	1.23	0.95	0.00	M3		
						712.56	M3	2427.65	1718773.20
	Providing & laying 1000 MM Dia NP3 Hume Pipe in single row -do-do- complete job.	0	2.50			0.00	M	4159.56	0.00
									1718773.20
	Add 1 % Contingency							17188.20	1729852.35
								Total	1747150.88
								Say	1747100.00

Rs 1735961.20  
204 Rs 17.3606

*[Signature]*  
25/10/2020  
J.E.


*[Signature]*  
25.10.2020  
A.E.

*[Signature]*  
25/10/20  
E.E.

Technically Approved for Rs 17.360 lac (Rupees Seventeen  
Lac Twenty Six Thousand) only

  
21/01/21

Superintending Engineer  
RWD Works Circle, Siwan

  
21/01/21