

Inspection Report For Flood Damage Work

Date :

1 Name of PIUs : Gopalganj-2

2 Name of Block/Road : Baikunthpur / Gauri Shankar Rai Ke Ghar se Hote Hue
Chitaha Dhala Tak.

A For Road

1 Damage Location / Chainage : 0m to 600m.

2 Damage Length : 306 m.

3 Nature of Damage: Heavy rain flood.

4 Details of Restoration Works:

i. Material being used in Restoration Works: Brick Bats

ii Equipments / Tools being used in Restoration Works: JCB, Tractors, Tools, Shovel etc

iii Procedure taken up in Restoration Works: Yes.

iv Restored Length: 306.00 m.

B For Bridge

N/A.

1 Damage Location / Chainage:

2 Damage Length:

3 Nature of Damage:

4 Details of Restoration Works:

i. Material being used in Restoration Works :

ii Equipments / Tools being used in Restoration Works :


iii Procedure taken up in Restoration Works:

iv Restored Length :


 24/11/2020
 AE


 24/11/2020
 EE


 24/11/2020
 EE


 24/11/2020
 Signature
 (Executive Engineer)
 R.W.D. W.D.
 Hathua



ग्रामीण कार्य विभाग

Rural Works Department, Govt. of Bihar

FLOOD DAMAGED REPAIR (F.D.R.)

STATE :- BIHAR
DISTRICT :- GOPALGANJ
BLOCK :- BAIKUNTHPUR

Dr Gauri Shankar Ray Ke Ghar Hote Hue Chiutaha Dhala Tak

ESTIMATED COST - RS. 1440600.00

SUBMITTED BY :-
EXECUTIVE ENGINEER
RWD (W) DIVISION
GOPALGANJ-2

Report

Name of Work :- Motorable work of Dr Gauri Shankar Ray Ke
Ghar Hote Hue Chiutaha Dhala Tak

Estimated Cost :- 1440600.00


Total length of Road :- km

Description :- The present estimate has been farmed under the supervision of Assistant engineer in accordance with the order of Executive Engineer, RWD, WD Gopalganj-2, letter No. - 1574 dated 18-08-2020. The part of above mentioned road has been damaged due to heavy rain/flood. And due to this damage the transporation has been obstructed. The immediate motorable work is necessary in public interest. Villagers will be benefitted by the completion of this motorable work.

In the estimate there has been a provision of repairing the damaged part of the road & making it motorable by filling brickbats. In the context of post flood scenario there is still the flow of water which prevails through the damaged part of the road.

In this estimate the rate of raw materials and labour wages has been prepared after the analysis of new rate. This estimate is as per the specifications. The estimate is devoted to technical and administrative acceptance.


25/10/2020
J.E.


25.10.2020
A.E.


25/10/20
E.E.

**Detailed Estimate For Motorable Work in Road from Dr Gauri Shankar Ray Ke Ghar
to Hue Chiutaha Dhala Tak damaged due to Heavy rain/flood for year 2020-2021**

Items	No.	L (M.)	W (M.)	D (M.)	Qty.	Unit	Rate	Amount
Providing brick bats billed in ditches including all cost of labour & material with all complete job.								
CH - 0 M to M	1	11.00	1.50	1.30	21.45	M3		
	1	20.00	2.10	1.30	54.60	M3		
	1	22.00	2.55	0.85	47.69	M3		
	1	11.00	1.50	0.85	14.03	M3		
	1	20.00	1.35	0.30	8.10	M3		
	1	30.00	1.60	1.50	72.00	M3		
	1	14.00	1.80	1.10	27.72	M3		
	1	29.00	1.20	1.10	38.28	M3		
	2	30.00	2.00	1.15	138.00	M3		
	1	25.00	2.50	0.60	37.50	M3		
	1	20.00	3.00	0.80	48.00	M3		
	1	30.00	3.00	0.40	36.00	M3		
	1	16.00	2.50	0.30	12.00	M3		
	1	28.00	1.45	0.30	12.18	M3		
	1	25.00	1.60	0.50	20.00	M3		
Less for H.P.	0	1.23	1.23	0.95	0.00	M3	2412.11	14172112
					587.54	M3	2427.65	1426341.48
Providing & laying 1000 MM Dia NP3 Hume Pipe in single row -do-do- complete job.	0	2.50			0.00	M	4159.56	0.00
								14172112
								1426341.48
Add 1 % Contingency								14172112
								14263.41
							Total	1440604.90
							Say	1440600.00

R. 14313832
Say Rs 14.314 Lacs.

[Signature]
25/10/2020
J.E.

[Signature]
25/10/2020
A.E.

[Signature]
25/10/20
E.E.

Technically Approved for Rs 14.314 Lacs (Rupees Fourteen Lacs
Thirty one Thousand & Four Hundred) only


21/01/21

Superintending Engineer
RWO Works Circle, Siwan

R/works
21/01/2021
4