

## Inspection Report For Flood Damage Work

	1	te	2	
57			_	

1 Name of PIUs:

Gopalgani - 2

2 Name of Block/Road: Baikunthopus | Gamhari Samudyeek Bhawas Se Shing For Road Brain Hote Lue Pakaha Bandh

A For Road

1 Damage Location / Chainage: 90 m to 150 m, 200 m to 490 m

2 Damage Length:

333,000

3 Nature of Damage:

Heavy Rain / Flood.

4 Details of Restroration Works:

Material being used in Restoration Works:

Brick Both

ii Equipments / Tools being used in Restoration Works: JCB, Tractor, Tooli, Belcha Shoud

iii Procedure taken up In Restoration Works: Yes

iv Restored Length:

333,000

B For Bridge

N/A

- 1 Damage Location / Chainage:
- 2 Damage Length:
- 3 Nature of Damage:
- 4 Details of Restroration Works:
  - i. Material being used in Restoration Works:
  - ii Equipments / Tools being used in Restoration Works:
  - iii Procedure taken up In Restoration Works:

iv Restored Length:

24.11.30 SV







## गामाता केंद्र विभाग

Rural Works Department, Govt. of Bihar

## FLOOD DAMAGED REPAIR (F.D.R.)

STATE :- BIHAR

DISTRICT :- GOPALGANJ

BLOCK :- BAIKUNTHPUR

Gamahari Samudyaek Bhawan Se Shivraj Brahm Hote Hue Pakaha Bandh

ESTIMATED COST - RS.

1451100.00

SUBMITTED BY :-

EXECUTIVE ENGINEER
RWD (W) DIVISION
GOPALGANJ-2

## Report

Name of Work

:- Motorable work of Gamahari Samudyaek Bhawan Se Shivraj Brahm Hote Hue Pakaha Bandh

Estimated Cost

:- 1451100.00

**Total length of Road** 

:-

km

Description :- The present estimate has been farmed under the supervision of Assistant engineer in accordance with the order of Executive Engineer, RWD, WD Gopalganj-2, letter No. - 1574 dated 18-08-2020. The part of above mentioned road has been damaged due to heavy rain/flood. And due to this damage the transporation has been obstructed. The immediate motorable work is necessary in public interest. Villagers will be benefitted by the completion of this motorable work.

In the estimate there has been a provision of repairing the damaged part of the road & making it motorable by filling brickbats. In the context of post flood scenario there is still the flow of water which prevails through the damaged part of the road. Hence there has been a provision of laying 1 Nos of R.C.C. NP3 1000 MM Dia hume pipe.

In this estimate the rate of raw materials and labour wages has been prepared after the analysis of new rate. This estimate is as per the specifications. The estimate is devoted to technical and administrative acceptance.

J.E.

A.E.

Jose 10:000

25/10/20 E.F. etailed Estimate For Motorable Work in Road from Gamahari Samudyaek Bhawan Se Shivraj Brahm Hote Hue Pakaha Bandh damaged due to Heavy rain/flood for

-			ye	ar 2020-:	2021				
•		No.	L (M.)	W (M.)	D (M.)	Qty.	Unit	Rate	Amount
	Providing brick bats billed in ditches including all cost of labour & material with all complete job.								
	CH - 90 M to 150 M	1	11.00	3.00	0.30	9.90	МЗ		
		1	12.00	2.00	0.45	10.80	МЗ		
		1	13.00	1.50	0.30	5.85	МЗ		
		1	15.00	1.20	0.35	6.30			
		1	15.00	1.05	0.30	4.73	МЗ		
		1	21.00	1.60	1.50	50.40	МЗ		
_	CH - 200 M to \$40 M	1	15.00	3.00	0.30	13.50	МЗ		
_		1	16.00	2.40	0.50	19.20	M3		
		1	20.00	2.10	0.60	25.20	МЗ		
		1	28.00	2.00	0.40	22.40	мз		
		1	26.00	2.15	1.30	72.67	МЗ		
		1	24.00	2.30	1.40	77.28	МЗ		
		1	30.00	2.50	1.55	116.25	М3	=	
		1	24.00	2.00	0.50	24.00	МЗ		
		1	15.00	3.00	1.00	45.00	МЗ		
		1	15.00	1.00	1.50	22.50	МЗ		
		1	30.00	1.00	2.10	63.00	МЗ		
		1	3.00	0.30	0.30	0.27	мз		
	Less for H.P.	0.79	1.23	1.23	5.00	5.98	МЗ	072.5307.89	programmer
_						583.27		2427:65	1415973.10
2	Providing & laying 1000 MM Dia NP3 Hume Pipe in single row -do-do- complete job.	2	2.50			5.00	м	2744-50° 4159.56	1372371 -20797:80
									14206742
	Add 1 % Contigency								1436770.90
								Total	14511/38.61
-	Jul 20				10 -			Say	1451100.00

Malya VO Works Circle, Savan