

Inspection Report For Flood Damage Work

Date :

1 Name of PIUs :

Gopalgarh - 2

2 Name of Block/Road :

Baikunthpur / Shivrath Ray Ke Bhalg Se Rajkumari
Singh Ke Pokhara Tak

A For Road

1 Damage Location / Chainage :

0 m to

2 Damage Length :

265.00 m

3 Nature of Damage :

Heavy Rain / Flood

4 Details of Restoration Works:

i. Material being used in Restoration Works: Brick Balls

ii Equipments / Tools being used in Restoration Works: JCB, Tractor, Tools, Balah, Shovel
etc

iii Procedure taken up in Restoration Works: Yes

iv Restored Length:

265.00 m

B For Bridge

1 Damage Location / Chainage:

2 Damage Length:

3 Nature of Damage:

4 Details of Restoration Works:


i. Material being used in Restoration Works :

ii Equipments / Tools being used in Restoration Works :

iii Procedure taken up in Restoration Works:

iv Restored Length :


 24/11/2020
 AE


 24.11.2020
 EE


 24/11/20
 EE


 03/11/21
 Signature
 (Executive Engineer)
 R.W.D. W.D.
 Hathua



ग्रामीण कार्य विभाग

Rural Works Department, Govt. of Bihar

FLOOD DAMAGED REPAIR (F.D.R.)

STATE :- BIHAR
DISTRICT :- GOPALGANJ
BLOCK :- BAIKUNTHPUR

Shivnath Ray Ke Dhala Se Raghunath Singh Ke Pokhara Tak

ESTIMATED COST - RS. 1407300.00

SUBMITTED BY :-
EXECUTIVE ENGINEER
RWD (W) DIVISION
GOPALGANJ-2

Report

Name of Work :- Motorable work of Shivnath Ray Ke Dhala Se Raghunath Singh Ke Pokhara Tak

Estimated Cost :- 1407300.00


Total length of Road :- 1.900 km

Description :- The present estimate has been farmed under the supervision of Assistant engineer in accordance with the order of Executive Engineer, RWD, WD Gopalganj-2, letter No. - 1574 dated 18-08-2020. The part of above mentioned road has been damaged due to heavy rain/flood. And due to this damage the transporation has been obstructed. The immediate motorable work is necessary in public interest. Villagers will be benefitted by the completion of this motorable work.

In the estimate there has been a provision of repairing the damaged part of the road & making it motorable by filling brickbats. In the context of post flood scenario there is still the flow of water which prevails through the damaged part of the road. Hence there has been a provision of laying 1 Nos of R.C.C. NP3 1000 MM Dia hume pipe.

In this estimate the rate of raw materials and labour wages has been prepared after the analysis of new rate. This estimate is as per the specifications. The estimate is devoted to technical and administrative acceptance.


25/10/2020
J.E.


25.10.2020
A.E.


25/10/20
E.E.

Sr.	Items	No.	L (M.)	W (M.)	D (M.)	Qty.	Unit	Rate	Amount
1	Providing brick bats billed in ditches including all cost of labour & material with all complete job.								
	CH - 0 M to 1000 M	1	7.00	1.75	0.50	6.13	M3		
		1	10.00	1.10	0.60	6.60	M3		
		1	12.00	1.10	0.30	3.96	M3		
		1	15.00	1.50	0.60	13.50	M3		
		1	8.00	6.00	0.80	38.40	M3		
		1	19.00	6.00	0.84	95.76	M3		
		1	23.00	3.00	1.00	69.00	M3		
		1	8.00	5.00	0.60	24.00	M3		
		1	12.00	5.00	1.50	90.00	M3		
		1	5.00	5.50	0.60	16.50	M3		
		1	15.00	4.00	1.40	84.00	M3		
		1	27.00	3.00	0.60	48.60	M3		
		1	10.00	2.50	0.20	5.00	M3		
		1	24.00	3.00	0.20	14.40	M3		
		1	20.00	5.00	0.20	20.00	M3		
		1	15.00	3.00	0.35	15.75	M3		
		1	20.00	1.50	0.50	15.00	M3		
		1	15.00	0.80	0.40	4.80	M3		
			265.00						
	Less for H.P.	0.79	1.23	1.23	5.00	5.98	M3		
						565.42		2427.65	1363855
								2427.65	1372322
2	Providing & laying 1000 MM Dia NP3 Hume Pipe in single row -do-do- complete job.	2	2.50			5.00	M	4159.56	20797.80
									1372322
									1393437.34
	Add 1 % Contingency								1393437
									1393437
								Total	1407300.00
								Say	1407300.00


[Signature]
25/10/2020
J.E.

[Signature]
25.10.2020
A.E.

[Signature]
25/10/20
E.E.

R 139135420
Say R 13.9146

Technically Approved for Rs. 13.914 lac (Rupees Thirteen Lac.
Ninety one Thousand & Four Hundred) only


21/01/21

Superintending Engineer
RWD W. of Dist. Jan
R. S. S.
21/01/21
u