

Inspection Report For Flood Damage Work

Date :

1 Name of PIUs: Bapalganj-22 Name of Block/Road: Baikunthpur / Sonwalya R.E.O Road Shambhu Dube Ke
ghas Kali Sthan Sasan Bandh Tak

A For Road

1 Damage Location / Chainage: 0 M To 1000 M.2 Damage Length: 156.10 M.3 Nature of Damage: Heavy Rain/Flood.

4 Details of Restoration Works:

i. Material being used in Restoration Works:

Bozok Bala.

ii Equipments / Tools being used in Restoration Works:

JCB, Tractor, Trulli, Boleha, Shawal etciii Procedure taken up in Restoration Works: yesiv Restored Length: 156.10 M.

B For Bridge

N/A

1 Damage Location / Chainage:

2 Damage Length:

3 Nature of Damage:

4 Details of Restoration Works:

i. Material being used in Restoration Works :

ii Equipments / Tools being used in Restoration Works :

iii Procedure taken up in Restoration Works:

iv Restored Length :

[Signature]
24/11/2020
AE[Signature]
24.11.2020
AE[Signature]
24/11/20
EE[Signature]
24/11/20
Signature
Executive Engineer
(Name of Inspector)
R.W.D. W.D.
Hathua



ग्रामीण कार्य विभाग

Rural Works Department, Govt. of Bihar

FLOOD DAMAGED REPAIR (F.D.R.)

STATE :- BIHAR
DISTRICT :- GOPALGANJ
BLOCK :- BAIKUNTHPUR

Sonwaliya REO Road Shambhu Dube Ke Ghar Kali Sthan Saran Bandh Tak

ESTIMATED COST - RS. 1520500.00

**SUBMITTED BY :-
EXECUTIVE ENGINEER
RWD (W) DIVISION
GOPALGANJ-2**

Report

Name of Work :- Motorable work of Sonwaliya REO Road
Shambhu Dube Ke Ghar Kali Sthan Saran
Bandh Tak

Estimated Cost :- 1520500.00


Total length of Road :- km


Description :- The present estimate has been farmed under the supervision of Assistant engineer in accordance with the order of Executive Engineer, RWD, WD Gopalganj-2, letter No. - 1574 dated 18-08-2020. The part of above mentioned road has been damaged due to heavy rain/flood. And due to this damage the transporation has been obstructed. The immediate motorable work is necessary in public interest. Villagers will be benefitted by the completion of this motorable work.

In the estimate there has been a provision of repairing the damaged part of the road & making it motorable by filling brickbats. In the context of post flood scenario there is still the flow of water which prevails through the damaged part of the road.

In this estimate the rate of raw materials and labour wages has been prepared after the analysis of new rate. This estimate is as per the specifications. The estimate is devoted to technical and administrative acceptance.


25/10/2020
J.E.


25.10.2020
A.E.


25/10/20
E.E.

**Detailed Estimate For Motorable Work in Road from Sonwalia REO Road
Shambhu Dube Ke Ghar Kali Sthan Saran Bandh Tak damaged due to Heavy
rain/flood for year 2020-2021**

Items	No.	L (M.)	W (M.)	D (M.)	Qty.	Unit	Rate	Amount
Providing brick bats billed in ditches including all cost of labour & material with all complete job.								
CH - 0 M to 1000 M	1	28.00	1.00	0.80	22.40	M3		
	1	20.00	6.00	4.50	540.00	M3		
	1	15.00	3.00	0.30	13.50	M3		
	1	4.00	1.00	0.50	2.00	M3		
	1	20.00	1.65	0.50	16.50	M3		
	1	14.00	1.60	0.60	13.44	M3		
	1	6.00	1.50	0.30	2.70	M3		
	1	8.00	2.00	0.40	6.40	M3		
	1	10.00	2.30	0.30	6.90	M3		
	1	15.00	3.00	0.30	13.50	M3		
	1	16.00	1.20	0.35	6.72	M3		
Less for H.P.	3.16	1.23	1.23	5.00	23.90	M3	2412.11	1495894.20
					620.16		2427.65	1505522.15
Providing & laying 1000 MM Dia NP3 Hume Pipe in single row -do-do- complete job.	0	2.50			0.00	M	4159.56	0.00
								1495894.20
								1505522.15
Add 1 % Contingency							1495920	15055.22
							Total	1520577.37
							Say	1520500.00

Rs 1510853.20
Say Rs 15.109 lacs

[Signature]
25/10/2020
J.E.

[Signature]
25.10.2020
A.E.

[Signature]
25/10/20
E.E.

Technically Approved for Rs 15.109 lacs (Rupees Fifteen lacs
Ten Thousand & Nine Hundred) only

[Signature]
21/10/21
Superintending Engineer
RWD Works Circle, Siwan