

Inspection Report For Flood Damage Work

Date :

1 Name of PILs: ~~Govt~~ Gopalganj-2.

2 Name of Block/Road: Baikunthpur/ R.E.D Road Gamhasi se Salempur.

A For Road

1 Damage Location / Chainage: 600m to 1100m.

2 Damage Length: 371.00m.

3 Nature of Damage: Heavy Rain/Flood.

4 Details of Restoration Works:

i. Material being used in Restoration Works: Bozok Bats

ii Equipments / Tools being used in Restoration Works: JCB, Trolly, Tractor, Belching Shovel etc.

iii Procedure taken up in Restoration Works: YES

iv Restored Length: 371.00m

B For Bridge

N/A

1 Damage Location / Chainage:

2 Damage Length:

3 Nature of Damage:

4 Details of Restoration Works:

i. Material being used in Restoration Works:

ii Equipments / Tools being used in Restoration Works:

iii Procedure taken up in Restoration Works:

iv Restored Length:

[Signature]
24/11/2020
JE

[Signature]
24.11.2020
AE

[Signature]
24/11/20
EE

[Signature]
13/01/21
Signature
Executive Engineer
(Name of Inspector)
R.W.D. W.D.
Hathua



ग्रामीण कार्य विभाग

Rural Works Department, Govt. of Bihar

FLOOD DAMAGED REPAIR (F.D.R.)

STATE :- BIHAR
DISTRICT :- GOPALGANJ
BLOCK :- BAIKUNTHPUR

REO Road Ghamhari Se Salempur

ESTIMATED COST - RS. 1558400.00

SUBMITTED BY :-
EXECUTIVE ENGINEER
RWD (W) DIVISION
GOPALGANJ-2

Report

Name of Work :- Motorable work of REO Road Ghamhari Se Salempur


Estimated Cost :- 1558400.00


Total length of Road :- km

Description :- The present estimate has been farmed under the supervision of Assistant engineer in accordance with the order of Executive Engineer, RWD, WD Gopalganj-2, letter No. - 1574 dated 18-08-2020. The part of above mentioned road has been damaged due to heavy rain/flood. And due to this damage the transporation has been obstructed. The immediate motorable work is necessary in public interest. Villagers will be benefitted by the completion of this motorable work.

In the estimate there has been a provision of repairing the damaged part of the road & making it motorable by filling brickbats. In the context of post flood scenario there is still the flow of water which prevails through the damaged part of the road.

In this estimate the rate of raw materials and labour wages has been prepared after the analysis of new rate. This estimate is as per the specifications. The estimate is devoted to technical and administrative acceptance.


25/10/2020
J.E.


25.10.2020
A.E.


25/10/20
E.E.

**Detailed Estimate For Motorable Work in Road from REO Road Ghamhari Se
Salempur damaged due to Heavy rain/flood for year 2020-2021**

Items	No.	L (M.)	W (M.)	D (M.)	Qty.	Unit	Rate	Amount
Providing brick bats billed in ditches including all cost of labour & material with all complete job.								
CH - 600 M to 1100 M	1	15.00	1.50	0.30	6.75	M3		
	1	25.00	2.00	0.30	15.00	M3		
	1	15.00	1.00	0.50	7.50	M3		
	1	25.00	2.10	1.00	52.50	M3		
	1	30.00	2.40	1.00	72.00	M3		
	1	24.00	2.50	0.35	21.00	M3		
	1	30.00	2.30	1.10	75.90	M3		
	1	30.00	1.20	1.20	43.20	M3		
	1	26.00	4.20	1.20	131.04	M3		
	1	24.00	2.30	0.80	44.16	M3		
	1	26.00	2.40	0.50	31.20	M3		
	1	30.00	1.30	0.65	25.35	M3		
	1	26.00	1.20	0.60	18.72	M3		
	1	27.00	5.00	0.50	67.50	M3		
	1	18.00	2.20	0.60	23.76	M3		
					635.58	M3	2427.65	1533089.20
Providing & laying 1000 MM Dia NP3 Hume Pipe in single row -do-do- complete job.	0	2.50			0.00	M	4159.56	0.00
								1533089.20
								1542965.79
Add 1 % Contingency							15331.20	15429.66
							Total	1558395.44
							Say	1558400.00

Rt 1548420.20
Sump Rs 15.4846

[Signature]
25/10/2020
J.E.

[Signature]
25.10.2020
A.E.

[Signature]
25/10/20
E.E.

Technically Approved for Rs 15.484 Lac (Rupees Fifteen Lac Forty Eight Thousand & Four Hundred) only


21/01/21

Superintending Engineer
Circle No. 01

R. Kumar
21/01/2021
4