

ABSTRACT

Road Name- Temporary Restoration of Road from T04,NH To Manihas
Kansi

Block-DARBHANGA

RWD (W) DIVISION DARBHANGA -1

Road Actual Length - 2.30 KM

Effect Road Length - 422.10 M.

S.No.		UNIT	QUANTITY	RATE	AMOUNT (Rs)
1	Providing and filling bricks bats in ditches including cost of bricks bats and labour all complete job as per specification and direction of E/I.	CUM	324.127		605391=00
	Add G.S.T. 12 %		324.877	1867.76	606792
	Add 1 % Labor cess				72815
	Seigniorage Fee @1063.00/cum x0.10				6068
					34534
					720210

72647=00

6054=00

34455=00

718,547=00

Rs - 7,18,547=00

[Signature]
J.E.

Work Section Darbhanga-2

[Signature]
A.E.

Work Sub-Division
Darbhanga

[Signature]
E.E.

RWD Darbhanga -1

कार्यपालक अभियंता द्वारा कार्य के कार्यप्रमंडल - कुलप्राप्त के पत्रांक 542 अ
दिनांक 07/04/2021. के द्वारा समर्पित ऑफ प्रविष्टि के आधार पर।
Post-Recto T/A for Rs - 7,18,547=00 (Rupees Seven
Eighteen thousand five hundred forty seven) only.

09.04.21
Superintending Engineer

RWD, Works Circle, Darbhanga.

09/04/2021

Detailed Estimate for Temporary Restoration of T04, NH TO Manihas Kansi road for the year 2020 -21.

k-Darbhangha

Total Restoration Length -422.10 M

.D.[W] Division -Darbhanga -1

Length -2.30 KM

item	No.	Length (M)	Width(M)	Depth (M)(AV)	Quantity (cum)
1 Providing and filling bricks bats in ditches including cost of bricks bats and labour all complete job as per specification and direction of E/I .					
Chainage in M					
200	1	3.50	1.50	0.250	1.313
	1	18.50	0.25	1.500	6.938
	1	10.00	0.30	1.500	4.500
	1	2.50	1.50	0.250	0.938
400	1	1.50	1.10	0.200	0.330
600	1	25.00	1.00	0.250	6.250
	2	25.00	1.10	0.250	13.750
	1	50.00	0.90	0.250	11.250
	1	6.50	0.50	0.300	0.975
	1	10.00	0.50	0.225	1.125
	1	10.00	0.60	0.250	1.500
	1	6.00	0.30	0.250	0.450
	1	5.00	1.25	0.450	2.813
	1	8.00	1.00	0.300	2.400
950	1	36.00	0.90	0.600	19.440
	1	2.60	0.90	0.450	1.053
	1	4.20	4.00	0.450	7.560
	1	0.80	1.10	0.300	0.264
	1	1.00	1.00	0.300	0.300
	1	1.00	1.50	0.300	0.450
1135	1	72.00	3.25	0.250	58.500
	1	4.00	3.50	1.300	18.200
	1	9.00	3.00	0.300	8.100
	1	22.00	3.80	0.300	25.080
	1	30.00	3.80	0.300	34.200
	1	10.00	3.60	(0.30+0.90)/2	21.600
1282	1	48.00	3.50	0.450	75.600
Total Qty .					324.877

3.75

30/12/20
S.E.

R

324.127

Signature