

FDR

DISTRICT :- DARBHANGA

BLOCK :- BAHADURPUR

Name of Road :- MANIYARI TO HARIJAN TOLA

Length of the Road:- 2.330 KM.

Effective Length 2.000 KM.

GENERAL ABSTRACT OF COST

SI No.	Item of Work	Amount (in Rs.)
1	Cost for restoration	17,49,740
2	Add 12 % GST	2,23,266.28
3	Add seigniorage	1,05,889.79
4	Add 1 % Labour Cess	18,605.52
Total cost:-		20,76,789.32

14/12/2020
Junior Engineer
Bahadurpur

Say Rs 20,76,789=00
Assistant Engineer
Bahadurpur

Executive Engineer
R.W.D.(W) Division, Darbhanga-1

कार्यपत्रक अग्नियता, जा० का० वि०, कार्यपत्रक - पुरापुरा का पत्रक
दिनांक 07/04/2021 को द्वारा समर्पित जाँच प्रतिवेदन का आदेश

Post-fee to T/A for Rs 20,76,789=00 (Rupees Twenty lac
seventysix thousand seven hundred eighty nine) only.

09/04/2021
RWD, Works Circle, Darbhanga

Detailed estimate for making moterale road.

Name of Road :- MANIYARI TO HARIJAN TOLA
 BLOCK :- BAHADURPUR
 DISTRICT :- DARBHANGA
 R.W.D. Works Division Darbhanga-1

Sl. No.	Item	Unit	No.	Length (m)	Avg. Bre adth (m)	Avg. De pth / Height	Quantity	Rate	Amount
1	Labour and placing of brick bats with light raming including cost of brick bats by tractor	cum	From MANIYARI						
			0.000 KM to 2.000 KM.						
			2	3.50	0.80	0.600	3.360		
			1	10.00	1.50	1.200	18.000		
			1	20.50	2.13	1.500	65.498	64.58	
			1	18.00	6.66	0.800	96.048	95.04	
			1	8.50	3.80	0.800	25.840		
			1	8.80	1.20	1.200	12.672		
			1	7.50	1.10	1.200	9.900		
			7	30.00	1.41	1.1200	367.920	323.40	
			1	3.00	3.50	0.600	6.300		
			2	5.20	0.80	0.600	4.992		
			1	8.60	0.80	0.800	5.504		
			1	5.50	0.80	0.600	2.640		
			1	9.00	0.80	0.600	4.320		
			1	5.50	1.00	0.800	4.400		
			1	5.80	0.90	0.600	3.132		
			1	7.50	1.00	0.800	6.000		
			1	17.50	1.60	0.600	16.800		
			1	8.40	1.07	0.800	7.190		
			1	7.50	1.00	0.800	6.000		
			1	12.50	1.07	1.000	13.375		
			1	5.20	0.80	0.600	2.496		
			2	2.80	1.90	0.800	8.512		
			1	4.80	1.07	0.800	4.109		
			3	0.60	0.60	0.200	0.216		
			1	17.20	1.10	1.200	22.704	18.92	
			1	7.50	1.60	0.300	3.600		
			1	9.50	1.63	0.300	4.646		
			2	1.50	1.50	0.300	1.350		
			1	7.50	2.63	0.400	7.890		
			1	9.50	2.60	0.400	9.880		
			3	1.80	1.00	0.300	1.620		
			3	1.50	1.60	0.300	2.160		
			1	4.20	1.80	0.300	2.268		
			1	8.50	1.70	0.400	5.780		
			1	1.60	1.50	0.300	0.720		
			1	8.60	0.55	0.400	1.892		
			1	2.50	0.40	0.300	0.300		
			1	8.80	3.15	0.450	12.474		
			1	10.80	2.70	0.800	23.328	21.87	
			1	2.40	3.30	0.800	6.336		
			1	2.50	0.80	1.200	2.400		
			1	2.80	2.20	1.500	9.240		
			1	3.50	1.60	1.500	8.400		
			1	5.50	1.40	0.800	6.160	5.78	
			1	8.50	3.55	1.200	36.720	36.21	
			1	7.80	0.77	0.300	1.802		
			1	2.00	1.80	0.300	1.080		
			3	0.60	0.60	0.300	0.324		
			3	30.00	1.50	0.800	108.000	101.25	
			2	2.50	1.40	0.400	2.800		
			2	1.80	1.30	0.300	1.404		
			1	8.50	2.30	0.800	15.640		


936.812

17,49,740 = 00

				Total	996.14	1867.76	1860552.31
							1860552.31


14/12/2020
Junior Engineer
Bahadurpur


Assistant Engineer
Bahadurpur


Executive Engineer
R.W.D.(W) Division, Darbhanga-1