

ABSTRACT
Road Name- Temporary Restoration of Road from Purana NH -57 Mahua
Per to Hingauli .

Effect Road Length - 759.00 M.

S.No.	UNIT	QUANTITY	RATE	AMOUNT (Rs)
1	CUM	391.236	1867.76	730735.20
		407.556		761217
				91346.87
				761217.00
				43323
				903498
				867,318.20

Rs - 8,67,318.20

80/12/20
J.E.

Work Section Darbhanga-2

[Signature]
30/12/22
A.E.

Work Sub-Division
Darbhanga

E.E.
RWD Darbhanga -1

कार्यपालक अभियंता द्वारा कार वि. कार्य प्रमंडल - कुलप्राप्त के पत्र कि 542
दिनांक 07/09/2021. / के द्वारा समर्पित ऑय प्रविवेदन के आया पर।
Post-Facto T/A. for Rs - 8, 67, 318-21 (Rupees Eight
Sixty Seven thousand three hundred eighteen) only.
09.04.21

Superintending Engineer
RWD Works Circle, Darbhanga
09/04/2024

**Detailed Estimate for Temporary Restoration of Purana NH-57 Mahua per to Hingauli
for the year 2020 -21.**

Block -Darbhanga

R.W.D.[W] Division -Darbhanga -1

Total Restoration Length -759.00 M

Length -1.005 KM

S.N.	item	No.	Length (M)	Width(M)	Depth (M)(AV)	Quantity (cum)
1	Providing and filling bricks bats in ditches including cost of bricks bats and labour all complete job as per specification and direction of E/I.					
	Chainage in M					
	(Right Side) 0-69	1	69.00	0.30	(1.70+2.30)/2	41.400
	69	1	4.00	1.20	0.350	1.680
	73-129	1	56.00	0.50	0.300	8.400
	168-329	1	161.00	0.60	0.350	33.810
	336	1	59.00	0.60	0.450	15.930
	395	1	26.00	1.20	0.300	9.360
	521	1	8.00	1.50	0.225	2.700
	530	1	34.00	0.75	0.300	7.650
	564	1	92.00	0.90	0.300	24.840
	656	1	62.00	1.25	0.300	23.250
	656	1	6.00	3.70	0.225	4.995
	718	1	35.00	0.30	1.500	15.750
	773	1	9.00	0.30	2.200	5.940
	790	1	46.00	(0.60+0.90)/2	1.500	51.750
	836	1	36.00	0.30	0.750	8.100
	904	1	50.00	0.75	0.250	9.375
	1000	1	6.00	0.50	0.250	0.750
	Left Side					
	26	1	24.00	1.00	0.300	7.200
	76	1	59.00	0.90	0.300	15.930
	247	1	11.00	0.50	0.250	1.375
	263	1	7.00	0.50	0.250	0.875
	291	1	30.00	0.50	0.300	4.500
	374	1	8.00	0.50	0.300	1.200
	394	1	11.00	0.45	0.200	0.990
	421-567	1	145.00	0.45	0.225	14.681
	567-656	1	89.00	0.90	0.225	18.023
	656-718	1	62.00	0.25	0.80 1.250	19.375 12.40
	718-753	1	35.00	0.30	1.00 1.250	13.125 10.5
	773-829	1	56.00	0.30	0.80 1.200	20.160 13.1

30/12/20
J-6

30/12/20
PC

page no (02/02)

lock -Darbhanga

.W.D.[W] Division -Darbhanga -1

Total Restoration Length -759.00 M


Length -1.005 KM

S.N.	item	No.	Length (M)	Width(M)	Depth (M)(AV)	Quantity (cum)
	829-880	1	51.00	0.60	0.300	9.180
	886-899	1	13.00	0.45	0.250	1.463
	906-923	1	17.00	0.60	0.250	2.550
	980-1005	1	25.00	0.30	1.500	11.250

TOTAL QTY.

~~407.556~~
391.236


J.E.


30/12/20
A.E.


E.E.

RWD(W) Division Darbhanga -1