

Detailed Estimate for Restoration/Motorable of Road damaged during Flood'2020

GENERAL ABSTRACT OF COST

HEAD FDR DIVISION JAYNAGAR
YEAR 19-20 BLOCK Basopatti
NAME OF ROAD : L037-T04 To Patauna (VR037)

UNDER CONSTRUCTION

UNDER MAINTENANCE/ OUT OF
MAINTENANCE

Damage length 28.300

Description	Unit	Quantity	Rate (Rs.)	Amount (Rs.)
Providing and filling brick bats in ditches including cost of brick bats and labour all complete job as per specification and direction of E/I.	Cum	26.91	1867.76	50261.00
			Total =	50261.00
			Add GST @ 12%	6031.00
			Add L.Cess @ 1%	503.00
Add Seignorage Fee	26.91 m ³	x Rs. 1063.00	x 10.0%	2861.00
			Grand Total =	₹ 59,656

Grand Total= 59656.00

Fifty Nine Thousand Six Hundred and Fifty Six only.

कार्यपालक अभियंता ग्रा. का. वि. कार्य प्रमंडल मंझारपुर का पत्रांक-336 आनु दिनांक 12-04-2021 के द्वारा सुप्रार्थित ऑन प्रलिवेदन के कारगर पर:-

Post Pcto T/A (Rs. 59656) (Rupees fifty Nine thousand Six hundred fifty six) only

Superintending Engineer
RWD, Works Circle, Darbhanga

J.E.
Works division Jaynagar

W. Jaynagar

E.E.
Works division Jaynagar

Detailed Estimate for Restoration/Motorable of Road damaged during Flood'2020

HEAD

FDR

NAME OF ROAD : L037-T04 To Patauna (VR037)

LENGTH OF ROAD 3.21 km

BLOCK : Basopatti

DIVISION : JAYNAGAR

Damage length : 28.30

CIRCLE : DARBHANGA

Measurement Brick bat

CH	Nos	Length	Width			Avg Width	Depth			Avg Depth	Qty (cum)	
3200	1	2	1.5	0	0	1.5	0.3	0	0	0.3	0.9	
2200 TO 2500	1	2.5	3	0	0	3	0	0.5	0.3	0.4	3	
2200 TO 2500	1	2	0.7	0.75	0	0.73	1	0	0	1	1.45	
2200 TO 2500	1	2.5	2	0	0	2	0.7	0	0	0.7	3.5	
2100 TO 2150	1	2	1.3	0	0	1.25	0.6	0	0	0.6	1.5	
2100 TO 2150	1	2	1.5	0	0	1.5	0.5	0	0	0.5	1.5	
2100 TO 2150	1	2	1	0	0	1	0.2	0	0	0.2	0.4	
2100 TO 2150	1	1.2	1	0	0	1	0.7	0.6	0	0.65	0.78	
1900	1	3	2.3	0	0	2.25	0.6	0	0	0.6	4.05	
1750 TO 1800	1	3	0.6	0	0	0.6	0.3	0	0	0.3	0.54	
1750 TO 1800	1	2.5	1	0	0	1	0.6	0	0	0.6	1.5	
1500 TO 1550	1	2.6	2.7	0	0	2.7	1	0	0	1	7.02	
1500 TO 1550	1	1	0.7	0	0	0.7	1.1	0	0	1.1	0.77	
Total Qty											26.910	


J.E


25/12/2020
A.E


E.E