

Detailed Estimate for Restoration/Motorable of Road damaged during Flood'2020

Block : Babubarhi

Division : Jaynagar

Circle : Darbhanga

ABSTRACT OF COST

Name of Road : L038 Babubarhi to Tirhuta


Length of Road : 5.804 Km

Estd. Length : 77 Mtr.

Sl. NO.	Item of Works	Unit	Quantity	Rate	Amount (Rs.)
1-	Providing and filling brick bats in ditches including cost of brick bats and labour all complete job as per specification and direction of E/I.	CUM	30.52	1867.76	57004.00 ✓
				Total Rs.	57004.00 ✓
				Add GST @ 12%	6840.00 ✓
				Add L.Cess @ 1%	570.00 ✓
	Add Seignorage Fee		30.52 m ³ x Rs. 1063.00 x 10 %		3244.00 ✓
				Grand Total Rs.	67658.00 ✓

Say ₹ 67,700.00

₹ 67658.00


Junior Engineer
Babubarhi


Assistant Engineer
Babubarhi


Executive Engineer
RWD Work Division,
Jaynagar.

कार्यपालक अभियन्ता द्वारा जारी वि० कार्य प्रमाणिका संख्या 336/2021 दि० 12-04-2021 के द्वारा स्वीकृत और प्रमाणित के आधार पर

Post-facto T/A for Rs 67658.00 (Rupees Sixty Seven thousand - Six hundred fifty eight) only.

13-04-21

Superintending Engineer
Works Circle, Darbhanga

Detailed Estimate for Restoration/Motorable of Road damaged
during Flood'2020

Name of Road : L038 Babubarhi to Tirhuta

Length of Road : 5.804 KM


Estd. Length : 77 Mtr.


Block : Babubarhi

Division : Jaynagar

Circle : Darbhanga

S.N.	ITEM OF WORKS	MEASUREMENT (L x B x H/D)	QUANTITY
1-	Providing and laying Brick Bats including -- do -- do -- E/I. CH- 2.000 to 3.000 Km		
		1 x 5.00 x 1/2(0.75 + 1.05) x 1/2(0.30 + 0.30) =	1.35 m ³ ✓
		1 x 15.00 x 1/2(1.05 + 1.45) x 1/2(0.30 + 0.45) =	7.03 ✓
		1 x 25.00 x 1/2(1.35 + 1.50) x 1/2(0.30 + 0.45) =	13.36 ✓
		1 x 10.00 x 1/2(1.00 + 1.25) x 1/2(0.30 + 0.50) =	4.50 ✓
		1 x 5.00 x 1/2(1.00 + 0.60) x 1/2(0.30 + 0.30) =	1.20 ✓
		19 x 0.90 x 1/2(0.60 + 0.60) x 1/2(0.30 + 0.30) =	3.08 ✓
		<u>0</u> x 1.50 x 1/2(1.75 + 2.25) x 1/2(0.30 + 0.60) =	<u>0.00</u>
		Total	30.52 m³ ✓


16/12/20
Junior Engineer
Babubarhi


19/12/20
Assistant Engineer
Babubarhi


15/12/20
Executive Engineer
RWD Work Division,
Jaynagar.