

Detailed Estimate for Restoration/Motorable of Road damaged
during Flood'2020

Block : Babubarhi

Division : Jaynagar

Circle : Darbhanga

ABSTRACT OF COST

Name of Road : L054 Tirhuta to Balansher

Length of Road : 1.600 Km

Estd. Length : 78 Mtr.

Sl. NO.	Item of Works	Unit	Quantity	Rate	Amount (Rs.)
1-	Providing and filling brick bats in ditches including cost of brick bats and labour all complete job as per specification and direction of E/I.	CUM	61.31	1867.76	114512.00
				Total Rs.	114512.00
				Add GST @ 12%	13741.00
				Add L.Cess @ 1%	1145.00
					6517.00
	Add Seignorage Fee		61.31 m ³ x Rs. 1063.00 x 10 %		
				Grand Total Rs.	135915.00
				Say	₹ 1,35,900.00



Junior Engineer
Babubarhi



Assistant Engineer
Babubarhi




Executive Engineer
RWD Work Division,
Jaynagar.

कम्प्यूटर, अभिलेखी 2110 को विट कार्य प्रमाणित अभिलेख का पत्रिकः 336 आगु रुद्रिक 12-04-2021 ई

द्वारा समीपित ज्ञान प्रविष्टन के आधार पर :-

Post fee to T/A for Rs 1,35,900 = 10 (Rupees) One Lac thirty

five thousand Nine hundred fifteen) only.


13-04-21
Superintending Engineer
RWD, Works Circle, Darbhanga

13/04/2021

Detailed Estimate for Restoration/Motorable of Road damaged
during Flood'2020

Name of Road : L054 Tirhuta to Balansher

Length of Road : 1.600 KM

Estd. Length : 78 Mtr.

Block : Babubarhi

Division : Jaynagar

Circle : Darbhanga

S.N.	ITEM OF WORKS	MEASUREMENT (L x B x H/D)	QUANTITY
Providing and laying			
I - Brick Bats including --			
do -- do -- E/L.			
CH- 0.200 to 0.600 Km	1 x 23.00 x 1/2(0.95 + 1.20) x 1/2(0.30 + 0.30) =	7.42 m ³	
	1 x 30.00 x 1/2(1.50 + 2.00) x 1/2(0.60 + 0.90) =	39.38	
	1 x 10.00 x 1/2(1.25 + 1.90) x 1/2(0.60 + 0.90) =	11.81	
	1 x 15.00 x 1/2(0.50 + 0.70) x 1/2(0.30 + 0.30) =	2.70	
Total			61.31 m ³


Junior Engineer
Babubarhi


Assistant Engineer
Babubarhi


Executive Engineer
RWD Work Division,
Jaynagar.