

Detailed Estimate for Restoration/Motorable of Road damaged during Flood'2020

Block : Babubarhi

Division : Jaynagar

Circle : Darbhanga

ABSTRACT OF COST


Name of Road : L055 Nabtoli L058 to Bela


Length of Road : 2.108 Km


Estd. Length : 24 Mtr.

Sl. NO.	Item of Works	Unit	Quantity	Rate	Amount (Rs.)
1-	Providing and filling brick bats in ditches including cost of brick bats and labour all complete job as per specification and direction of E/I.	CUM	45.56	1867.76	85095.00
				Total Rs.	85095.00
				Add GST @ 12%	10211.00
				Add L.Cess @ 1%	851.00
	Add Seignorage Fee		45.56 m ³ x Rs. 1063.00 x 10 %		4843.00
				Grand Total Rs.	101000.00

Say ₹ 1,01,000.00


Junior Engineer
Babubarhi


Assistant Engineer
Babubarhi


Executive Engineer
RWD Work Division,
Jaynagar.

कार्यपालक अभियन्ता गणकाठवि कार्य प्रमोडले भन्नाथपुरका पत्रांक 336 अगुा दिनांक 12.04.2021.
के द्वारा स्मृति में प्रविष्टन के आधार पर —

Post-recto T/A for Rs 1,01,000 = 10 (Rupees one lakh one thousand) only.


Superintending Engineer

RWD, Works Circle, Darbhanga


12/04/2021

**Detailed Estimate for Restoration/Motorable of Road damaged
during Flood'2020**

Name of Road : L055 Nabtoli L058 to Bela

Length of Road : 2.108 KM

Estd. Length : 24 Mtr.

Block : Babubarhi

Division : Jaynagar

Circle : Darbhanga

S.N.	ITEM OF WORKS	MEASUREMENT (L x B x H/D)	QUANTITY
------	---------------	----------------------------	----------


1- Providing and laying
Brick Bats including --
do -- do -- E/L.


CH- 0.000 to 0.300 Km 1 x 6.00 x ½(3.75 + 4.50) x ½(0.60 + 0.90) = 18.56 m³ ✓

1 x 18.00 x ½(1.50 + 2.50) x ½(0.60 + 0.90) = 27.00 ✓

Total 45.56 m³ ✓


16/11/20
**Junior Engineer
Babubarhi**


**Assistant Engineer
Babubarhi**


15/11/20
**Executive Engineer
RWD Work Division,
Jaynagar.**